



भारतीयविमानपत्तनप्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सं./Ref. No. AAI/HYD/ENGG (E)/CW-07/2019-20/2242-7

दिनांक /Date: 18.02.2020

BY SPEED POST/E-MAIL

सेवा में/To,

**M/s. Swas & IT Private Limited,
#23,1st Floor,2 Cross, behind Hennur
Police Station, Babusa Payal, Kalyan
Nagar Post, Bangalore-43.**

कार्यकानाम/ Name of Work : Provision of Standby feeder cable to glidepath-27 at Begumpet Airport

स सं./Ref. 1. Bid Invitation No.2019_AAI_39850_1 Dated. 08.01.2020.

2. Your E-tender (Envelope-III -Financial bid) opened on 31.01.2020.

महोदय / Dear Sir(s),

1. Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 17,28,144/- (Rupees Seventeen Lakhs Twenty Eight Thousand One Hundred and Forty Four Only) excluding GST which is 24.58% below the estimated cost of Rs.22,91,457/- excluding GST.
2. The Asst. General Manager (Engg-E), AAI, Hyderabad Airport, Begumpet, shall be the Engineer-in-Charge of the work. You are requested to attend the office of the Asst. General Manager (Engg-E), AAI, Begumpet Airport, Hyderabad - 500 016 by 27.02.2020 to sign and complete contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp papers shall be borne by you.
3. The earnest money amount of Rs.45830/- (Rupees Forty Five Thousand Eight Hundred and Thirty Only) received along with your tender vide DD No: 035898 Dated : 17.01.2020 of Axis Bank has been converted as part of security deposit as per the clauses of the contract clause No.1A of contract document. Please deposit Rs.1,26,984.00- (Rupees One Lakh Twenty Six Thousand Nine Hundred and Eighty Four only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from yours running bills as per condition of contract document
4. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules there of Central and State Governments.

Contd.,

*Recd
Chd*

*ch-m
18/2/2020
Acmm*



भारतीयविमानपत्तनप्राधिकरण

AIRPORTS AUTHORITY OF INDIA

5. You are also directed to contact Asst. General Manager (Engg-Elect), AAI, Begumpet Airport, Hyderabad – 500 016 immediately who will arrange to hand over the site to you.
6. Please note that the time allowed for carrying out the work shall be 03(Three) months and same shall be reckoned from 27.02.2020.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

अनुलग्नक/Encl: Schedule of Quantities

सहायक महाप्रबंधक-इंजी (वि)
Asst. General Manager-Engg. (Elect.)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
महदीन/Your's Faithfully
हैदराबाद-500 016.
Hyderabad-500 016

सं.महाप्रबंधक (अभि-वि)/Asst. General Manager (Engg-E),
अध्यक्ष के लिए एवं की ओर से/For & On Behalf of The Chairman,
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India,
भा वि प्रा, हैदराबाद हवाई अड्डा/AAI, Begumpet Airport
Hyderabad- 500 016

NOO:

में कॉपी /Copy to:-

1. The General Manager (CIC), AAI, Hyderabad Airport --- for information please.
2. The Jt. GM(E-E)/RHQ/SR/AAI/Chennai Airport, Chennai.
3. The Asst. General Manager (Fin), AAI, Begumpet Airport, Hyderabad – FC dated 17.02.2020.
4. The Dy. General Manager (Civil), AAI, Begumpet Airport, Hyderabad.
5. Manager (Engg-E)-II AAI, Begumpet Airport, Hyderabad.
6. Concerned File.
7. The Asst. Labour Commissioner (Central), AT 1 Campus, Vidyanagar Hyderabad-500007.
8. The Jt. GM (CNS), AAI, Hyderabad Airport.

Validate

Item Rate BoQ

Tender Inviting Authority: Asst.General Manager(E-E), AAI, Begumpet Airport

Name of Work: Provision of standby feeder cable to glidepath-27 at Begumpet Airport.

Contract No: 2019_AAI_39850_1

Name of the Bidder/ Bidding Firm / Company :	SWAS AND IT PRIVATE LIMITED							
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST in Rs. P	TOTAL AMOUNT Excluding GST In Words
1	2	3	4	5	12	13	53	55
1	Supply of 3½ core x 240 mm2 XLPE insulated and PVC sheathed Aluminium conductor armoured power cable of 1.1KV grade confirming to relevant IS 1554 / IS 7098 with upto date amondments etc, as required.	Item No 1	1500	Meter	INR	695.00	1042500.00	INR Ten Lakh Forty Two Thousand Five Hundred Only
2	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. a) 120 mm dia (OD-120 mm & ID-103 mm nominal)	Item No 2	800	Meter	INR	189.00	151200.00	INR One Lakh Fifty One Thousand Two Hundred Only
3	Laying of one number PVC insulated and PVC sheathed I XLPE power cable of 1.1 kV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. A) Above 185 sq. mm and upto 400 sq. mm.	Item No 3	24	Meter	INR	389.00	9336.00	INR Nine Thousand Three Hundred & Thirty Six Only
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size in the existing RCC/ HUME/ METAL/DWC/HDPE pipe as required. a) Above 185 sq. mm and upto 400 sq. mm.	Item No 4	956	Meter	INR	108.00	103248.00	INR One Lakh Three Thousand Two Hundred & Forty Eight Only
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size in the existing masonry open duct as required. a) Above 185 sq. mm and upto 400 sq. mm.	Item No 5	310	Meter	INR	132.00	40920.00	INR Forty Thousand Nine Hundred & Twenty Only
6	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. a) Above 185 sq. mm and upto 400 sq. mm. (clamped with 40x3mm MS flat clamp)	Item No 6	20	Meter	INR	126.00	2520.00	INR Two Thousand Five Hundred & Twenty Only
7	Providing, laying and fixing following dia G.I pipe (medium class) in ground complete with G.I fittings including trenching (75 cm deep) and re-filling etc. as required. a) 100 mm dia	Item No 7	56	Meter	INR	625.00	35000.00	INR Thirty Five Thousand Only
8	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. a) 3.5 X 240 sq. mm	Item No 8	4	Set	INR	4680.00	18720.00	INR Eighteen Thousand Seven Hundred & Twenty Only
9	Supplying and Making end termination with brass compression gland and aluminium lugs for following PVC insulated and PVC sheathed / XLPE insulated 1.1KV grade cables as required. a) 3.5 Core x 240 Sq. mm	Item No 9	2	Set	INR	580.00	1160.00	INR One Thousand One Hundred & Sixty Only
10	Excavation of the cable trenches in hard rock not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	Item No 10	20	Cum	INR	378.00	7560.00	INR Seven Thousand Five Hundred & Sixty Only
11	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) in foundation of pump, DG set etc including form work etc as required.	Item No 11	10	Cum	INR	4780.00	47800.00	INR Forty Seven Thousand Eight Hundred Only
12	Supplying and fixing 200A, Offload Changeover Switch in sheet enclosure, 4P, 415 volts, on surface/recess, complete and powder painted including earthing etc. as required.	Item No 12	1	Job	INR	9780.00	9780.00	INR Nine Thousand Seven Hundred & Eighty Only

Ch. M
18/2/2020
Aerms

13	Supply, Installation, Testing and Commissioning of Three phase Surge protection (MOV, plug in type) capable with Neutral Earth of carrying nominal discharge of 100KA (block MOV), 8/20 micro second surge, protection level of 1.5KV in IP55 grade enclosure, complete with suitable safety circuit breaker, base interconnection with copper cable, end terminations etc., as per specifications enclosed (First stage protection to be provided at power entry point) Make : Tercel	Item No 13	1	Job	INR	84340.00	84340.00	INR Eighty Four Thousand Three Hundred & Forty Only
14	Providing of earth pits material using ISOGEL earth enhanced compound of 20kgs. ISOROD advanced chemical earth rod made with k type copper tube of 2.5" dia., 8fts. Long, 1.6mm thick installed vertically or horizontally as per the site conditions complete with flanges bends top cover heavy duty plastic inspection chamber including excavation and refilling etc as required. Make: Tercel.	Item No 14	1	Job	INR	38920.00	38920.00	INR Thirty Eight Thousand Nine Hundred & Twenty Only
15	Providing and fixing of copper tape/strip of size 25x3mm on surface/existing pipe for loop earthing for site earthing and bonding etc., as required in 40mm dia GI pipe i/c supply and laying as per site requirement.	Item No 15	15	Mtrs	INR	716.00	10740.00	INR Ten Thousand Seven Hundred & Forty Only
16	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in the existing cable trench but excluding sand cushioning and protective covering etc. , complete as required. a) 75 mm dia (For OFC Cable)	Item No 16	1000	Mtrs	INR	62.00	62000.00	INR Sixty Two Thousand Only
17	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC/HDPE pipe as required. a) Upto 35 sq. mm (for OFC Cable)	Item No 17	1000	Mtrs	INR	52.00	52000.00	INR Fifty Two Thousand Only
18	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct including zip ties etc. , as required. a) Upto 35 sq. mm (for OFC Cable)	Item No 18	200	Mtrs	INR	52.00	10400.00	INR Ten Thousand Four Hundred Only
Total in Figures							1728144.00	INR Seventeen Lakh Twenty Eight Thousand One Hundred &
Quoted Rate in Words		INR Seventeen Lakh Twenty Eight Thousand One Hundred & Forty Four Only						

Ch. VM 18/09/2020
AcmmG

Signature Not Verified

Digitally signed by CHINTALA VENKATESWARA RAO
Date: 2020.09.04 15:57:35 IST
Location: eProcurement System for Central PSUs

