



संदर्भ सं.: भाविप्रा/पक्षे/समप्र (इंजी-वि)/एनडीबी/दीव /सीडब्लू-02/2019-20/478
Ref.No : AAI/WR/AGM (E-E)/NDB/DIU/CW-02/2019-20/

दिनांक: 25.02.2020

Date: 25.02.2020

सेवा में/ To,

मेसर्स सेंटर टेप इंजीनियरिंग M/s. Centre-Tap Engineering

30 कामेश्वर ट्विंस, 30 Kameshwar Twins

बी/एच श्रेयास स्कूल B/H Shreyas School

अम्बावड़ी, अहमदाबाद -15 Ambawadi, Ahmedabad -15

कार्य का नाम: रि-इन्स्टालेशन ऑफ एनडीबी अट दीव एअरपोर्ट, दीव. उपशीर्ष: इलेक्ट्रिकल कार्य.

Name of Work: Re-installation of NDB at Diu Airport, Diu. SH: Electrical Works.

संदर्भ: 1) आपकी ई-निविदा नं. 2020_AAI_40003 दिनांक 12.02.2020 को खोला गया।

1) Your e-tender id. 2020_AAI_40003 opened on Dated 12.02.2020.

महोदय, / Dear Sir(s),

- उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है, आपके द्वारा बताए गये मद मूल्यों पर आपकी ई-निविदा राशि कुल **रु. 58,05,255.00 (रुपए अठ्ठावन लाख पाँच हजार दो सौ पचपन मात्र) + जीएसटी** है, जो कि ई-निविदा की उचितलागत राशि रु. 69,96,228/- से **17.02% नीचे** है। एजन्सी द्वारा वैध टैक्स इन्वाइस प्रस्तुत करने पर जीएसटी अदा किया जाएगा। दीव के लिए जीएसटी क्र. GSTIN:- 25AAACA6412D1ZC है।
Your e-tender for the work mentioned above is hereby accepted on behalf of The Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 58,05,255.00 (Rupees Fifty Eight Lakh Five Thousand Two Hundred Fifty Five only) + GST**, which is **17.02% Below** the Estimated cost of Rs. 69,96,228.00. GST will be paid against valid Tax invoice from the agency. For Diu state AAI GST no. is GSTIN: 25AAACA6412D1ZC
- सहा. महा. प्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, विलेपार्ले (पूर्व), मुंबई-400099, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आपकी ओर से एक विश्वसनीय प्रतिनिधी प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक **06.03.2020** तक सहा. महा. प्रबंधक (इंजी-विद्युत), भाविप्रा, परिचालन कार्यालय भवन, न्यु एअरपोर्ट कालोनी, विलेपार्ले (पूर्व), मुंबई-400099 के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करें। ठेके का करारनामा रु.100/- के नॉनजुडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।
Asst. Gen. Manager (Engg-Elect), RHQ (WR), Vile Parle (E), Mumbai - 400 099 shall be the Engineer-In-Charge of this work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office to the Asst. Gen. Manager (Engg-Elect), ,RHQ (WR), Operational office building, New Airport Colony, Vile Parle (E), Mumbai-400 099 by **06.03.2020** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/-** and the cost of the stamp paper shall be borne by you.
- आपकी निविदा के साथ प्राप्त ई.एम.डी. रु. 1,39,925.00 (रुपए एक लाख उन्तालीस हजार नौ सौ पच्चीस मात्र) राशि निविदा ठेका दस्तावेज के (संविदाकी सामान्य शर्तों के संविदा के नियम 1A) के अनुसार प्रतिभूति राशि में तब्दिल कर दिया गया। कृपया रु. 4,40,601.00 (रुपये चार लाख चालीस हजार छः सौ एक मात्र) प्रतिभूति जमा के रुप में यह पत्र जारी करने के तारीख बाद 10 दिन के अंदर जमा किजिये। जमा करने की असफलता में वह राशि बिल से ठेके की शर्तों के अनुसार काट दी जायेगी।
The earnest money amount of **Rs. 1,39,925.00 (Rupees One lakh Thirty Nine Thousand Nine hundred Twenty Five only)** received along with your e-tender will be treated as part of security deposit as per General condition of contract (GCC) clause No. 1A of tender document. Please deposit **Rs. 4,40,601.00 (Rupees Four**

पृष्ठ 3

Lakh Forty Thousand Six Hundred One only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your bill as per contract conditions.

4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम (नियम तथा उन्मुलन) 1971 के केन्द्रीय नियम श्रम नियम (नियमन तथा उन्मुलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।

You are requested to comply with provision of contract labour (Regulation and Abolition Act 1970 and contract labour Regulation & Abolition) Central rule 1971 and minimum wages Act & rules thereof central and state Govt.

5. आपको यह निर्देश दिया जाता है कि आप प्रबंधक (इंजी-विद्युत), दीव हवाईअड्डा से संपर्क करें जो आपको साईट सौंपने की व्यवस्था करेंगे।

You are directed to contact Manager (E-E), Diu Airport immediately who will arrange to handover the site.

6. कृपया नोट कर लें कि काम करने का अनुमानित समय 03 (तीन) माह है जोकि इस पत्र के जारी होने के 10 वे दिन से गिना जाएगा। Please note that the time allowed for carrying out the complete work is **Seven (07) months**, which shall be reckoned **from 10th day of issue of this letter**.

7. इस ठेके के संबंध में आगे का कोईभी पत्राचार सहा. महा. प्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, एकीकृत प्रचालन कार्यालय भवन, विलेपार्ले (पुर्व), मुंबई-400099 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to Asst. Gen. Manager (Engg-Elect), RHQ (WR), Integrated Operational office building, Vile Parle (E), Mumbai - 400099.

8. कृपया पावती भेजें तथा इस आदेश की दोहरी प्रति आपके हस्ताक्षर के पश्चात इस कार्यालय में भेजें जो कि स्वीकृती टोकन समझा जाएगा। Please acknowledge the receipt and return the duplicate copy of this order enclosed herewith after signing to the undersigned as a token of acceptance.

यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जायेगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

धन्यवाद/ Thanking You,

Encl: 1. SOQ

भवदीय / Yours faithfully,



(सी. एस. शेवारे)/(C.S. Sheware)

सहा. महा. प्रबंधक (इंजी-विद्युत),

Asst. Gen. Manager (Engg-Elect),

भा. वि. प्रा., क्षे. मु., मुम्बई

AAI, RHQ-WR, Mumbai

कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,

For and on behalf of Chairman, Airports Authority of India

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority : AGM(EE)

Name of Work : Reinstallation of NDB at Diu Airport. SH : Electrical Works

Contract No : 2020_AAI_40003_1

Name of the Bidder/ Bidding Firm / Company :	Centre Tap Engineering					
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of following sizes of XLPE insulated PVC sheathed, armoured, aluminium conductor cable of 1.1KV grade as per IS 7098: 1988 part-I as amended up to date complete etc., as required. 3.5 X 185 Sq.mm	6000	Meter	500.00	3000000.00	INR Thirty Lakh Only
2	Supplying and laying of 110 mm OD HDPE Pipe of PE 63 PN 6 ISI Marked along with all accessories like socket, bend etc., confirming to IS 4984 complete with fitting and cutting, jointing etc., direct in ground (0.75 mtr below the ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., as required.	5600	Meter	200.00	1120000.00	INR Eleven Lakh Twenty Thousand Only
3	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 X 185 Sq.mm	10	Each	4200.00	42000.00	INR Forty Two Thousand Only
4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated PVC sheathed / XLPE Aluminium conductor cable of 1.1 kV grade as required. 3.5 X 185 SQ.MM	4	Each	850.00	3400.00	INR Three Thousand Four Hundred Only


NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe/HDPE pipe as required. Above 95 sq. mm and upto 185 sq. mm	5600	Meter	170.00	952000.00	INR Nine Lakh Fifty Two Thousand Only
6	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Above 95 sq. mm and upto 185 sq. mm (clamped with 25x3mm MS flat clamp)	400	Meter	130.00	52000.00	INR Fifty Two Thousand Only
7	Construction and Supply of Pre-Cast RCC Manhole Chamber of Internal Dimension 1MX1MX1M (External 1.2MX1.2MX1.2M) with CC of 1:2:4 of thickness 100mm with Square Top Cover of 600X600mm size with L angle reinforced at all side of top and bottom of cover, lifting hook including finishing with Cement Coat as required.	10	Job	11500.00	115000.00	INR One Lakh Fifteen Thousand Only
8	Supply of LED Baten surface/pendant mounted Light fixture i/c supply of LED tube of not less than 1900 Lumens with Lumen Efficacy of Minimum 95 Lumens/Watt made of CRCA sheet steel / aluminium housing along with all suitable fixing accessories, having IP20 Protection & colour temperature range 5500-6500k, prewired etc. complete suitable for operation on single phase 230V, 50Hz, AC supply etc as required	10	Each	1700.00	17000.00	INR Seventeen Thousand Only
9	Supply of LED Street Light fixture of not less than 2375 Lumens with Lumen Efficacy of Minimum 95 Lumens/Watt made of Pressure Die Cast aluminium housing along with all suitable fixing accessories, having IP65 Protection & colour temperature range 5500-6500k, prewired etc. complete suitable for operation on single phase 230V, 50Hz, AC supply etc as required.	4	Each	6000.00	24000.00	INR Twenty Four Thousand Only
10	Supply of 1200 mm sweep, 5 star electrical ceiling fan without regulator complete with down rod, canopies, ball bearing, motor, blades, capacitor etc. and suitable for use on 230 volts, 50 Hz, single phase, A.C. supply as required.	2	Each	2500.00	5000.00	INR Five Thousand Only
11	Supply of 300 mm exhaust fan including louvers and all accessories suitable for single phase, 230 V 50 Hz, A.C. Supply etc. Complete as required	1	Each	2500.00	2500.00	INR Two Thousand Five Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
12	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable on surface UPVC mini trunking, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	20	Each	40.00	800.00	INR Eight Hundred Only
13	Wiring for light/ power plug wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface UPVC mini trunking etc. as required.					
13.01	2 x 1.5 sqmm + 1 x 1.5 sqmm earth wire	30	Meter	40.00	1200.00	INR One Thousand Two Hundred Only
13.02	2 x 2.5 sqmm + 1 x 2.5 sqmm earth wire	30	Meter	40.00	1200.00	INR One Thousand Two Hundred Only
13.03	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	50	Meter	85.00	4250.00	INR Four Thousand Two Hundred & Fifty Only
14	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required	10	Each	850.00	8500.00	INR Eight Thousand Five Hundred Only
15	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required	5	Each	600.00	3000.00	INR Three Thousand Only
16	Supplying and fixing 20 Amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 16/25 amps, 300 mA, RCCB in sheet steel enclosure, on surface or in recess, with metal cover for the socket out let and complete with connections, testing and commissioning etc, as required.	2	Each	3350.00	6700.00	INR Six Thousand Seven Hundred Only
17	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 12 way Double door	3	Each	2000.00	6000.00	INR Six Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
18	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 125 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required. (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.)	1	Each	850.00	850.00	INR Eight Hundred & Fifty Only
19	Supplying and fixing of following rating, 240 / 415 volts, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
19.01	6 amps to 32 amps SP MCB 'C' curve	24	Each	170.00	4080.00	INR Four Thousand & Eighty Only
19.02	6 amps to 32 amps SPN MCB 'C' curve	3	Each	600.00	1800.00	INR One Thousand Eight Hundred Only
19.03	32 amps TPN MCB 'C' curve	1	Each	1700.00	1700.00	INR One Thousand Seven Hundred Only
19.04	32 amps TP MCB 'C' curve	3	Each	1200.00	3600.00	INR Three Thousand Six Hundred Only
20	Supplying and fixing 2M step type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2	Each	700.00	1400.00	INR One Thousand Four Hundred Only
21	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	5	Each	30.00	150.00	INR One Hundred & Fifty Only
22	Installation, testing and commissioning of pre-wired LED fitting of all types, complete with all accessories and tube etc. directly on ceiling/ wall/false ceiling, including connection with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required	10	Each	420.00	4200.00	INR Four Thousand Two Hundred Only
23	Installation, testing and commissioning of prewired LED street light integral luminaire complete with all accessories directly on the building/wall including providing & fixing street light bracket of suitable size made out of "B" class GI pipe along with GI clamp/bolt/nuts etc., as required	4	Each	1250.00	5000.00	INR Five Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
24	Installation, testing and commissioning of ceiling fan, including wiring in the existing down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earth connection etc. as required.	2	Each	850.00	1700.00	INR One Thousand Seven Hundred Only
25	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. Upto 450 mm sweep	1	Each	850.00	850.00	INR Eight Hundred & Fifty Only
26	Dismantling and Re-Installation, Testing & commissioning of A/C units of 1.5 TR as available with AAI site which includes mounting of indoor & outdoor unit with MS stand at their respective location alongwith laying of refrigerant pipeline with insulation & flexible PVC covering pipe, connecting both the units, leak testing of entire system, connecting both indoor and outdoor units with three/four core 2.5 sq mm PVC insulated flexible copper cable supplied with the unit, topup of refrigerant (if required), minor civil repairing work as per site requirement complete as required.	2	Job	4200.00	8400.00	INR Eight Thousand Four Hundred Only
27	Providing & fixing of Refrigerant copper piping with insulation & other accessories in all respect for connection between Indoor and Outdoor unit suitable for R410A (Supply and return) for Split type Airconditioners as required. (Measurement of 1 run/mtr will include both supply & return Cu.Pipe)	10	Meter	420.00	4200.00	INR Four Thousand Two Hundred Only
28	Providing and fixing of suitable minimum 15 mm PVC drain pipe for the respective units, clamping on surface, sealing the joints including making of opening and repairing of wall as per site condition.	5	Meter	85.00	425.00	INR Four Hundred & Twenty Five Only
29	Supply & fixing of 4 C x 4 sqmm. copper conductor multi core cable between indoor and outdoor unit complete as required.	10	Meter	170.00	1700.00	INR One Thousand Seven Hundred Only
30	Supply, installation, testing and commissioning of 100 Amps, 4-pole, Automatic Transfer Switch with controller and having Automatic/Manual operation including enclosure complete as required suitable for operation on 3-phase, 415V, 50Hz AC Supply.	1	Each	25000.00	25000.00	INR Twenty Five Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
31	SITC of MV Switch Board Indoor Type Panel made out of 2mm Thick CRCA Sheet Steel, dust tight, vermin proof, Totally enclosed, cubicle type, floor mounting, free standing, suitable for operation at 433 V, 3 Phase, 4 Wire, 50 Hz, A.C. System complete with all accessories, interconnection, connection, earthing, painting, provided with bottom base channel etc., as required and comprising of the following: (a) Two Nos. of 160 A, 36 KA, 4P MCCB with Thermal Magnetic Based Releases including providing and fixing of electrical and mechanical inter locking facilities for INCOMERS with Resin Cast C.T. operated Digital Meter, ON/OFF/TRIP Indication Lamps and Phase Indication Lamps, as required. (b) Two No. of 63 A, 36 KA, 4P MCCB with Thermal Magnetic Based Releases as Outgoings, with ON/OFF/TRIP Indication Lamps as required. (c) Three Nos. of 63 A, 10 KA, DP MCB as Outgoings as required (d) Three Nos. of 32 A, 10 KA, DP MCB as Outgoings as required (e) 25% Space for future Spare Switches as Outgoings as required (f) One Set of 200 Amps Al. Bus Bars with at Par Neutral BUS BARS as required. (g) All accessories such as fuses, auxillary contactors, auxillary switches, etc. as required. ALL AS ABOVE Complete in all respect.	1	Each	125000.00	125000.00	INR One Lakh Twenty Five Thousand Only
32	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	2	Each	10000.00	20000.00	INR Twenty Thousand Only
33	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required	10	Meter	250.00	2500.00	INR Two Thousand Five Hundred Only
34	Providing and fixing 25mm x 5mm G.I strip in 40 mm dia. GI pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc.as required.	10	Meter	420.00	4200.00	INR Four Thousand Two Hundred Only




NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
35	SITC of 70 KA, 3 phase Surge diverter with neutral protection in IP55 grade powder coated metal enclosure with 63 Amps safety circuit breaker, interconnection with copper cables, end terminations etc. as required to be installed at the main switch board panel in parallel mode complete as required.	2	Each	8500.00	17000.00	INR Seventeen Thousand Only
36	SITC of 34L seamless storage cylinder duly filled with NOVEC 1230 or equivalent agent (approx. 19 Kg) complete with valve assembly, pressure gauge and pressure switch and other associated standard accessories.	1	Each	120000.00	120000.00	INR One Lakh Twenty Thousand Only
37	SITC of (a) control head suitable for operating electrically from fire detection and control panel with all accessories. (b) High pressure flexible rubber discharge hose with braided reinforcement. (c) Discharge nozzles designed to provide the proper flow and distribution of gas to flood hazard area at 180/360 degrees. (d) Gas discharge pressure switch to trip A.C., electrical equipment etc. All shall be as per OEM recommendation & standards.	1	Each	42000.00	42000.00	INR Forty Two Thousand Only
38	SITC of manual gas release station and Manual gas abort station having manual break glass push button type call points with auxiliary contacts, hammer gland etc. complete in all respect and shall be as per OEM recommendation & standards.	1	Each	1250.00	1250.00	INR One Thousand Two Hundred & Fifty Only
39	SITC of 4 cross zone Fire Alarm Gas release panel with built in time relay, auto/manual selector switch housed in a suitable 16 SWG M.S. Sheet panel. The control panel shall have the arrangement for Audio/ Visual indications by dual lamps LED's for fire and fault in each zone with lamp test facility. The panel shall be connected to smoke detectors. The control panel shall be working on standby power supply by 2x12 volts, 7 AH sealed maintenance free batteries complete with circuit wiring etc., as per IS :2189 and have provision for testing each circuit separately including resetting and shall be as per OEM recommendation & standards.	1	Set	25000.00	25000.00	INR Twenty Five Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
40	SITC of photo electric smoke detectors complete with base and mounting accessories.	5	Each	1700.00	8500.00	INR Eight Thousand Five Hundred Only
41	Providing & fixing seamless pipe complete with all fittings painting with one coat of red oxide and 2 coats of enamel paint, piping to be fixed on ceiling with MS suspended supports, clamps, anchor fasteners, cutting chases / holes in valve ceiling and making good the same as required for the following sizes:- a) 32mm All shall be as per OEM recommendation & standards.	6	Meter	850.00	5100.00	INR Five Thousand One Hundred Only
42	Supply of 2C x 1.5 sq.mm armoured, FRLS, Flexible, Multi strand, copper conductor cable and laying/fixing the same on ceiling/wall/false-ceiling/in pipe/trunking etc connection, testing and commissioning complete as required as per OEM.	40	Meter	85.00	3400.00	INR Three Thousand Four Hundred Only
43	Supply, installation, connection, testing and commissioning of Sounder/Hooter complete including base plate, box, necessary accessories etc. complete as required as per OEM.	1	Each	1700.00	1700.00	INR One Thousand Seven Hundred Only
Total in Figures					5805255.00	INR Fifty Eight Lakh Five Thousand Two Hundred & Fifty Five Only
Quoted Rate in Words		INR Fifty Eight Lakh Five Thousand Two Hundred & Fifty Five Only				

Signature Not Verified

Digitally signed by CHANDRASHEKHAR SHIVAJI SHEWARE
Date: 2020.02.27 16:58:51 IST
Location: eProcurement System for Central PSUs


25/04/2020
च. शि. शेवारे / C. S. SHEWARE
सहायक महाप्रबंधक (अभि.-वि.) / Asstt. General Manager (E-E)
भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, प. शे.
Airports Authority of India, RHQ, WR
मुंबई / Mumbai - 400 099.