

(पंजीकृत डाक)

संदर्भ: भा.वि.प्रा. / रापु. / अभि(सि) / स.म.प्र. / ए.एम.सी.-एन.आई.टी.बी. / 2020/1469-80 दिनांक:-22.05.2020

सेवा में,

मेसर्स राकेश कुमार सिंह,
संजीवन विला, डी-16,
गैलेक्सी रेसीडेंसी, अमलीडीह,
रायपुर (छ.ग.)-492006

To,

M/s Rakesh Kumar Singh,
Sajeevan Villa, D-16,
Galaxy Residency, Amlideh
Raipur (C.G.)-492006

विषय: स्वामी विवेकानन्द हवाई अड्डा, रायपुर में एन.आई.टी.बी. भवन में सिविल रख-रखाव कार्यों के लिए वार्षिक अनुबंध। (2020-22)
निविदा क्रमांक : 2020_AAI_40105_1

Sub: Annual Repair Maintenance Contract for Civil Work in NITB at S.V. Airport, Raipur (2020 - 22).

Tender ID: - 2020_AAI_40105_1

संदर्भ: आपकी ई-निविदा जो दिनांक 28.02.2020 को खोली गयी।

Ref: Your E-tender opened on 28.02.2020

महोदय/Sir,

1. उपरोक्त कार्य के लिए आपकी निविदा में आपके द्वारा उद्धरित प्रतिशत दर शेड्यूल ए (निविदा दस्तावेज के पेज क्रं. SOQ-2 पर उल्लेखित भुगतान पद्धति के अनुसार) पर 30.33 प्रतिशत नीचे है को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है। इस कार्य हेतु कुल रुपये 127.12 लाख का आबंटन है।

Your percentage rate tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at your quoted percentage rate of 30.33% below schedule-A (As per payment methodology mentioned at page SOQ-2 of tender document). The fund allotted for this work is Rs. 127.12 Lakhs.

2. आपसे अनुरोध है कि कृपया दिनांक 05.06.2020 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 05.06.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 2,54,240/- (रुपये दो लाख चौवन हजार दो सौ चालीस मात्र) को जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा। कृपया इस कार्यादेश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये 10,16,960/- (रुपये दस लाख

सोलह हजार नौ सौ साठ मात्र) इस कार्यालय में जमा कराये अन्यथा यह निविदा दस्तावेज के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. 2,54,240/- (Rupees Two Lakhs Fifty Five Thousand Two Hundred Forty Only) received along with your tender will be treated and converted as part of security deposit as per Clause no. 1A on Page GCC-16 of tender document. Please deposit Rs. 10,16,960/- (Rupees Ten Lakh Sixteen Thousand Nine Hundred Sixty Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page GCC-16 of tender document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर जी.सी.सी-50 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनिमय एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही ठेका श्रमिक (विनिमय एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनिमय) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनिमय, अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 तथा केन्द्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 50 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई.एस.आई. अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ई.एस.आई. पंजीकरण काम के वास्तविक समापन तक वैध रहें।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप प्रबंधक (इंजी-सि), स्वामी विवेकानंद हवाई अड्डा, रायपुर से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg. - Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 24 (चौबीस) महीने होगा और इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 24 (Twenty Four) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

भवदीय,

संलग्न: अनुसूची-अ

22/05/2020

(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)

भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

मूलप्रति में नहीं

प्रतिलिपि:

1. क्षेत्रीय कार्यापालक निदेशक, पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
2. महाप्रबंधक (अभि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
4. उपमहाप्रबंधक (अभि-सि), भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
5. सहायक महाप्रबंधक (सर्तकता), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
6. सहायक श्रम आयुक्त (सी), डी-6, आदर्श सोसाइटी, सेक्टर-1, अवंती विहार, रायपुर।
7. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक-डी, स्कीम नं.-32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.)-492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
2. सहायक महाप्रबंधक (अभि-वि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
3. वरिष्ठ प्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
4. प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
5. कार्यालय प्रति।

22/05/2020

(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)

RC
Kamish
22-5-2020

Schedule-A

Name of Work: Annual Repair Maintenance Contract for Civil Work in NITB at S.V. Airport, Raipur (2020 – 22).

Item No.	Description of Work / Item(s)	Units	Rate
(I)	Schedule "A"(Part-I) (As per DSR'2016 with upto date correction slips) available in the office of Senior Manager (Engg.-Civil)		
	(Followed the sub heads of DSR 2016 from 01 to 26)		
(II)	Schedule "A" (Part - II) (Rate derived as per prevailing market rates)		
27	Additional Misc. Items :-		
27.1	Supplying and fixing Plastic Speed Bump of size 500x400x50 mm made up of "STUDLY" plastic studded with reflectors on both side, and fixed with 4 no. 12 mm dia 150 mm long bolt as per manufacturer specification, direction and satisfaction of Engineer-in-Charge.	Metre	2488.85
27.2	Brick work with fly ash bricks (Min compressive strength 35 kg / sq cm) in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	3456.70
27.3	Brick work with fly ash bricks (Min compressive strength 35 kg / sq cm) above plinth upto floor V level: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	4756.65
27.4	Half brick masonry with fly ash bricks (Min compressive strength 35 kg / sq cm) above plinth upto floor V level: A) Cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm	645.45
27.5	Supplying Manpower for day to day maintenance jobs, (The contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future by State/Central Govt. during the entire period of the contract. The contractor will be responsible to supervise the work assigned to labours and has to supply T & P as per the requirement. (quoted percentage above /below will not be applicable on this item, the prevailing minimum wages should be paid under this item.)		
a)	Skilled	Each	781.30
b)	Semi-skilled	Each	667.50
c)	Unskilled	Each	590.05
27.6	Supplying and fixing G.I. fittings such as Tees, Elbows, Sockets, Nipple etc. of all size including dismantling old one and replacing with new one as per direction and satisfaction of Engineer-in-charge.		
a)	15 mm to 20 mm dia	each	79.15

b)	25 mm to 32 mm dia	each	136.90
c)	40 mm to 50 mm dia	each	282.40
d)	65 mm to 80 mm dia	each	408.45
27.7	Supplying and fixing of brass spindles (heavy) of all size including dismantling old one and replacing with new one in pillar cock, bib cock etc. as directed by Engineer-in-charge.	each	303.80
27.8	Providing and fixing C.P. brass pillar cock of approved make etc. complete as per satisfaction of Engineer-In-Charge a) 15 mm nominal bore	each	993.10
27.9	Providing and fixing Gunmetal gate valve of approved quality with C.I. Wheel of make Neta or equivalent (screwed end) as per direction and satisfaction of Engineer-in-Charge a) 15 mm nominal bore	each	375.90
27.10	Cleaning of choked/blocked rain water pipe, soil waste pipe, vent pipe, manhole, sewerage pipe, gully traps, EWC, IWC, wash basin, kitchen sink, bottle traps, floor traps, house drain, storm water drain, etc. of any diameter and sizes including removal of garbage/malba for all leads and lifts within Airport premises etc. all complete as per direction and satisfaction of Engineer-in-Charge.		
a)	Manhole including connected sewerage pipes upto the next manhole.	each	573.45
b)	Gully traps/EWC/IWC/wash basins including connected soil waste/sewerage pipe upto the nearest manhole.	each	99.90
c)	Storm water drain for drain width upto 0.50 mtr	metre	22.95
d)	Storm water drain for drain width above 0.50 mtr	metre	36.30
e)	Rain water pipe / soil waste and vent pipe.	Mtr	15.10
f)	EWC/IWC/basin including connected traps and soil waste pipe upto the nearest opening point in the soil waste pipe.	Each	10.35
g)	House drain (open)	Mtr	18.90
h)	House drain (covered)	Mtr	64.40
27.11	Providing and fixing sun control film (Garware or equivalent) after thorough cleaning of glass surface i/c removal of existing sun control film wherever required etc. all complete as per direction and satisfaction of Engineer-in-Charge.	sqm	574.95
27.12	Providing and placing glass of make saint gobian with machine polished edge for table top complete as per direction of E I C		
a)	12mm thick Bevelled edge	sqm	1693.60
b)	8mm thick bevelled edge	sqm	1479.40
27.13	Replacement of worn out Neoprene beading/gasket with new one in existing aluminium partitions, doors and windows i/c removing the old one and fixing the new one etc. all complete as per direction and satisfaction of E. I. C	metre	24.30

27.14	Providing and Fixing aluminium sheet (0.30 mm) on doors/windows shutters with steel screws, Fevicol etc. and sealing the edges with special structural quality Silicone adhesive sealant layer manufactured to standards like wacker, Dow Corning or equivalent etc. all complete as per direction and satisfaction of Engineer-in-charge.	sqm	834.75
27.15	Providing & fixing of 3M Radium computer cut letters on existing information / notice board etc. complete as per direction of Engineer-in-charge	sqm	2304.70
27.16	Printing on 3M vinyl sheet and pasting on existing notice board/signage board i/c necessary arrangements etc. complete as per the direction of Engineer-in-charge	sqm	647.10
27.17	Providing & fixing signages board printed on 3 M Vinyl sheet and pasting over 3 mm thick PVC/Acrylic sheet i/c necessary arrangements complete as per direction and satisfaction of Engg-in charge. (Frame work if required to be paid separately)	sqm	2190.20
27.18	Lettering with synthetic enamel paint of approved brand and manufacture in appropriate width, colour, arrangement etc. complete as per direction of Engineer-in-Charge.	per letter per cm height	3.45
27.19	Repairing aluminium door/windows shutters & frames including removing, cutting, realigning and refixing i/c fixing hinges, screw etc. wherever required all complete as per direction and satisfaction of Engineer-in-charge.	each	458.70
27.20	Repairing of hydraulic floor spring/door closer in existing aluminium/wooden door.	Each	189.45
27.21	Repairing and refixing of wooden door/window shutter including removal of shutter from chowkhat, cutting wherever required and providing butt hinges on other side of frame of shutter wherever required all complete as per direction and satisfaction of Engineer-in-charge. (cost of hinges shall be paid extra).	Each	463.70
27.22	Providing and fixing stainless steel jali (with hole or without hole) over floor trap/ nahani trap etc. as per direction & satisfaction of Engineer-in-Charge.		
a)	100 mm dia	each	47.50
b)	125 mm dia	each	57.45
27.23	Providing and fixing mosquito proof NETLON over frames of window, ventilators etc. fixing arrangement like stappling well crow strip over wooden frames including stitching other half of welcrow on netlon jali fit to size complete as directed by Engineer-in-Charge.	Sqm	769.75

27.24	Attending various day to day complaints and rectifying the defects/cause of complaints by deploying labour (unskilled, semi-skilled & skilled as and when required) with necessary the T & P but without changing replacing the fitting / fixtures etc. all complete as per direction and satisfaction of Engineer-in-Charge (the minor stores like screws for tightening hinges etc. and washers, thread, safeda etc. to prevent the leakage in bib cocks, stop cocks, pillar cocks, stop cocks etc., is included in the rate)	per month	17243.00
27.25	Credit for taking away following dismantle materials from the site out side Airport premises at own transportation cost complete. (Note:- Rate shall be treated as minus rate)		
a)	C. P. brass items like pillar cock, bib cock, sliding door bolt, handles and other similar items.	Kg.	27.00
b)	M.S. items like pipe, angles, channels, handles, tower bolt, and other similar items.	Kg.	17.00
c)	Aluminium item like handles, section, doors, fittings and other similar items.	Kg.	82.00
d)	G.I. fittings items like union, socket, bend pipe and other similar items.	Kg.	27.00
e)	G.I. sheet and frofile sheet items.	Kg.	12.00
f)	All type of dismantle wooden items like frame, shutters, window, doors and similar items	Kg.	7.00
g)	All types of PVC items	Kg.	27.00
27.26	Providing and fixing Plywood of make Regal/Century/Oxford or equivalent with screws etc to the existing frame work in the ceiling/openings (door, windows etc) to close the openings etc all complete as per direction and satisfaction of the EIC.		
a)	6 mm thick plywood	Sqm	567.20
b)	12 mm thick plywood	Sqm	920.75
c)	18 mm thick plywood	Sqm	1274.20
d)	19mm thcik commercial ply	Sqm	979.65
27.27	Providing and fixing magnetic ball catcher in wooden cupboards/shelves/drawers etc. complete and as per the direction of Engineer-In-Charge.	Each	112.80
27.28	Providing and fixing E-board (cement based) with screws etc fixed to the existing frame work in the ceiling/openings (door, windows etc) to close the openings etc all complete as per direction and satisfaction by the EIC.		
a)	6 mm thick	Sqm	449.40
b)	10 mm thick	Sqm	626.15
c)	12 mm thick	Sqm	802.90
27.29	Providing and fixing roller blinds of make Vista or equivalent of required size, shade and colour etc. including installation & operating mechanism complete at site as per direction of Engineer-in-charge.	Sqm	4502.15

27.3	Providing and fixing 100 mm wide vertical blinds of make-Marvel, Vista or equivalent i/c operating mechanism etc complete in all respect as per direction of Engineer-in-charge.	Sqm	1462.10
27.31	Application of silicon sealant of make DOWCORNING (all weather resistant) or equivalent for filling of gaps/joints (Minimum 5mm wide & 5mm deep) in aluminium/wooden/M.S. structures as well as repairing of cracks & leakages etc all complete as per direction and satisfaction of EIC.	metre	72.30
	GLASS ITEMS:		
27.32	Providing and fixing glass 17.52mm thick laminated glass (8mm thick toughened glass + 1.52mm P.V.B. lamination + 8 mm thick toughened clear glass) in existing glazing structures of any height including scaffolding and removing of old broken glass all complete as per direction of Engineer-in-charge. (No Extra payment will be made for dismantalling & Scaffolding shall be paid extra as per actual)	Sqm	7615.55
27.33	Providing and fixing double glazed hermetically sealed glazing in existing glazing system of all heights with 6 mm thick toughened outer glass, having 12 mm air gap, and 6mm thick clear toughned inner glass etc. complete in all respect as per direction of Engineer-in-charge. (Scaffolding shall be paid extra as per actual)	Sqm	4664.80
27.34	Providing and fixing 12 mm thick toughened clear float glass of approved make for sensor door complete in all respect as per direction of Engineer-incharge. (Scaffolding shall be paid extra as per actual)	Sqm	3686.00
27.35	Providing and fixing 19 mm thick toughened clear float glass of required size and shape and of approved make in Stainless steel railing (Ht. 900 from top of step) of Staircase complete in all respect as per direction of Engineer-incharge. (Scaffolding shall be paid extra as per actual)	Sqm	7766.75
27.36	Providing and fixing 10 mm thick clear float toughened glass glass of required size and shape and of approved make in frameless show window, The glass to be fixed in line and plumb with a minimum gap of 6 mm between glass to glass and filled with clear weather sealent of Dow Corning or approved equivalent. The gaps between both sides of channel and glass should be inserted with sealent. All the perimeter gaps between the channel and masonry / RCC/ stone shall also be sealed with clear weather sealant of Dow Corning or approved equivalent complete in all respect as per directions of Engineer-incharge. (Scaffolding shall be paid extra as per actual)	Sqm	2118.85

27.37	Providing and fixing of 12mm thick toughened clear glass of AIS make or equivalent in existing spider fitting frame all complete as per direction of E.I.C. (item includes the cost of cartage and shifting of glass in building anywhere. Nothing extra will be payable in this regard) (Scaffolding shall be paid extra as per actual)	Sqm	3837.10
27.38	Providing and laying glass flooring with 19mm thick safety (Toughened) glass of approved make over MS frame work including fixing the glass with structural sealant of approved manufacture as per directions of Engineer-in-charge. (Scaffolding shall be paid extra as per actual)	Sqm	8383.70
JAQUAR SANITARY & PLUMBING ITEMS:			
27.39	Providing and fixing flush valve dual flow 32 mm (codeFLV-1085) of Jaguar including wall plate or approved equivalent, water volume adjustment and flush pipe, complete as per directions of Engineer-in-charge.	Each	2542.85
27.4	Providing and fixing Piston/spindle for flush valve dual flow 32 mm (codeFLV-1085) of Jaguar including wall plate or approved equivalent, water volume adjustment and flush pipe, complete as per directions of Engineer-in-charge.	Each	2542.85
27.41	Providing and fixing 32 mm dia bottle trap eith internal partition (Code ALD-769) of Jaguar or approved equivalent and with 250 mm & 190 mm long wall conection pipe & wall flange for wash basin and urinals etc. complete in all respect as per directions of Engineer-in-Charge.	Each	1233.05
27.42	Providing and fixing C.P. Brass Long Body Bib Cock (JAQUAR Make CON -107KN) of approved quality all complete as per the directions of Engineer-in-charge.	Each	941.10
27.43	Providing and fixing in position CP Brass Robe hook including necessary S/S screws etc. complete (CAN 1191 N) Jaguar or approved equivalent complete as per the directions of Engineer-in-charge.	Each	342.10
27.44	Providing and fixing C.P. Angular stop cock of 15mm nominal bore JAQUAR make (Cat No. FLR5053 N) or equivelent etc. complete as per direction of Engineer-in-Charge.	Each	952.50
27.45	Providing and fixing in position Health faucet with 1m flexible tube and wall hook with all necessary accessories (code ALD-579) of Jaguar or approved equivalent complete as per directions of Engineer-in-charge.	Each	941.75
27.46	Providing and fixing 32mm size full thread with 80 mm height C.P. waste coupling JAQUAR make model no. ALD 705/ALD 709, all complete as per direction of Engineer-in-charge..	Each	519.70

27.47	Providing and fixing of Auto Closing Pillar Cock PRS-031 of JAQUAR or equivalent including dismantling old one etc. complete as per direction of Engineer-in-Charge.	Each	1522.20
27.48	Providing and fixing C.P.brass Two-way Bib Cock (15 mm) will wall flange etc. of JAQUAR make (Cat-FLR-5041 N) or APPROVED equivalent complete in all respect as per directions of Engineer-in-charge.	Each	1281.77
27.49	Providing and fixing first quality off white vitreous china wall hung WC with seat & cover off (Model No. SLS-WHT-0117/SLS-WHT-6951) of JAQUAR or approved equivalent complete in all respect as per direction of EIC.	Each	7554.10
27.5	Providing and fixing first quality off white vitreous china Oval undercounter Wash Basin (Model No. CNS-WHT-WB03/CNS-WHT-705) of JAQUAR or approved equivalent complete in all respect as per direction of EIC.	Each	2194.85
27.51	Providing and fixing first quality off white vitreous china Wash Basin (Model No. SLS-WHT-0611 & SLS-WHT-1505) of JAQUAR or approved equivalent complete in all respect as per direction of EIC.	Each	2519.45
27.52	Providing & Fixing first quality off white vitreous china Urinal without sensor in white (Model No. URS-WHT-13255) of JAQUAR complete in all respect as per direction of EIC.	Each	6026.00
27.53	Providing & Fixing Electronic Concealed Urinal Sensor DC (Model No.SNR-CHR-51077) of JAQUAR complete in all respect as per direction of EIC.	Each	10516.50
27.54	Supplying and fixing of Connector with cable of jaquar make (ZSN-CHR-071) for Automatic sensor urinals complete as per direction and satisfaction of Engg-in-charge	Each	1106.55
27.55	Supplying and fixing Battery of jaquar make (ZSN-CHR-056) for Automatic sensor urinals complete as per direction and satisfaction of Engg-in-charge	Each	1282.40
27.56	Supplying and fixing eye for urinal sensor of jaquar make (ZSN-CHR-055A) for Automatic sensor urinals complete as per direction and satisfaction of Engg-in-charge	Each	5971.05
27.57	Supplying and fixing AA/AAA size batteries of approved make or manufacture for urinal sensors asper direction and satisfaction of E-I-C.	Each	9.95
27.58	Maintenance of Metropole flush valve of Jaquar make for regular operation by rectifying the defects except replacement of parts etc. complete in all respect as per direction of EIC.	Each	995.55
DORMA AOYOMATIC DOOR PARTS AND OTHER FITTINGS:			

27.59	Providing & fixing Dorma or equivalent make BTS 75 floor spring for glass door i/c necessary fixing arrangements etc. complete as per the direction of EIC.	Each	14668.80
27.6	Providing & fixing SS TGDI H Pull handles - Grade: 316, TGDIH 350 X 25, SSS Total Length: 350mm, CTC: 250mm of Dorma make satin finish or equivalent on glass as per existing standard the satisfaction of EIC.	Each	5168.35
27.61	Providing & fixing SS C tube handle - Grade: 316, of required size of Dorma make satin finish or equivalent for glass doors as per satisfaction and direction of EIC.		
a)	a) 350x25 mm	Each	3157.55
b)	b) 300x22 mm	Each	2696.45
c)	c) 200x19 mm	Each	1891.85
27.62	Providing & fixing Universal glass door corner lock, US 10 Std of dorma make or equivalent on glass as per existing standard to the satisfaction of EIC.	Each	5407.10
27.63	Providing & fixing patch fitting PT Std Door top patch of Dorma make or equivalent for glass door as per existing standard to the satisfaction of EIC.	Each	3681.50
27.64	Providing & fixing patch fitting PT Std Door - bottom Patch dorma make or equivalent on glass door complete as per satisfaction of EIC.	Each	3681.50
27.65	Providing & fixing door sensor Eagle (1 Rada (New eagle 2) of dorma make or equivalent for sliding door i/c necessary fixing arrangement complete as per satisfaction of EIC.	Each	14621.80
27.66	Maintenance of Automatic Sensor Door of Dorma make for regular operation by rectifying the defects except replacement of parts etc. complete in all respect as per direction of EIC.	Each Per Month	1700.70
27.67	Providing & fixing 1250 mm glass clamping rail of dorma make or equivalent for glass door i/c necessary fixing arrangement complete as per satisfaction of EIC.	Set	10844.30
27.68	Supplying and fixing SMPS of DORMA make for automatic sliding door i/c necessary fixing arrangements as per direction and satisfaction of E-I-C.	Each	14991.30
27.69	Supplying and fixing ES 200 big roller of DORMA make for automatic sliding door i/c necessary fixing arrangements as per direction and satisfaction of E-I-C.	Each	2050.60
27.7	Supplying and fixing five position programme switch of DORMA make for automatic sliding door i/c necessary fixing arrangements as per direction and satisfaction of E-I-C.	Each	2067.95

27.71	Supplying and fixing Module for DORMA make automatic sliding door i/c necessary fixing arrangements as per direction and satisfaction of E-I-C.	Each	32958.60
27.72	Supplying and fixing Encoder cable 450 mm for DORMA make automatic sliding door i/c necessary fixing arrangements as per direction and satisfaction of E-I-C.	Each	3369.20
27.73	Providing and fixing 16 mm thick & 60mm wide PERGO or equivalent laminated wooden skirting profile in approved pattern and colour for wooden flooring all complete as per direction of Engineer-in-charge.	Mtr.	221.45
27.74	Providing and Fixing 316 grade stainless steel V-series spider and FHB-M12 bolt assembly of DORMA-German/LISUS-Singapore including provision of solid threaded M.S. bush of suitable size, welded to M.S. pipe (to be paid separately) and SS 316 grade bolt to fasten spider with M.S. bush complete including all, to the satisfaction of the Engineer - in- charge for FRAMELESS GLASS INTERNAL PARTITIONS.		
a)	V1-1 ARM SPIDER WALL BRACKET (DORMA MAKE)	Each	4440.30
b)	V1-2 ARM SPIDER WALL BRACKET	Each	5089.10
	MISCELLANEOUS ITEM:		
27.75	Providing pest control services for honey control, outside NITB area with WHO approved chemicals and ISI specifications as per direction and satisfaction of Engineer in charge.	Job	497.75
27.76	Providing pest control services for Rodent controls in NITB inside and outside area with WHO approved chemicals and ISI specifications as per direction and satisfaction of Engineer in charge.	Job	1991.10
27.77	Providing pest control services forfogging for Mosquitos control in NITB inside and outside area with WHO approved chemicals and ISI specifications as per direction and satisfaction of Engineer in charge.	Job	3185.75
27.78	Supplying and Placing of Neel kamal make free litter swinging bin of 100 ltr capacity as per manufacturer specification, direction and satisfaction of E-I-C.	Each	1493.30
27.79	Supplying and placing of plastic/pvc make flower pot of size 450 mm dia in approved colour as per direction and satisfaction of E-I-C.	Each	547.55
27.8	Supplying and fixing Spring Post of size 80x750 mm made up of PVC, 3 no. Reflective band of size 75 mm pasted over it , Pole Base of 200 mm dia and fixed with 3 no. 12 mm dia 150 mm long bolt as per manufacturer specification, direction and satisfaction of E-I-C.	Each	1692.40

27.81	Supplying and fixing Plastic Speed Bump of size 250x350x50 mm made up of "STUDLY" plastic studded with reflectors on both side, and fixed with 4 no. 12 mm dia 150 mm long bolt as per manufacturer specification, direction and satisfaction of E-I-C.	Mtr.	2222.80
27.82	Providing administrative and Technical services for office work i/c operating computer, printer and photocopier and handling day to day services etc. for the Senior official in one general shifts by deploying required number of skilled/unskilled manpower as per requirement and as directed by Engineer in charge. (Minimum 1 skilled and 1 unskilled manpower to be deployed to execute the item)	Each	35360.70
27.83	Providing Operational services for all toilets, bathrooms, urinals, Kitchens like clearing the chocking of EWC, IWC, Water-cooler & Wash-basin and its waste connecting pipes of Terminal building in two operational shifts by deploying required number of skilled manpower with necessary tools and equipments as per requirement and as directed by Engineer in charge. (Min. Two no. skilled & 2 no unskilled labour required for operation)	Each	70525.65
27.84	Providing and fixing of mirror 6mm thick of approved make as per direction and satisfaction of E-I-C.	Sqm	1216.75
27.85	Supplying of 304 grade Stainless steel studs of dimensions 35 x 25 x 4.5mm, having 8 grooves over flooring as per direction of E-I-C.	Each	51.75

Agg3hndm
22/05/2020