

(पंजीकृत डाक)

संदर्भ: भा.वि.प्रा./रापु./अभि(सि)/स.म.प्र./ए.एम.सी.-प्रचालन/2020/1481-92 दिनांक:-22.05.2020

सेवा में,

मेसर्स राकेश कुमार सिंह,
संजीवन विला, डी-16,
गैलेक्सी रेसीडेंसी, अमलीडीह,
रायपुर (छ.ग.)-492006

To,

M/s Rakesh Kumar Singh,
Sajeevan Villa, D-16,
Galaxy Residency, Amlideh
Raipur (C.G.)-492006

विषय: स्वामी विवेकानन्द हवाई अड्डा, रायपुर में प्रचालन क्षेत्र में सिविल रख-रखाव कार्यों के लिए
वार्षिक अनुबंध। (2020-22)

निविदा क्रमांक : 2020_AAI_40107_1

Sub: Annual Repair Maintenance Contract for Civil Work in Operational Area at S.V. Airport,
Raipur (2020 - 22).

Tender ID: - 2020_AAI_40107_1

संदर्भ: आपकी ई-निविदा जो दिनांक 28.02.2020 को खोली गयी।

Ref: Your E-tender opened on 28.02.2020

महोदय/Sir,

1. उपरोक्त कार्य के लिए आपकी निविदा में आपके द्वारा उद्धरित प्रतिशत दर शेड्यूल ए (निविदा दस्तावेज के पेज क्रं. SOQ-2 पर उल्लेखित भुगतान पद्धति के अनुसार) पर 31.33 प्रतिशत नीचे है को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है। इस कार्य हेतु कुल रुपये 127.12 लाख का आबंटन है।

Your percentage rate tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at your quoted percentage rate of 31.33% below schedule-A (As per payment methodology mentioned at page SOQ-2 of tender document). The fund allotted for this work is Rs. 127.12 Lakhs.

2. आपसे अनुरोध है कि कृपया दिनांक 05.06.2020 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 05.06.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 2,54,240/- (रुपये दो लाख चौवन हजार दो सौ चालीस मात्र) को जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा। कृपया इस कार्यादेश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये 10,16,960/- (रुपये दस लाख

सोलह हजार नौ सौ साठ मात्र) इस कार्यालय में जमा कराये अन्यथा यह निविदा दस्तावेज के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. 2,54,240/- (Rupees Two Lakhs Fifty Five Thousand Two Hundred Forty Only) received along with your tender will be treated and converted as part of security deposit as per Clause no. 1A on Page GCC-16 of tender document. Please deposit Rs. 10,16,960/- (Rupees Ten Lakh Sixteen Thousand Nine Hundred Sixty Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page GCC-16 of tender document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर जी.सी.सी-50 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनिमय एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही ठेका श्रमिक (विनिमय एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनिमय) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनिमय, अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 तथा केन्द्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 50 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई.एस.आई. अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ई.एस.आई. पंजीकरण काम के वास्तविक समापन तक वैध रहें।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप प्रबंधक (इंजी-सि), स्वामी विवेकानंद हवाई अड्डा, रायपुर से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg. - Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 24 (चौबीस) महीने होगा और इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 24 (Twenty Four) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

भवदीय,

संलग्न: अनुसूची-अ

अजय
22/05/2020
(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)

भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

मूलप्रति में नहीं
प्रतिलिपि:

1. क्षेत्रीय कार्यापालक निदेशक, पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
2. महाप्रबंधक (अभि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
4. उपमहाप्रबंधक (अभि-सि), भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
5. सहायक महाप्रबंधक (सर्तकता), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
6. सहायक श्रम आयुक्त (सी), डी-6, आदर्श सोसाइटी, सेक्टर-1, अवंती विहार, रायपुर।
7. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक-डी, स्कीम नं.-32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.)-492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
2. सहायक महाप्रबंधक (अभि-वि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
3. वरिष्ठ प्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
4. प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
5. कार्यालय प्रति।

अजय
22/05/2020

(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)

RC
Kam
22-5-20

Schedule-A

Name of Work: Annual Repair Maintenance Contract for Civil Work in Operational Area at S.V. Airport, Raipur (2020 – 22).

Item No.	Description of Work / Item(s)	Units	Rate
(I)	Schedule "A"(Part-I) (As per DSR'2016 with upto date correction slips) available in the office of Senior Manager (Engg.-Civil)		
	(Followed the sub heads of DSR 2016 from 01 to 26)		
(II)	Schedule "A" (Part - II) (Rate derived as per prevailing market rates)		
27	<u>Additional Misc. Items : -</u>		
27.1	Brick work with fly ash bricks (Min compressive strength 35 kg / sq cm) in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	3456.65
27.2	Brick work with fly ash bricks (Min compressive strength 35 kg / sq cm) above plinth upto floor V level: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	4756.60
27.3	Half brick masonry with fly ash bricks (Min compressive strength 35 kg / sq cm) above plinth upto floor V level: A) Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	645.45
27.4 (a)	Supplying Manpower for day to day maintenance jobs, (The contractor is bound to pay the minimum fair wages prevailing at the time of opening the tender and or statutory increase in future by State/Central Govt. during the entire period of the contract. The contractor will be responsible to supervise the work assigned to labours and has to supply T & P as per the requirement. (quoted percentage above /below will not be applicable on this item, the prevailing minimum wages should be paid under this item.) a) Skilled	Each	781.30
b)	Semi-skilled	Each	667.50
c)	Unskilled	Each	590.05
27.5(a)	Supplying and fixing G.I. fittings such as Tees, Elbows, Sockets, Nipple etc. of all size including dismantling old one and replacing with new one as per direction and satisfaction of Engineer-in-charge. (a) 15 mm to 20 mm dia	each	79.15
b)	25 mm to 32 mm dia	each	136.90
c)	40 mm to 50 mm dia	each	282.40
d)	65 mm to 80 mm dia	each	408.45
27.6	Supplying and fixing of brass spindles (heavy) of all size including dismantling old one and replacing with new one in pillar cock, bib cock etc. as directed by Engineer-in-charge.	each	303.80

27.7	Providing and fixing C.P. brass pillar cock of approved make etc. complete as per satisfaction of Engineer-In-Charge a) 15 mm nominal bore	each	993.10
27.8	Providing and fixing Gunmetal gate valve of approved quality with C.I. Wheel of make Neta or equivalent (screwed end) as per direction and satisfaction of Engineer-in-Charge a) 15 mm nominal bore	each	375.90
27.9	Providing & fixing different size PVC tank cover of make Sintex or equivalent at all floor level with necessary fittings etc. complete as per the direction of Engineer-in-Charge.	each	283.90
27.10	Testing of potable water as per BIS 1050 standard from local water supply authority or govt. approved lab I/c supplying of water sample to the laboratory and providing the water test report to Engineer-in-charge.	each Test	7665.70
27.11(a)	Cleaning of choked/blocked rain water pipe, soil waste pipe, vent pipe, manhole, sewerage pipe, gully traps, EWC, IWC, wash basin, kitchen sink, bottle traps, floor traps, house drain, storm water drain, etc. of any diameter and sizes including removal of garbage/malba for all leads and lifts within Airport premises etc. all complete as per direction and satisfaction of Engineer-in-Charge. (a) manhole including connected sewerage pipes upto the next manhole	each	573.45
b)	Gully traps/EWC/IWC/wash basins including connected soil waste/sewerage pipe upto the nearest manhole.	each	99.90
c)	Storm water drain for drain width upto 0.50 mtr	metre	22.95
d)	Storm water drain for drain width above 0.50 mtr	metre	36.30
e)	Rain water pipe / soil waste and vent pipe.	Mtr	15.10
f)	EWC/IWC/basin including connected traps and soil waste pipe upto the nearest opening point in the soil waste pipe.	Each	10.35
g)	House drain (open)	Mtr	18.90
h)	House drain (covered)	Mtr	64.40
27.12(a)	Cleaning of septic tank including removal of garbage/malba etc. all complete as per direction and satisfaction of Engineer-in-Charge. (a) Upto 7.5 sqm surface area.	each	4796.90
b)	Beyond 7.5 m2 surface area upto 15 sqm.	each	7309.35
c)	For surface area above 15 sqm.	each	10110.95
27.13(a)	Cleaning of under ground tanks/surface tanks and removing of silt/malba including disinfecting the tank with bleaching powder & washing etc. all complete as per direction and satisfaction of Engineer-in-Charge. (a) Upto 5000 liter capacity.	each	1494.30
b)	For every additional 1000 litres capacity.	each	256.15


27.14(a)	Cleaning of G.I./M.S./Masonry/Sintex over head tank including removal of silt/malba and disinfecting the tank with bleaching powder & washing etc. all complete as per direction and satisfaction of Engineer-in-Charge. (a) Upto 500 liters capacity.	each	540.60
b)	For every additional 100 litres capacity.	each	108.10
27.15	Trimming of trees (ht above 4.0 metres) in Airport premises including shifting the debris, cleaning the site etc. complete as per direction and satisfaction of the Engineer-in-Charge.	each	278.85
27.16	Providing and fixing sun control film (Garware or equivalent) after thorough cleaning of glass surface i/c removal of existing sun control film wherever required etc. all complete as per direction and satisfaction of Engineer-in-Charge.	sqm	574.95
27.17(a)	Providing and placing glass of make saint gobian with machine polished edge for table top complete as per direction of E I C (a) 12mm thick Bevelled edge	sqm	1693.60
b)	8mm thick bevelled edge	sqm	1479.40
27.18	Replacement of worn out Neoprene beading/gasket with new one in existing aluminium partitions, doors and windows i/c removing the old one and fixing the new one etc. all complete as per direction and satisfaction of E. I. C	metre	24.30
27.19	Providing and Fixing aluminium sheet (0.30 mm) on doors/windows shutters with steel screws, Fevicol etc. and sealing the edges with special structural quality Silicone adhesive sealant layer manufactured to standards like wacker, Dow Corning or equivalent etc. all complete as per direction and satisfaction of Engineer-in-charge.	sqm	835.30
27.20	Providing & placing in position HDPE bags of weight 30 kg including filling with sand and tying with thread complete as per direction of Engineer-in-charge.	each	58.90
27.21	Providing & fixing of 3M Radium computer cut letters on existing information / notice board etc. complete as per direction of Engineer-in-charge	sqm	2304.70
27.22	Printing on 3M vinyl sheet and pasting on existing notice board/signage board i/c necessary arrangements etc. complete as per the direction of Engineer-in-charge	sqm	647.10
27.23	Providing & fixing signages board printed on 3 M Vinyl sheet and pasting over 3 mm thick PVC/Acrylic sheet i/c necessary arrangements complete as per direction and satisfaction of Engg-in charge. (Frame work if required to be paid separately)	sqm	2190.20

27.24	Lettering with synthetic enamel paint of approved brand and manufacture in appropriate width, colour, arrangement etc. complete as per direction of Engineer-in-Charge.	per letter per cm height	3.45
27.25	Hiring of hydraulic excavator / JCB i/c operator , fuel and maintenance etc. complete for working in Airport premises as per direction and satisfaction of Engineer-in-Charge.	Per hour	1294.20
27.26	Repairing aluminium door/windows shutters & frames including removing, cutting, realigning and refixing i/c fixing hinges, screw etc. wherever required all complete as per direction and satisfaction of Engineer-in-charge.	each	458.70
27.27	Repairing of hydraulic floor spring/door closer in existing aluminium/wooden door.	Each	189.45
27.28	Repairing and refixing of wooden door/window shutter including removal of shutter from chowkhat, cutting wherever required and providing butt hinges on other side of frame of shutter wherever required all complete as per direction and satisfaction of Engineer-in-charge. (cost of hinges shall be paid extra).	Each	463.70
27.29(a)	Repairing and re-fixing gates (heavy) by welding using welding machine including transportation of electric welding machine etc. complete as per direction and satisfaction of Engineer-in-Charge (power will be supplied by the department if feasible). (a) For area upto 5.0 sqm	each	2137.45
b)	For area above 5.0 sqm	each	2468.95
27.30(a)	Providing and fixing stainless steel jali (with hole or without hole) over floor trap/ nahani trap etc. as per direction & satisfaction of Engineer-in-Charge. (a) 100 mm dia	each	47.50
b)	125 mm dia	each	57.45
27.31	Providing and fixing mosquito proof NETLON over frames of window, ventilators etc. fixing arrangement like stappling well crow strip over wooden frames including stitching other half of welcrow on netlon jali fit to size complete as directed by Engineer-in-Charge.	Sqm	769.75
27.32	Supplying of drinking water tanker of capacity 4500 litre at AAI premises of Swami Vivekananda Airport Raipur.	Each	597.35
27.33	Attending various day to day complaints and rectifying the defects/cause of complaints by deploying labour (unskilled, semi-skilled & skilled as and when required) with necessary the T & P but without changing replacing the fitting / fixtures etc. all complete as per direction and satisfaction of Engineer-in-Charge (the minor stores like screws for tightening hinges etc. and washers, thread, safeda etc. to prevent the leakage in bib cocks, stop cocks, pillar cocks, stop cocks etc., is included in the rate)	per month	17243.00

27.34(a)	Credit for taking away following dismantle materials from the site out side Airport premises at own transportation cost complete. (Note:- Rate shall be treated as minus rate) (a) C.P. Brass items like pillar cock, bib cock, sliding door bolt, handles and other similar items	Kg.	27.00
b)	M.S. items like pipe, angles, channels, handles, tower bolt, and other similar items.	Kg.	17.00
c)	Aluminium item like handles, section, doors, fittings and other similar items.	Kg.	82.00
d)	G.I. fittings items like union, socket, bend pipe and other similar items.	Kg.	27.00
e)	G.I. sheet and frofile sheet items.	Kg.	12.00
f)	All type of dismantle wooden items like frame, shutters,	Kg.	7.00
g)	All types of PVC items	Kg.	27.00
27.35(a)	Providing and fixing Plywood of make Regal/Century/Oxford or equivalent with screws etc to the existing frame work in the ceiling/openings (door, windows etc) to close the openings etc all complete as per direction and satisfaction of the EIC. (a) 6 mm thick plywood	Sqm	567.20
b)	12 mm thick plywood	Sqm	920.75
c)	18 mm thick plywood	Sqm	1274.20
d)	19 mm thick commercial plywood	Sqm	979.65
27.36	Providing and fixing magnetic ball catcher in wooden cupboards/shelves/drawers etc. complete and as per the direction of Engineer-In-Charge.	Each	112.80
27.37(a)	Providing and fixing E-board (cement based) with screws etc fixed to the existing frame work in the ceiling/openings (door, windows etc) to close the openings etc all complete as per direction and satisfaction by the EIC. (a) 6 mm thick	Sqm	449.40
b)	10 mm thick	Sqm	626.15
c)	12 mm thick	Sqm	802.90
27.38(a)	Providing and fixing roller blinds of make Vista or equivalent of required size, shade and colour etc. including installation & operating mechanism complete at site as per direction of Engineer-in-charge. (a) blackout FB series of marvel	Sqm	4502.15
27.39	Providing and fixing 100 mm wide vertical blinds of make-Marvel, Vista or equivalent i/c operating mechanism etc complete in all respect as per direction of Engineer-in-charge.	Sqm	1462.10
27.40	Application of silicon sealant of make DOWCORNING (all weather resistant) or equivalent for filling of gaps/joints (Minimum 5mm wide & 5mm deep) in aluminium/wooden/M.S. structures as well as repairing of cracks & leakages etc all complete as per direction and satisfaction of EIC.	metre	72.30

27.41	Carriage of malba from inside/outside of AAI premises to outside/inside of premises by mechanical means including loading and unloading by truck / tractor etc all complete as per direction and satisfaction of EIC		
a)	Upto 3 cum truck / tractor trolly capacity.	each trip	497.75
GLASS ITEMS:			
27.42	Providing and fixing wired glass of 6mm thick on the existing doors,windows,ventilator shutters and partitions etc. with PVC neoprene gasket etc.complete as per direction of E I C.	Sqm	1315.35
27.43	Providing and fixing glass 17.52mm thick laminated glass (8mm thick toughened glass + 1.52mm P.V.B. lamination + 8 mm thick toughened clear glass) in existing glazing structures of any height including scaffolding and removing of old broken glass all complete as per direction of Engineer-in-charge. (No Extra payment will be made for dismantalling & Scaffolding shall be paid extra as per actual)	Sqm	7615.55
27.44	Providing and fixing double glazed hermetically sealed glazing in existing glazing system of all heights with 6 mm thick toughened outer glass, having 12 mm air gap, and 6mm thick clear toughned inner glass etc. complete in all respect as per direction of Engineer-in-charge. (Scaffolding shall be paid extra as per actual)	Sqm	4664.80
27.45	Providing and fixing 10 mm thick clear float toughened glass glass of required size and shape and of approved make in frameless show window, The glass to be fixed in line and plumb with a minimum gap of 6 mm between glass to glass and filled with clear weather sealent of Dow Corning or approved equivalent. The gaps between both sides of channel and glass should be inserted with sealent. All the perimeter gaps between the channel and masonry / RCC/ stone shall also be sealed with clear weather sealant of Dow Corning or approved equivalent complete in all respect as per directions of Engineer-incharge. (Scaffolding shall be paid extra as per actual)	Sqm	2118.85
JAQUAR SANITARY & PLUMBING ITEMS:			
27.46	Providing and fixing flush valve dual flow 32 mm (codeFLV-1085) of Jaguar including wall plate or approved equivalent, water volume adjustment and flush pipe, complete as per directions of Engineer-in-charge.	Each	2542.60
27.47	Providing and fixing in position Health faucet with 1m flexible tube and wall hook with all necessary accessories (code ALD-579) of Jaguar or approved equivalent complete as per directions of Engineer-in-charge.	Each	941.75

27.48	Providing & fixing Dorma or equivalent make BTS 75 floor spring for glass door i/c necessary fixing arrangements etc. complete as per the direction of EIC.	Each	14668.80
MISCELLANEOUS ITEMS:			
27.49	Supplying and Placing of Neel kamal make free litter swinging bin of 100 ltr capacity as per manufacturer specification, direction and satisfaction of E-I-C.	Each	1493.30
27.50	Supplying and placing of plastic/pvc make flower pot of size 450 mm dia in approved colour as per direction and satisfaction of E-I-C.	Each	547.55
27.51	Providing administrative and Technical services for office work i/c operating computer, printer and photocopier and handling day to day services etc. for the Senior official in one general shifts by deploying required number of skilled/unskilled manpower as per requirement and as directed by Engineer in charge. (Minimum 1 skilled and 1 unskilled manpower to be deployed to execute the item)	per month	30308.30
27.52	Cutting grass in operational area surrounding basic strip of the runway by deploying departmental tractor with necessary fuel, mobile etc. complete excluding the services of tractor operator and helper as per direction of E-I-C. (Grass cutting machine, fuel, mobile etc. to be provided by AAI, rate for tractor operator and helper to be provided by the agency for this item.	Per month	43278.25
27.53	Cutting grass in operational area beyond basic strip of the runway (near boundary wall, outside drain etc.) by deploying departmental hand cutter machine with necessary fuel, mobile etc. complete excluding the services of hand cutter machine and as per direction of E-I-C. (Grass hand cutting machine, fuel etc. to be provided by AAI, rate for grass cutter operator to be provided by the agency for this item.	Day	566.45
27.54(a)	Cutting of Bushes in operational area and disposal the same (un-serviceable material) outside the periphery of the area cleared. (a) Girth upto 5 cm.	Each	15.05
b)	Girth beyond 5cm upto and including 10 cm.	Each	25.05
27.55	Supplying of cans of epoxy resing and hardner (each of one liter) at site of approved make as directed by Engineer in charge.	Each	925.85
27.56	Hiring of Hydra/crane i/c operator , fuel and maintenance etc. complete for working in Airport premises as per direction and satisfaction of Engineer-in-Charge.	Per Hour	869.55


 22/05/2020
 Aum (E-C)