



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



COIMBATORE INTERNATIONAL AIRPORT

सं.सं.:भा.वि.प्रा./सीबीई/इ-वि/CW-01&02/02/W-31/2019-20

Ref. No: AAI/CBE/E-E/CW-01&02/02/W-31/2019-20

दिनांक: 26.02.2020

द्रुत डाक द्वारा

BY SPEED POST

सेवा में /To

M/s. C.P.Monchester Electricals,
D-60, Brindhavan Nagar,
Civil Aerodrome Post,
Coimbatore - 641014.

मेल आई.डी / Mail id: cpmonchesterele@gmail.com

Name of Work: Replacement of Feeder Cable for SAPL R/W 23 and Provision of standby Feeder for R/W 23 PAPI at Coimbatore International Airport.SH: Laying of AFL Cable & Allied works.

संदर्भ / Ref: 1) दि. 17.02.2020 को आपका वित्तीय बोली खोला गया। / Your Financial Bid Opened on

.17.02.2020. (E-bid No: 2020_AAI_40892_1)

महोदय/Dear Sir (s),

1. उपर्युक्त कार्य के संबंध में आपका निविदा को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया गया है, मद के लिए आपके द्वारा उद्धृत राशि कुल रू. 13,99,993.00 प्लस जी.एस.टी सेवा कर भी जो न्यायोचित राशि रू. 18,11,153.00. से 22.70 % नीचे। Your E-tender for the above mentioned work is accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 13,99,993.00 (Rupees Thirteen Lakhs Ninety Nine Thousand Nine Hundred and Ninety Three Only) excluding GST @ 18%, which is 22.70% below the estimated cost put to tender of Rs. 18,11,153.00 excluding GST.
2. भा.वि.प्रा. कोयंबतूर अंतरराष्ट्रीय हवाईअड्डा के सहायक संयुक्त महाप्रबंधक (इंजि-वि), इस कार्य के इंजिनियर प्रभारी है। आपसे अनुरोध है कि दि. 06.03.2020 को, भा.वि.प्रा. कोयंबतूर हवाईअड्डा संयुक्त महाप्रबंधक (इंजि-वि), के कार्यालय आए और करार को हस्ताक्षरित करके पूरा करें। अनुबंध एग्रीमेंट गैर न्यायिक स्टाम्प कागज मूल्य रू.100.00 (एक सौ मात्र) के लिए निष्पादित करना है और स्टैम्प कागज का मूल्य आपके द्वारा वहन किया जाएगा। Jt. Gen. Manager (Engg-Elect), AAI, Coimbatore International Airport shall be the Engineer-In- Charge of the work. You are requested to attend the office of the Jt.Gen.Manager (Engg-Elect), AAI, Coimbatore Airport on or before 06.03.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100.00 (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.
3. अनुबंध निविदा के पृष्ठ 16 पर धारा के मुताबिक, आपके निविदा के साथ रू. 36,223.00 की अग्रिम राशि पर विचार किया जाएगा और उसे सुरक्षा जमा के एक हिस्से में परिवर्तित कर दिया जाएगा.आपके द्वारा निविदा के साथ सुरक्षा जमा राशि के भाग के रूप में माना जाएगा। यह पत्र जारी के 10 दिनों के अंदर रू. 1,03,776.00 को कृपया सुरक्षा राशि के रूप में जमा करें, जमा नहीं किया तो चालू बिलों से उपर्युक्त राशि की कटौती की जाएगी। The Earnest money amount of Rs.36,223.00 (Rupees Thirty Six Thousand Two Hundred and Twenty Three Only) received along with your tender will be

COIMBATORE INTERNATIONAL AIRPORT, COIMBATORE - 641 014

PHONE/FAX: 0422-2571668

Web Site: www.airportsindia.org.in



COIMBATORE INTERNATIONAL AIRPORT

treated and converted as part of security deposit as per clause on page no.16 of contract document. Please deposit Rs 1,03,776.00 (Rupees One Lakh Three Thousand Seven Hundred and Seventy Six Only) as Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills.

4. कृपया ध्यान दें कि कार्य को करने के लिए अनुमत समय 3 महीने का होगा और इस पत्र के जारी होने के 10 वें दिन से इसे फिर से लिया जाएगा।/ Please note that the time allowed for carrying out the work shall be 3 (Three) Months and same shall be reckoned from the 10th day of issue of this letter.
5. कार्य की पूर्णता की तारीख से दोष देयता अवधि 12 (बारह) महीने होगी। The Defects Liability Period shall be 12 (Twelve) months from the date of completion of Work.
6. आपको वरिष्ठ प्रबंधक (इंजीनियरिंग-इलेक्ट्रिकल), भारतीय विमानपत्तन प्राधिकरण, कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे से तुरंत संपर्क करने के लिए निर्देशित किया जाता है, जो आपको साइट सौंपने की व्यवस्था करेगा। You are also directed to contact Sr.Manager (Engg-Elect), AAI, Coimbatore International Airport immediately who will arrange to handover the site to you.
7. आपसे अनुरोध है कि जीएसटीआईएन का जिक्र करते हुए जीएसटी अधिनियम के अनुसार वैध जीएसटी चालान जमा करने का अनुरोध किया जाए, जो कि जीएसटी दरों को लागू करता है और इनपुट टैक्स क्रेडिट विवरण इंगित करता है यदि एआई कोयंबटूर जीएसटी का उल्लेख करने वाले बिलों को संसाधित करने के लिए कोई है। 33AAACA6412D1ZF/ You are requested to submit valid GST invoice as per GST act mentioning the GSTIN, indicating the GST rates applicable and input tax credit details if any for processing the bills mentioning the AAI Coimbatore GST no.33AAACA6412D1ZF.
8. अनुबंध के संबंध में कोई और पत्राचार आम तौर पर सहायक को संबोधित किया जाना चाहिए संयुक्त महा प्रबंधक (इ-वि), कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे। Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (Engg-Elect), AAI, Coimbatore International Airport.
9. कृपया इस कार्य आदेश की प्राप्ति को स्वीकार करें। Please acknowledge the receipt of this work order.

अनुलग्नक/Encl: अनुसूची/Schedule 'A'.

संयुक्त महाप्रबंधक (इ-वि),
Jt. Gen. Manager (Engg-Elect)

Name of Work : Replacement of Feeder Cable for SAPL R/W 23 and Provision of standby Feeder for R/W 23 PAPI at Coimbatore International Airport. SH: Laying of AFL Cable & Allied works

Schedule A

Schedule of Quantities


Item No.	Description of Item	Qty	Rate	Unit	Amount
1	Supply of C.I. Transformer housing box water tight round type metal container of out side dia of 330 mm, height 450 mm made of 10 mm thick cast iron moulding all round except on top surface which is 15 mm thick suitable to receive a light fitting base plate at the top and underground housing associated with transformer power cable and having two nos of collar at opposite sides 75 mm above bottom surface suitable to receive two nos. for 50 mm dia 'B' class G.I. pipe & having clear opening of 220 mm at top surface and 6 nos. M 10 tapped hole at the center of 260 mm to receive light fitting base plate and bolts and with 3mmx330mm round MS cover plate to fix on CI box as required.	8	5000.00	Job	40000.00
2	Installation of C.I. Transformer housing box water tight round type metal container of outside dia of 330 mm, height 450 mm in ground with 1:2:4 concrete (1: cement, 2 : coarse sand, 4 : concrete of 20mm nominal size) at base and all around the CI box of 100 mm thick and a pedestral concrete of 1 mtr x 1 mtr near the ground level at a depth of 20 cm with suitable coping at top as specified in the drawing including providing of MS base plate of thickness 10 mm, gasket, 6 sets of SS hardware and fixing of the same with CI Transformer housing box etc. complete as required as per specification & drawing.	8	4500.00	Job	36000.00
3	SITC of 3mm thick hot press moulded SMC box (GS -JB -3126 type or equivalent) of size with outside dimensions not less than 317mm(H) x 265 mm(W) x 160mm(D) outer dimensions and fixing on surface and making necessary provision for cable entry for 2 x 25 sq.mm/2 x16 sq.mm/1x6sq.mm PVC sheathed & PVC insulated armoured/unarmoured cable and cable connection arrangement by providing 2 nos. of 100A kitkat fuse base and carrier on 8 mm thick hylum sheet of suitable size etc. as required.	2	7000.00	Job	14000.00

Item No.	Description of Item	Qty	Rate	Unit	Amount
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 5 kV grade of following size in the existing RCC/ HUME/ METAL/ PIPE / closed masonry duct as required. 2 x 16 Sqmm	5218	24.00	Mtr	125232.00
5	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size on wall surface/ cable tray etc. as required. 2 x 16 Sqmm	42	90.00	Mtr	3780.00
6	Supplying and laying of following size ISI marked DWC HDPE pipe along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.in the existing trench/ duct ., complete as required. 50 mm OD, 38 mm ID	5023	117.00	Mtr	587691.00
7	Making field connections by crimping 2 x16/6 Sq.mm plug and receptacle with existing 2 x16/6 Sq.mm single core copper conductor PVC insulated and PVC sheathed cable including filling the gap with water sealent material applying HT tape over PVC tape etc as required.	8	200.00	Set	1600.00
8	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc. in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 meters.	902	375.00	Cum	338250.00
9	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge: Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	3	1500.00	Cum	4500.00
10	Providing and laying in position cement concrete of specified grade excluding the cost of 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	3	4500.00	Cum	13500.00

Item No.	Description of Item	Qty	Rate	Unit	Amount
11	Earthing with G.I. earth pipe 2.75 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	8	6000.00	Set	48000.00
12	Supply and laying of 6 SWG dia GI wire along with cable including providing lugs for termination, etc complete as required.	5260	24.00	Mtr	126240.00
13	Providing, laying and fixing following dia RCC pipe NP2 class (light duty) in ground complete with RCC collars, jointing with cement mortar 1:2 (1 cement : 2 fine sand) including trenching (75 cm deep) and refilling etc. as required. 300 mm dia	8	900.00	Mtr	7200.00
14	Constructing masonry chamber of size 80x80x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for cable laying i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick with common burnt clay F.P.S.(non modular) bricks of class designation 5, including fabrication and fixing of GI chequered plate manhole cover with 80 x 80 cm size and 5 mm thick including MS L angle support, lifting hooks etc. the masonry chamber shall protrude 10 cm above the ground level to prevent water entry etc, complete as required.	2	27000.00	Job	54000.00
Grand Total					1399993.00

(Rupees Thirteen Lakhs Ninety Nine Thousand Nine Hundred and Ninety Three Only)

(Excluding GST @ 18%)


26/07/2020
Jt.Gen.Manager (E-E)

Signature Not Verified

Digitally signed by SHIVA KUMAR GUNDA
Date: 2021.06.28 16:08:12 IST
Location: eProcurement System for Central PSUs