



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
अभियांत्रिकी विधुत विभाग, सुरत हवाई अड्डा

ENGINEERING ELECTRICAL DEPARTMENT, SURAT AIRPORT
Phone: 0261-2700200 / 2700209, Fax: 0261-2700295/2700244

संख्या : भाविप्रा/सुरत/अभि-वि./एप्रन एक्सटेंशन/ए.एफ.एल/2020-21/6797-6312
No: - AAI/SURAT/ENGG (E)/Apron Extension/AFL/2020-21

दिनांक: - 23.10.2020
Date: - 23.10.2020

(कार्य आदेश / Work Order)

सेवा में,
मेसर्स. न्यू वाटर वर्ल्ड,
109, सर्वोदय नगर, शुभम फ्लैट के सामने,
प्रमुख फरसान के पास, 120 फीट. बमरोली रोड,
पांडेसरा, सुरत - 394210

To,
M/s. New Water World.
109, Sarvodaya nagar, Opp. Shubham Flate.
Near. Pramukh Farsan, 120 ft. Bamroli
Road, Pandesara, Surat - 394210

कार्य का नाम: "सुरत हवाई अड्डे के समग्र विकास सहित टर्मिनल बिल्डिंग तथा एप्रन का विस्तार,
एवं समान्तर टेक्सी ट्रैक के निर्माण हेतु।
उपशीर्ष : एप्रन फ्लड लाइट और संबंधित कार्य।"

Name of Work: "Holistic Development of Surat Airport Including Extension of Apron and
Terminal Building and construction of Parallel Taxi Track.
SH: Apron flood lights & associated works."

संदर्भ / Ref.: - 1. आपका टेंडर दिनांक 21.08.2020 को खोला गया। (निविदा आईडी: सं.: 2020_AAI_41740_1)
1. Your tender opened on. 21.08.2020 (Tender Id No: 2020_AAI_41740_1)

महोदय / Dear Sir,

1. उपर उल्लेखित कार्य हेतु आपका टेन्डर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण कि ओर से स्वीकृत किया जाता है, आपके द्वारा बताये गये मद मूल्यों पर आपकी टेन्डर राशी रु. 92,56,122.20 (रुपए: बयान्वे लाख छप्पन हजार एक सौ बाईस रुपए बीस पैसा) है, जो कि टेंडर कि उचित राशि रु. 1,30,30,696.00 से 28.97% नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you to Rs. 92,56,122.20 (Rupees: Ninety Two Lakh Fifty Six Thousand One Hundred Twenty Two Rupees Twenty Paise). which is 28.97% below the justified cost put to tender of Rs. 1,30,30,696.00 (Rupees: One Crore Thirty Lakh Thirty Thousand Six Hundred Ninety Six Only).

2. सहा. महाप्रबंधक (अभि-वि.) भाविप्रा, सिविल एरोड्रम सुरत - 394 550 कार्य के प्रभारी अभियंता होंगे आपसे निवेदन है की दि. 15.11.2020 तक सहा. महाप्रबंधक (अभि-वि.) , भाविप्रा ,सिविल एरोड्रम सुरत - 394 550 के कार्यालय में उपस्थित हो तथा ठेके के करारनामे को पूरा करें। ठेके का करारनामा 100/- (रुपये एक सौ मात्र) के नॉज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जायेगा ,तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा।

[Signature]

[Signature]

Asst. Gen. Manager (Engg-E) AAI, civil Aerodrome, Surat - 394 550 shall be Engineer-In-Charge of this work. You are requested to attend the office of Asst. Gen. Manager (Engg.-E), AAI, Civil Aerodrome, Surat -394 550 by 15.11.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non judicial stamp paper of value Rs. 100/- (Rupees Hundred Only) and the cost of the stamp paper shall be borne by you.

3. ठेका कागजात की संविदा की सामान्य शर्तों के पृष्ठ - 26 की शर्त 1 (ए), के अनुसार आपकी संविदा के साथ रु.2,60,237.00 (रुपए: दो लाख साठ हजार दो सौ सैंतीस केवल) की बयाना राशि को प्रतिभूति जमा के कुछ भाग में तब्दील कर दिया गया है। कृपया शेष राशि रु. 6,65,375.00 प्रतिभूति जमा के रूप में, यह पत्र जारी करने के तारीख के बाद दस दिन के अन्दर जमा करे, जमा करने कि असफलता के कारन वह राशि ठेका दस्तावेज के सामान्य नियम और निर्देश (जीसीसी) के शर्तों के पन्ना क्र. 16 पर संविदा के खंड - 1 (क) के शर्त के अनुसार काट दी जायेगी।

The earnest money amount of Rs. 2,60,237.00/- (Rupees: Two Lakh Sixty Thousand Two Hundred Thirty Seven Only) received along with your tender will be treated and converted as part of Security Deposit as per clause 1 (A) on Page 26 of the General condition of contract of Tender document. Please deposit balance Rs. 6,65,375.00 towards security deposit within 10 (TEN) days from the date of issue this letter, failing which the same will deducted from the running bills as per General Rules & Directions(GCC) clauses of contract - clause 1A on page 16 of the contract document.

4. ठेका कागजात की संविदा की सामान्य निर्देश एवं नियम के पृष्ठ-19 की शर्त 13, के अनुसार आपकी संविदा ए एल क्यू बी है और इस कारण आपके द्वारा, क्यू पी बीजी के रूप में जमा की गयी राशी रु. 51,690.00 (रुपए: इक्यावन हजार छे सौ नब्बे केवल), कार्य समाप्ति तक भा.वि.प्रा. के पास जमा रहेगी।

The amount of Rs. 51,690.00 (Rupees: Fifty One Thousand Six Hundred Ninety Only) paid by you as a QPBG being ALQB, will remain with AAI till the completion of work as per clause 13 on page 19 of the General rule and direction of Tender document.

5. आपसे निवेदन है की आप केन्द्रीय एवं राज्य सरकारों के 1970-अधिनियम, अनुबंध श्रम नियम (नियमन तथा अनुमूलन) और 1971 केन्द्रीय नियम अनुबंध श्रम नियम (नियमन तथा अनुमूलन) और केंद्र तथा राज्य सरकारों का न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) ACT 1970 Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act and rules thereof Central and State governments.

6. आपसे निवेदन है की जीसीसी के खंड-46 के अनुसार दिए गए सभी जोखम निति का अनुपालन करे और ओल रिस्क पोलिसी जमा करे

You are also requested to comply with the Clause 46 of GCC and submit the all risk policy as stipulated in the Clause.

7. आपको निर्देश दिया जाता है की आप तुरंत प्रबंधक (अभि.-वि), सुरत हवाईअड्डे पर संपर्क करो। वह आपको साईट सोपने कि व्यवस्था करेगे।

You are also directed to contact Manager (Engg.-E), Surat immediately, who will arrange to hand over the site to you.

8. कृपया नोट करे कि काम करने का अनुमानित समय (10) माह का होगा जो की इस पत्र के जारी करने के दसवे दिन से माना जायेगा ।

Please note that the time allowed for carrying out the work shall be (10) Ten Month and which shall be reckoned from the 10th day of the date of issue of this letter.

9. इस ठेके संबंध में आगे का कोई भी पत्राचार सहा. महाप्रबंधक (अभि.-वि.), एअरपोर्ट ऑथोरिटी ऑफ़ इंडिया, सुरत एअरपोर्ट, सुरत-394550 के पते पर किया जाए ।

Any further correspondence in connection with the contract should normally be addressed to the Asst. Gen. Manager (Engg.-E), Airport Authority of India, Surat Airport, Surat - 394550.

10. कृपया पावति भेजे और इसके साथ सलग्न इस पत्र की अनुलिपि हस्ताक्षर करने के बाद अधोहस्ताक्षरी को स्वीकृती के टोकन रूप हेतु लौटाए ।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

यदि अंग्रेज़ी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेज़ी विवरण सही माना जायेगा ।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

धन्यवाद /Thanking You.

भवदीय /Yours faithfully,

(सुनिल कुमार कोटिया) / (Sunil Kumar Kotia)

सहा. महाप्रबंधक(अभि. – वि.)/Asst. Gen. Manager (Engg.-E)

अभियांत्रिकी विधुत, सुरत हवाईअड्डा /ENGINEERING ELECTRICAL SURAT AIRPORT

कृते तथा ओर से अध्यक्ष भारतीय विमानपत्तन

For and on behalf of the Chairman, Airports Authority of India.

सलग्नक : मात्रा की सूची

Encl: - Schedule of Quantity (Page No. 01 to 08)

CC:-Agreement.

प्रतिलिपि / Copy to:-

1. Regional Labour Commissioner (Central), Chandraprabha Flat No. 2, Krishna Nagar Society, Opp. Moti Baugh, Place, Navapura, Vadodara, Gujarat 390001 - Along With from (VI-B) for commencement of work.
2. Regional Provident Fund Commissioner, EPFO, Bhavishya Nidhi Bhavan, Ram Chowk, God Dod Road, Surat-395001.
3. Additional Commissioner of Income Tax, TDS Range, Room No.312, Ayker Bhavan, Opposite New Civil Hospital, Majuragate, Surat.

Validate Print Help <u>Item Rate BoQ</u>							
Tender Inviting Authority: AGM (E E), AAI, CA Surat							
Name of Work: Holistic Development of Surat Airport Including Extension of Apron and Terminal Building and construction of Parallel Taxi Track SH: Apron flood lights & associated works							
Contract No:							
Name of the Bidder/ Bidding Firm / Company :	M/s. New Water World						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	High Mast						
1.01	Design, supply, Installation, Erection, Testing and commissioning of 30 m flood light high mast fabricated in three telescopic sections(MS), hot Dip galvanised finish totally on externally and internally etc (with base plate welded to the bottom sections) and suitable for wind velocity as per IS 875 part 3 (latest) and holdings suitable for installation of flood lighting luminaries including erection of mast & other assemblies as required with following accessories etc as per the tender specifications.						
1.02	Lantern carriage fabricated and galvanized suitable to hold 6 Nos.or more as per illumination design 350& 500 watt LED flood light fittings and 2 Nos. LED type Single dome aviation obstruction lights(i/c supply of 2nos LED Type single dome aviation light) and to accommodate control gear boxes(as required), Supply and fixing of 20/21 way terminal block suitable for interconnection of flood light fixtures (Qty. 2 Nos.for each high mast) and have self balance including junction box, Heavy guage hot dip galvanized lightening arrester finial.						

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.03	Electrically operated raising and lowering mechanism consisting of suitable double drum winch assembly, head frame assembly on top with self lubricating bearing, Stainless steel shaft, noncorrosive pulley and stainless steel wire ropes(2 nos one for each drum) of minimum 6mm dia (7/19) etc. and designed to operate with electric driven power tool and also suitable for manual operation including connector, integral power tool motor, manual handle, trailing cable, junction box etc.						
1.04	Providing & laying required length & appropriate rating of 1.1 KV grade 2 runs of 5 core x 2.5 sq mm copper conductor trailing (EPR insulated PCP sheathed cable for power supply from the top carriage of mast to bottom distribution box / feeder pillar/coupler/connector i/c wiring to the individual fittings & also providing G.I. flexible pipe for protection if required at site.						
1.05	Supply of foundation bolts manufactured from special steel along with nuts, washer, suitable size anchor plates and template etc as required.						
1.06	Design & construction of suitable shallow foundation (RCC) with 1:2:4 M20 grade concrete for the highmast considering the safe soil bearing capacity at site at 2 metre depth with all materials and labour. Concrete foundation required for the mast shall be designed based on the soil bearing capacity of site as per relevant IS standards and shall got vetted from the IIT/SVNIT or other reputed institutions to validate the foundation design						
1.07	Erection of the high mast with the help of suitable equipments and wiring of luminaires with all wiring materials and labour i/c testing & commissioning etc. Complete as required as per site requirement.	Item 1	10.00	Job	382386.00	3823860.00	INR Thirty Eight Lakh Twenty Three Thousand Eight Hundred & Sixty Only

(2/8)

[Signature]
23/10/2020

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Supplying and installation of cubicle type totally enclosed free standing, dust & vermin proof and water proof outdoor(IP-55) single door type feeder pillar of suitable size suitable for 415 V, 3 Phase, 4 wire 50 Hz AC supply system fabricated out of 2mm thick CRCA sheet duly powder coated of approved shade, 3mm thick detachable gland plates at bottom with 2 Nos. earth stud of min. 12 mm dia bolt, including angle iron frame work at bottom with legs of minimum 600 mm height made out of 75 x 75 x 5 mm MS angle iron including all civil works like excavation, PCC, brick work pedestal, plastering, refilling etc as required. The control wiring shall be of minimum 2.5 sq mm size FRILS, PVC insulated and feeder pillar shall have the following : 1) Incoming: 32 A, 4P, 10KA MCB and 32 A TP AC-3 Rating contactor with thermal O/L relay and 230 VAC operating coil and 2NO/2NC aux. contact for automatic power supply redundancy. – 2 nos 2) 25 A, 4P, 10KA MCB with 25A TP AC-3 Rating contactor with 230 VAC operating coil & thermal O/L relay and 2NO/2NC aux. for the automatic switching of luminaries with illuminated push button for local operation & selector switch for Local/ Remote operation - 01 no. 3) 24Hrs dial time switch/ single pole contactor with 6 A protection DP MCB for aviation light. 4) Power tool control with 2 no. 9A contactors and 4A MPCB for 2 hp motor having thermal release 2.5-4.0A, SPP and Raise /Lower push button. It shall be interlocked with power contactor so that it shall not be operated when power contactor is ON. 5) Incoming and outgoing cables of size 4x35sq mm connectors, terminations and any other item as required to complete the job.	Item 2	10.00	Each	17500.00	175000.00	INR One Lakh Seventy Five Thousand Only
3	Supply & installation of following LED fixture complete with LED, driver & all accessories pre wired upto terminal block operating on 100 -277 volts & 50 Hz with CRI>70% & IP66 protection & IK08 capable to operate from -10o C to 45o C ambient temp. Driver shall be with THD less than 10% and power factor shall not be less than 0.95 & other specifications as per tender.						

(3/8)

[Signature]
23/10/2020

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
3.01	350W (Maximum system wattage) flood light fixture with beam angle 330 + 10% and made of pressure die cast with fin aluminum alloy duly powder coated housing with clear toughend glass and cradle for mounting giving minimum system output of 35000+ 10% Lumens and 5700K+ 300 CCT	Item 3	44.00	Job	17500.00	770000.00	INR Seven Lakh Seventy Thousand Only
3.02	500W (Maximum system wattage) flood light fixture with beam angle of 220 + 10% and made of pressure die cast with fin aluminum alloy duly powder coated housing with clear toughend glass and cradle for mounting giving minimum system output of 60000+ 10% Lumens and 5700K+ 300 CCT	Item 4	16.00	Job	25300.00	404800.00	INR Four Lakh Four Thousand Eight Hundred Only
4	Supply of following Size. XLPE insulated, PVC sheathed AL. conductor armoured power cable of 1.1 KV grade conforming to IS:7098 Part-I with upto date amendment etc. complete as required.						
4.01	4 core x 35 Sq. mm	Item 5	2100.00	Mtrs	180.00	378000.00	INR Three Lakh Seventy Eight Thousand Only
4.02	3.5 core x 300 Sq. mm	Item 6	2100.00	Mtrs	1180.00	2478000.00	INR Twenty Four Lakh Seventy Eight Thousand Only
5	Supply of following size XLPE insulated PVC inner sheathed copper stranded conductor armoured LT control cable of 650/1100 v grade conforming to IS:7098 Part-I(1988) with up to date amendment etc. complete as required.						
5.01	19 core x 1.5 Sq. mm	Item 7	600.00	Mtrs	250.00	150000.00	INR One Lakh Fifty Thousand Only
5.02	10 core x 1.5 Sq. mm	Item 8	200.00	Mtrs	250.00	50000.00	INR Fifty Thousand Only

(4/8)



NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
6	Supply and Laying of 120 mm dia (OD-120 mm & ID-103 mm nominal) sizes DWC HDPE pipe ISI marked conforming to IS 16205 PART 24 (formerly known as IS 14930 Part II) along with all accessories like socket, bend, couplers etc complete with fitting and cutting, jointing etc direct in ground (75 cm below ground level) including excavation & refilling the trench with same excavated earth.	Item 9	440.00	Mtr	150.00	66000.00	INR Sixty Six Thousand Only
7	Supply and Laying of 120 mm dia (OD-120 mm & ID-103 mm nominal) size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 16205 PART 24 (formerly known as IS 14930 Part II) complete with fitting and cutting, jointing etc. in the existing trench, complete as required.	Item 10	580.00	Mtr	150.00	87000.00	INR Eighty Seven Thousand Only
8	Supplying and making end termination with brass compression gland and Aluminum lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 kV grade as required.						
8.01	3.5x300Sq.mm	Item 11	12.00	Each	50.00	600.00	INR Six Hundred Only
8.02	4 x 35 Sq.mm	Item 12	40.00	Each	20.00	800.00	INR Eight Hundred Only
8.03	10 /19 core 1.5 Sq.mm (copper)	Item 13	18.00	Each	20.00	360.00	INR Three Hundred & Sixty Only
9	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/PVC pipe as required						
9.01	Upto 35 sq. mm	Item 14	2550.00	Mtr	5.00	12750.00	INR Twelve Thousand Seven Hundred & Fifty Only
9.02	above 95 sq. mm upto 185 sq mm	Item 15	1830.00	Mtr	5.00	9150.00	INR Nine Thousand One Hundred & Fifty Only

(5/8)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
10	Supplying and installation of cubicle type totally enclosed free standing, dust & vermin proof and water proof (IP-55) outdoor double door type feeder pillar(openable on front & back) of suitable size suitable for 415 V, 3 Phase, 4 wire 50 Hz AC supply system fabricated out of 2mm thick CRCA sheet duly powder coated of approved shade, 3mm thick detachable gland plates at bottom with 2 Nos. earth stud, including angle iron frame work at bottom with legs of minimum 600 mm height made out of 75x75x5 mm MS angle iron including all civil works like excavation, PCC, brick work pedestal, plastering, refilling etc as required. The control wiring shall be of minimum 2.5 sq mm size FRLS, PVC insulated and feeder pillar shall have the following switch gears as per the approved drawing.						
10.01	INCOMER						
10.02	2 Nos-100A, 25KA, 4 pole MCCB with thermal release & adjustable O/L setting 0.8-1.0xIn and RYB, ON, OFF & trip indicator with control MCB Make- L&T Cat no: DN0-100C or equi. approved						
10.03	BUSCOUPLER						
10.04	1 No-100A, 25KA, 4 pole MCCB with thermal release ON & OFF indicator with control MCB Make- L&T Cat no: DN0-100C or equi. approved						
10.05	Busbar						
10.06	1 Set of 100 Amp (Minimum) TPN busbars of high conductivity electrolytic grade aluminium with heat shrinkable colour sleeves & DMC/SMC supports						
10.07	Outgoing						
10.08	2 Nos-100A, 25KA, 4 pole MCCB with thermal release & adjustable O/L setting 0.8-1.0xIn and RYB, ON, OFF & trip indicator with control MCB Make- L&T Cat no: DN0-100C or equi. approved						
10.09	8 nos.- 32 Amp, 4P, 10KA MCB with suitable size connector & copper flexible wire						

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
10.10	Other Accessories						
10.11	Internal connections, industrial connectors for cables to be provided. There shall be electrical & mechanical interlocking between incomers & bus coupler and 50x6 mm AL common Earth & any other accessories etc as required. Control wiring shall be done with minimum 2.5 sqmm copper FRLS flexible wire.	Item 16	3.00	Job	115000.00	345000.00	INR Three Lakh Forty Five Thousand Only
11	Earthing with GI earth pipe (B-Class) 4.5 mtr long, 40mm dia including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required.	Item 17	10.00	Set	8500.00	85000.00	INR Eighty Five Thousand Only
12	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	Item 18	20.00	Set	5200.00	104000.00	INR One Lakh Four Thousand Only
13	Providing and laying 6 SWG dia. GI wire on surface or in recess for loop earthing along with the existing cable on surface/recessed/in cable trench or in pipes etc. complete as required.	Item 19	4200.00	Mtr	8.00	33600.00	INR Thirty Three Thousand Six Hundred Only
14	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	Item 20	100.00	Mtrs	370.00	37000.00	INR Thirty Seven Thousand Only
15	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required	Item 21	30.00	Mtrs	85.00	2550.00	INR Two Thousand Five Hundred & Fifty Only
16	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.						
16.01	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Item 22	72.00	Cum	3000.00	216000.00	INR Two Lakh Sixteen Thousand Only

(7/8)





NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST)	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
17	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.						
17.01	All kinds of soil	Item 23	248.00	Cum	100.00	24800.00	INR Twenty Four thousand Eight Hundred Only
18	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Item 24	26.46	Cum	70.00	1852.20	INR One Thousand Eight Hundred & Fifty Two and Paise Twenty Only
Total in Figures						9256122.20	INR Ninety Two Lakh Fifty Six Thousand One Hundred & Twenty Two and Paise Twenty Only
Quoted Rate in Words		INR Ninety Two Lakh Fifty Six Thousand One Hundred & Twenty Two and Paise Twenty Only					

[Handwritten Signature]
23/10/2020

AGM (Engg E)
CA Sund

Signature Not Verified

Digitally signed by SUNIL KUMAR
KOTIA
Date: 2020.11.03 11:50:02 IST
Location: eProcurement System for
Central PSUs

A.A.I