



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

No: AAM/ENGG/AMED-VIII/2020-21/W.O-1/RC-SplitAC/A-07/2020-21

Dated: 10.06.2020

BY SPEED POST/ email

WORK ORDER

To,

M/s. Volks Energie Pvt Ltd,
306, Bakshi House, 40-41,
Nehru Place, New Delhi-110019.

Name of Work: Rate contract for SITC of Split, Cassette & Tower type Air conditioners, Water coolers and Water Dispensers for various locations at CIA for the period of One year (e-tender ID-2020_AAI_42711_1).

Ref: 1) Your e-tender price bid opened on 03.03.2020.
2) Our email communication dated 10.06.2020.

Dear Sirs,

1. Your e tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the items rates quoted by you totaling to **Rs.35,95,400.00 (Rupees Thirty five Lakhs Ninety five Thousand Four Hundred Only) Plus applicable GST**, which is 4.87 % below the justified cost of Rs.37,79,464.00 (Excluding GST).
2. Joint General Manager (Engineering-Electrical)-II, AMED,AAI, Chennai Airport, shall be the Engineer-in charge of the work. You are requested to attend the office of Jt.Gen.Manager (Engg-Elect)-II, AMED, AAI, Chennai Airport by 30.06.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100/-(Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. The EMD amount of **Rs.75,589.00** submitted by you along with the tender has been converted as part of the Security deposit as per page 4 of 132 of the e-Tender document. Please deposit the balance amount of **Rs.10,55,071.00 (Rupees Ten Lakhs Fifty Five Thousand and Seventy One Only)** towards Security deposit within 10 days from the date of issue of this letter failing which the same will be deducted as per conditions of Clause 1A of Page 16 of 132 of GCC of the tender document.
4. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act and rules thereof Central and State Governments.
5. You are also requested to contact the Asst.Gen.Manager (Engg-Elect) AMED-VIII immediately who will arrange to handover the site to you.

...2....

फैक्स: 044 - 2256 0008 ई पी ए बी एक्स: 2256 0551, चेन्नई हवाई अड्डे, चेन्नई - 600 027.
Fax: 044 - 2256 0008 EPABX: 2256 0551, Chennai Airport, Chennai - 600 027.



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

6. Please note that the time allowed for carrying out the work shall be **12 (Twelve) Months with effect from 01.07.2020.**
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
9. All other terms and conditions shall be as per agreement.

Encl: Work Order Schedule (04 pages).

Yours faithfully,
W. Francis Xavier
10/06/2020

(W.FRANCIS XAVIER)
Jt. General Manager (Engg.-Elect.)-II
AAI, Chennai.

AIRPORTS AUTHORITY OF INDIA
CHENNAI INTERNATIONAL AIRPORT
AIRPORT MAINTENANCE ELECTRICAL DIVISION-VIII

WORK ORDER SCHEDULE

NAME OF WORK : Rate contract for SITC of Split, Cassette & Tower type Air conditioners, Water coolers and Water Dispensers for various locations at CIA for the period of One year.

SI No	Description of Item	Qty	Unit	Rate	Amount
1.00	Supply of following capacity wall mounted type Split AC unit (5 star rating inverter type) fitted with hermetically sealed compressor operating on 220 V +10% 50 Hz Single phase AC supply with evaporator and condensing unit made of copper tubes with aluminium fins i/c cordless remote control, copper piping for both suction and discharge of 4 metres length, power and control cabling of 4 meters length etc complete on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)				
1.01	1.5 TR	8	No	33000.00	2,64,000.00
1.02	2.0 TR	32	No	44000.00	14,08,000.00
2.00	ITC of following capacity wall mounted type Split AC unit including all accessories as per above item complete etc. on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)				
2.01	1.5 TR	8	No	1550.00	12,400.00
2.02	2.0 TR	32	No	1600.00	51,200.00
3.00	SITC of following capacity voltage stabilisers with copper wound coil having range of 200 to 275 voltage single phase, 50 Hz AC supply i/c necessary fixing arrangements, clamps, screws, metal clad top, connecting 3 core cable of 1 metre length, complete, etc on as and when required basis as per specifications complete as required. (Prices quoted by the firm shall be firm from the date of opening of Price Bid till the completion period of the contract)				
3.01	1.5 TR	8	No	2000.00	16,000.00
3.02	2.0 TR	32	No	2500.00	80,000.00
4.00	Supply and Installation of required Angle frame for mounting condensing units of upto 2.0 TR capacity with all accessories etc. etc on as and when required basis as per specifications complete as required. (Prices shall be firm for 1 year period from the date of start of work)	40	Jobs	450.00	18,000.00

AIRPORTS AUTHORITY OF INDIA
CHENNAI INTERNATIONAL AIRPORT
AIRPORT MAINTENANCE ELECTRICAL DIVISION-VIII

WORK ORDER SCHEDULE

NAME OF WORK : Rate contract for SITC of Split, Cassette & Tower type Air conditioners, Water coolers and Water Dispensers for various locations at CIA for the period of One year.

SI No	Description of Item	Qty	Unit	Rate	Amount
5.00	Supply of 4TR capacity ceiling suspended Cassette type AC unit fitted with hermetically sealed compressor operating on 415 V +10% 50 Hz 3 phase AC supply with evaporator and condensing unit made of copper tubes with aluminium fins i/c cordless remote control, Angle iron wall / floor stand for condensing unit, complete etc. on as and when required basis as per specifications complete as required. (Prices shall be firm for 1 year period from the date of start of work)	3	Nos	84000.00	2,52,000.00
6.00	ITC of 4TR capacity ceiling suspended Cassette type AC unit including all accessories as per above item complete etc. on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	3	Jobs	4000.00	12,000.00
7.00	Supply of 4TR capacity Floor standing tower type Split AC unit fitted with hermetically sealed compressor operating on 415 V +10% 50 Hz 3 phase AC supply with evaporator and condensing unit made of copper tubes with aluminium fins i/c cordless remote control, Angle iron floor stand for indoor unit, Angle iron wall / floor stand for condensing unit, etc complete as required. (Prices shall be firm for 1 year period from the date of start of work)	4	Jobs	90000.00	3,60,000.00
8.00	ITC of 4TR capacity Floor standing tower type Split AC unit including all accessories as per above item complete etc, as required. (Prices shall be firm for 1 year period from the date of start of work)	4	Jobs	4000.00	16,000.00
9.00	Supply and Installation of required size copper pipe (beyond 3 meters per unit) for suction and delivery line with all accessories suitable for following capacity ACs i/c Insulation, power & Control cabling etc. on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)				
9.10	1.5 TR Split type AC unit	20	mtr	590.00	11,800.00
9.20	2.0 TR Split type AC unit	100	mtr	600.00	60,000.00
9.30	4.0 TR Cassette / Floor Standing type AC unit	100	mtr	680.00	68,000.00
10.00	Supplying & laying of condensate water drain pipe made of PVC having size of 40mm 6kg/cm capacity, for additional requirement for AC units i/c necessary clamps, screws, supports, etc on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	300	Mtr	130.00	39,000.00

AIRPORTS AUTHORITY OF INDIA
CHENNAI INTERNATIONAL AIRPORT
AIRPORT MAINTENANCE ELECTRICAL DIVISION-VIII

WORK ORDER SCHEDULE

NAME OF WORK : Rate contract for SITC of Split, Cassette & Tower type Air conditioners, Water coolers and Water Dispensers for various locations at CIA for the period of One year.

SI No	Description of Item	Qty	Unit	Rate	Amount
11.00	Supplying & fixing of following sized PVC trunking profile on wall / surface to facilitate installation of copper piping, insulation, power cabling, control cabling, condensate drain water piping and as directed by the Engineer - in - Charge on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)				
11.10	75 X 50 mm	50	Mtr	300.00	15,000.00
11.20	100 X 50 mm	10	Mtr	500.00	5,000.00
12.00	Supplying of following rated Cyclic timer for Split / Tower type air conditioners, suitable for cycle the air conditioners between duty and standby units at predetermined intervals that are settable between 1 to 12 hours, with necessary buttons, display, inbuilt power and control contactors, control circuits, terminals, on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)				
12.10	Cyclic timer for split AC having 2 TR capacity, AC Single Phase power supply (Similar to Model No. A-MCT-02, make of Presevi Industries Pvt Ltd)	20	Nos	1700.00	34,000.00
12.20	Cyclic timer for split AC (Floor standing, Tower type) having 4 TR capacity, AC, 3 Phase power supply.(Similar to Model No. A-MCT-02-AM, make of Presevi Industries Pvt Ltd)	4	Nos	6500.00	26,000.00
13.00	Supply of floor mounted type water cooler having 80 ltr purification capacity (Per hour) and 40 ltr cooling capacity with RO + UV purification, 40 ltr capacity of cooling water tank, 40 ltr capacity of normal water tank, 5 ltr capacity of hot water tank, Stainless steel 304 Grade body, Non-CFC refrigerant, fitted with hermetically sealed compressor operating on 220 V +10% 50 Hz Single phase AC supply with evaporator and condenser made of copper tubes, HOT/ COLD/ NORMAL water taps, necessary piping / hose connections with nearby water source, power cable connections complete etc. on as and when required basis as per technical specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	12	Nos	65000.00	7,80,000.00
14.00	ITC of 80 ltr purification capacity (Per hour) floor mounted type water cooler as per above item on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	12	Jobs	2500.00	30,000.00

AIRPORTS AUTHORITY OF INDIA
CHENNAI INTERNATIONAL AIRPORT
AIRPORT MAINTENANCE ELECTRICAL DIVISION-VIII

WORK ORDER SCHEDULE

NAME OF WORK : Rate contract for SITC of Split, Cassette & Tower type Air conditioners, Water coolers and Water Dispensers for various locations at CIA for the period of One year.

SI No	Description of Item	Qty	Unit	Rate	Amount
15.00	Supply of 20 ltr capacity floor mounted type water dispenser having Stainless Steel 304 Grade / Plastic body, Non-CFC refrigerant, fitted with hermetically sealed compressor operating on 220 V +10% 50 Hz Single phase AC supply with HOT/ COLD/ NORMAL water taps with provision for spill water inbuilt drainage , necessary power / control / piping / hose connections for operation with 20 ltr water can / bottle source, provision to keep the 20 ltr water can/bottle within the unit, complete on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	5	Nos	7000.00	35,000.00
16.00	ITC of 20 ltr capacity floor mounted type water dispenser as per above item on as and when required basis as per specifications complete as required (Prices shall be firm for 1 year period from the date of start of work)	5	Jobs	400.00	2,000.00
				Rs.	35,95,400.00

(Rupees Thirty five Lakhs Ninety five Thousand Four Hundred Only)Plus applicable GST

N. J. K.
10/4/2020
JGM(E-E)-II
AMED,AAI,C.I.A