




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

JAS-ANZ



COIMBATORE INTERNATIONAL AIRPORT

सं.सं.:भा.वि.प्रा./सीबीई/इ-वि/CW-09/W-33/2019-20

Ref. No: AAI/CBE/E-E/CW-09/W-33/2019-20

दिनांक: 12.03.2020

द्रुत डाक द्वारा

BY SPEED POST

सेवा में /To

M/s. C.P.Monchester Electricals,
D-60, Brindhavan Nagar,
Civil Aerodrome Post,
Coimbatore - 641014.

मेल आई.डी / Mail id: cpmonchesterele@gmail.com

Name of Work: Construction of Doppler VHF Omni Range Make: MOPIENS at Coimbatore International Airport. SH: Electrical Works.

संदर्भ / Ref: 1) दि. 02.03.2020 को आपका वित्तीय बोली खोला गया। / Your Financial Bid Opened on

.02.03.2020. (E-bid No: 2020_AAI_42923_1)

महोदय/Dear Sir (s),

- उपर्युक्त कार्य के संबंध में आपका निविदा को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया गया है, मद के लिए आपके द्वारा उद्धृत राशि कुल रू. 35,12,345.00 प्लस जी.एस.टी सेवा कर भी जो न्यायोचित राशि रू. 46,45,297.00. से 24.39 % नीचे। Your E-tender for the above mentioned work is accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to Rs. 35,12,345.00 (Rupees Thirty Five Lakhs Twelve Thousand Three Hundred and Forty Five Only) excluding GST @ 18%, which is 24.39% below the estimated cost put to tender of Rs. 46,45,297.00 excluding GST.
- भा.वि.प्रा, कोयंबतूर अंतरराष्ट्रीय हवाईअड्डा के सहायक संयुक्त महाप्रबंधक (इंजि-वि), इस कार्य के इंजिनियर प्रभारी है। आपसे अनुरोध है कि दि. 21.03.2020 को, भा.वि.प्रा, कोयंबतूर हवाईअड्डा संयुक्त महाप्रबंधक (इंजि-वि), के कार्यालय आए और करार को हस्ताक्षरित करके पूरा करें। अनुबंध एग्रीमेंट गैर न्यायिक स्टॉप कागज मूल्य रू.100.00 (एक सौ मात्र) के लिए निष्पादित करना है और स्टैप कागज का मूल्य आपके द्वारा वहन किया जाएगा। Jt. Gen. Manager (Engg-Elect), AAI, Coimbatore International Airport shall be the Engineer-In- Charge of the work. You are requested to attend the office of the Jt.Gen.Manager (Engg-Elect), AAI, Coimbatore Airport on or before 21.03.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100.00 (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.
- अनुबंध निविदा के पृष्ठ 16 पर धारा के मुताबिक, आपके निविदा के साथ रू. 92,906.00 की अग्रिम राशि पर विचार किया जाएगा और उसे सुरक्षा जमा के एक हिस्से में परिवर्तित कर दिया जाएगा.आपके द्वारा निविदा के साथ सुरक्षा जमा राशि के भाग के रूप में माना जाएगा। यह पत्र जारी के 10 दिनके अंदर रू. 2,58,329.00 को कृपया सुरक्षा राशि के रूप में जमा करें, जमा नहीं किया तो चालू बिलों से उपर्युक्त राशि की कटौती की जाएगी। The Earnest money amount of Rs.92,906.00 (Rupees Ninety Two Thousand Nine Hundred and Six Only) received along with your tender will be treated and converted as part of security deposit as per clause on page no.16 of contract document.

COIMBATORE INTERNATIONAL AIRPORT, COIMBATORE - 641 014

PHONE/FAX: 0422-2571668

Web Site: www.airportsindia.org.in



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



COIMBATORE INTERNATIONAL AIRPORT

Please deposit Rs 2,58,329.00 (Rupees Two Lakhs Fifty Eight Thousand Three Hundred and Twenty Nine Only) as Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills.

4. कृपया ध्यान दें कि कार्य को करने के लिए अनुमत समय 5 महीने का होगा और इस पत्र के जारी होने के 10 वें दिन से इसे फिर से लिया जाएगा।/ Please note that the time allowed for carrying out the work shall be 5 (Five) Months and same shall be reckoned from the 10th day of issue of this letter.
5. कार्य की पूर्णता की तारीख से दोष देयता अवधि 12 (बारह) महीने होगी। The Defects Liability Period shall be 12 (Twelve) months from the date of completion of Work.
6. आपको वरिष्ठ प्रबंधक (इंजीनियरिंग-इलेक्ट्रिकल), भारतीय विमानपत्तन प्राधिकरण, कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे से तुरंत संपर्क करने के लिए निर्देशित किया जाता है, जो आपको साइट सौंपने की व्यवस्था करेगा। You are also directed to contact Sr.Manager (Engg-Elect), AAI, Coimbatore International Airport immediately who will arrange to handover the site to you.
7. आपसे अनुरोध है कि जीएसटीआईएन का जिक्र करते हुए जीएसटी अधिनियम के अनुसार वैध जीएसटी चालान जमा करने का अनुरोध किया जाए, जो कि जीएसटी दरों को लागू करता है और इनपुट टैक्स क्रेडिट विवरण इंगित करता है यदि एआई कोयंबटूर जीएसटी का उल्लेख करने वाले बिलों को संसाधित करने के लिए कोई है 33AAACA6412D1ZF/ You are requested to submit valid GST invoice as per GST act mentioning the GSTIN, indicating the GST rates applicable and input tax credit details if any for processing the bills mentioning the AAI Coimbatore GST no.33AAACA6412D1ZF.
8. अनुबंध के संबंध में कोई और पत्राचार आम तौर पर सहायक को संबोधित किया जाना चाहिए संयुक्त महा प्रबंधक (इ-वि), कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे। Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (Engg-Elect), AAI, Coimbatore International Airport.
9. कृपया इस कार्य आदेश की प्राप्ति को स्वीकार करें। Please acknowledge the receipt of this work order.

अनुलग्नक/Encl: अनुसूची/Schedule 'A'.

12/03/2020

संयुक्त महाप्रबंधक (इ-वि),
Jt. Gen. Manager (Engg-Elect)

COIMBATORE INTERNATIONAL AIRPORT, COIMBATORE - 641 014

PHONE/FAX: 0422-2571668

Web Site: www.airportsindia.org.in

Name of Work: Construction of Doppler VHF Omni Range Make: MOPIENS at Coimbatore International Airport. SH: Electrical Works

Schedule A

Schedule of Quantities

SI No	Item Description	Qty	Unit	Rate	Amount
	Cable laying, SITC of Panel and Earthing				
1	Supplying of following sizes of 1.1 KV grade, XLPE insulated, Aluminium conductor armoured Power Cable conforming to IS 7098 Part-I 1985 with upto date amendments complete as required as per specifications and as per site requirement. 3.5 core, 185 sq.mm	2400	Metre	675.00	1620000.00
2	Laying of one number PVC insulated and PVC sheathed I XLPE power cable of 1.1 kV grade of following size in the existing RCC/ HUME/ duct/ METAL pipe as required. Above 95 upto 185 sq.mm	2400	Metre	45.00	108000.00
3	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size on wall/ surface/cable tray as required. Above 95 upto 185 sq/mm	400	Metre	90.00	36000.00
4	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc..direct in ground (75 cm below ground level) in existing trench etc., complete as required as per site requirement. 90 mm OD and 76 mm ID	2200	Metre	121.00	266200.00
5	Supplying and making end termination with brass single compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 core x 185 sq.mm	8	Set	1,200.00	9600.00
6	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc. in layers of 20 cm, and disposal of surplus excavated soil as directed, within a lead of 50 meter without ramming and watering.	450	cum	360.00	162000.00

Sl No	Item Description	Qty	Unit	Rate	Amount
7	Dismantling bituminous road / concrete manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge etc as required.	5	cum	1500.00	7500.00
8	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level including form work etc as required.	5	cum	4500.00	22500.00
9	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	4	Job	7,000.00	28000.00
10	Supplying and laying 25 mm X 6 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	25	Meter	200.00	5000.00
11	Providing and fixing 6 SWG dia G.I. wire on surface or in recess or ground for loop earthing along with existing cable as required.	2400	Meter	24.00	57600.00
12	SITC of indoor MV Feeder pillar panel with single door arrangement completely made up of i/c internal partitions of 14 SWG CRCA sheet steel, door dust tight, vermin proof, totally enclosed, cubicle type, floor mounting, free standing, including providing and fixing 250A Aluminium Bus bar with all accessories suitable for operation at 415V, 3 phase, 4 wire, 50 Hz A.C. power supply system complete with all accessories, interconnection, connection, earthing, painting, grouting, providing pedestal, cable entry provision etc. as required and comprising the following : a) 100A, 25KA, 4P MCCB with Microprocessor based releases as incomer with R,Y,B,ON,OFF, Trip indication lamps, resin cast CT's with multifunction meter (Schneider EM 6459 or Equivalent)-2 sets as incomer. b) 100A, 25KA, 4P MCCB with Microprocessor based releases as buscoupler with R,Y,B, ON, OFF and three locks two key mechanical interlock- 1 set				

SI No	Item Description	Qty	Unit	Rate	Amount
	c) 63A, 36KA, 4P MCCB with microprocessor based releases with ON, OFF, Trip indication lamps as outgoing with digital ammeter and surge protection Device (class C, Type-2) - 4 sets. As outgoing. d) Spare compartment suitable for providing switch gear with all necessary arrangements etc complete as required - 2 Nos. e) Provision for feeding Mobile DG 30 KVA supply plug point for emergency purpose-1 No. f) Primary surge protection : Supply, installation, Testing & commissioning of Block MOV based surge Divertor (BMOVSD) 100 KA, 3 phase, 4 wire class-B, Qty-1 g) Secondary protection : Supply, Installation, Testing & commissioning of Block MOV based surge divertor 40KA, 3 phase, 4 wire class-B, Qty-1. h) With all necessary accessories including DSITC of suitable isolating switch gear of appropriate rating for surge protectors etc, complete as required.	1	Job	300,000.00	300000.00
	Internal Wiring				
13.01	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 volts, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required. 8 way (4 + 24), Metal door	3	Job	14,000.00	42000.00
13.02	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 volts, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required. 4 way (4 + 8), Metal door	4	Job	9,900.00	39600.00
14	Supplying and fixing following way, single pole and neutral, sheet steel, IP54 MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 2 + 6 way, Double door	3	Job	2,500.00	7500.00

Sl No	Item Description	Qty	Unit	Rate	Amount
15	Supplying and fixing Four Pole 63 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	4	Each	2,000.00	8000.00
16	Supplying and fixing Triple pole 6 to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	6	Each	1,200.00	7200.00
17	Supplying and fixing Double pole 6 to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	11	Each	700.00	7700.00
18	Supplying and fixing 6 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	26	Each	180.00	4680.00
19	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required) 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	120	Meter	90.00	10800.00
20	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required) 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	120	Meter	126.00	15120.00
21	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required a) 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	230	Meter	126.00	28980.00
22	Supply and Installation of PVC Trunking of size 100mmx50mm including all accessoires like jointing sleeve, junction box, end cover,external/internal corner, coupler etc required for the complete installation on wall as required.	60	Meter	360.00	21600.00

SI No	Item Description	Qty	Unit	Rate	Amount
23	Supplying and fixing suitable size GI box with glossy modular cover plate and base frame in front on surface or in recess, including providing and fixing 3/6 pin 5/6 amps modular socket outlet and 5/6 amps modular switch with ISI mark, connection etc. as required.	12	Each	360.00	4320.00
24	Supplying and fixing suitable size GI box with glossy modular cover plate and base frame in front on surface or in recess, including providing and fixing ISI marked 3/6 pin 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	18	Each	450.00	8100.00
25	Supplying and fixing suitable size of 6 module GI box with glossy modular cover plate and base frame in front on surface or in recess, including, connections etc. as required. (For light plugs to be used in non residential buildings).	8	Job	360.00	2880.00
26	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	12	Each	90.00	1080.00
27	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.(Group B)	31	Each	900.00	27900.00
28	Supply and installation of outdoor type 45W, LED Luminaire of min 4950 lumens fitted with white colour LED suitable to operate 230V, 50Hz AC supply with surge protection, providing the required cable, termination and providing suitable mounting arrangements on the wall using 40 mm dia GI pipe of suitable length with necessary welding, conduiting, junction boxes etc. complete as required .	7	Each	2700.00	18900.00
29	Supply and installation of surface /recess mounting type 25/28W, 2'x2' LED type Luminaire of min 2800 lumen output fitted with white colour LED suitable to operate 230V, 50Hz AC supply on the ceiling including driver unit with suitable mounting arrangements etc. as required.	11	Each	2100.00	23100.00
30	Supply of 18W LED; 6000-6500K, (4 ft.) with LED lamp & batten for LED tube (single) made of extruded aluminium with heat sink provided for efficient heat dissipation & integrated electronic driver suitable for operation on 220V, 50 Hz AC supply etc. as required.	8	Each	1,200.00	9600.00

SI No	Item Description	Qty	Unit	Rate	Amount
31	Supply of Energy saving new generation 10W LED bulkhead luminaire with opal diffuser for operation on 220V, 50 Hz AC supply or equivalent complete as required.	5	Each	900.00	4500.00
32	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent / LED fitting of all types, complete with all accessories and tube/driver etc. directly on ceiling / wall, including connection with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	31	Each	150.00	4650.00
33	Supply and installation of 380 mm sweep high quality plastic Exhaust fan which is resistant to colour change having anti-static properties, with minimum speed of 1200 rpm, air delivery of minimum 850CMM, suitable for mounting on wall for operation on 220V, 50 Hz AC supply or equivalent in AAI approved make in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.Upto 450 mm sweep of complete as required.	3	Each	3,600.00	10800.00
34	Supply Installation, testing and commissioning of 1200mm sweep high quality Ceiling fan of 5 star rated, which is resistant to colour change having anti-static properties for operation on 220V, 50 Hz AC supply or equivalent in AAI approved make, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FR PVC insulated , copper conductor, single core cable etc. as required. complete as required.	3	Each	2,000.00	6000.00
35	Supplying and fixing single module stepped type electronic fan regulator on the existing modular plate switchbox including connections etc. as required.	3	Each	360.00	1080.00
36	Supplying & fixing suitable size CRCA sheet steel enclosure with provision to mount MCB/Isolator or other devices including connection etc. as required.	7	Job	600.00	4200.00


Sl No	Item Description	Qty	Unit	Rate	Amount
37	SITC of high wall mounted inverter type split air-conditioning units having capacity of 1.5 TR with 5 Star rating of inverter (variable speed) technology suitable for operation on 230V, 50Hz, AC supply, complete with of non-ductable indoor unit with remote control and outdoor unit having copper condenser coil with aluminium fins, standard length of refrigerant piping (minimum 5 mtrs) suitable size interconnecting cabling, drain piping, first charge of refrigerant, providing raised platform / MS stand for outdoor units etc complete as required.	6	Job	50000.00	300000.00
38	Supply and fixing of automatic electronic 4 KVA voltage stabilizer suitable for 1.5 TR Split Air conditioners having an input range of 170-270V with high/low voltage cut off, intelligent timer, including making connection from the MCB enclosure etc complete as required	6	Job	2700.00	16200.00
Fire Alarm and Detection					
39	Supply, installation, testing and commissioning of conventional type Photoelectric smoke detectors (UL Listed) along with mounting base with unique optical sensing chamber, visible LED's, complete with all accessories including connections etc. as required.	7	Job	2700.00	18900.00
40	Supply, installation, testing & commissioning of conventional type Heat Detector (UL listed) with standard base, accessories like base, base box, visible LEDs etc. to install under/above false ceiling, roof and concealed space etc.complete as required as per specification.	2	Job	2700.00	5400.00
41	Supply, installation, testing and commissioning of weather proof conventional type manual call point (UL Listed) complete with all accessories including connections etc. as required.	1	Job	4,500.00	4500.00
42	Supply, installation, testing and commissioning of Response Indicator on false ceiling etc complete as required.	3	Job	500.00	1500.00
43	Supplying and fixing of 19/20 mm B class steel conduit along with all fittings and accessories in surface/recess including painting using red colour incase of surface conduit, or cutting the wall and making good the same in case of recessed conduit etc complete as required.	85	Metre	150.00	12750.00
44	Supplying and drawing of 2 X 1.5 Sqmm FRLS insulated copper conductor single core cable in the existing surface/ recessed steel conduit/flexible conduit, including terminations etc complete as required.	85	Metre	45.00	3825.00

SI No	Item Description	Qty	Unit	Rate	Amount
45	Supply, installation, testing and commissioning of conventional type Fire detection & alarm control panel having minimum of 2 zones for connecting smoke detectors, manual call points, Hooters etc suitable for operation on 220 Volts, 50 Hz AC power supply, LED indicators to indicate fire and normal operation & power supply status, push button for accept and Reset, maintenance free batteries with minimum 1 hour backup on alarm mode & 8 hours on normal operation mode with battery charger etc., shall be complete as required. Panel shall have necessary provision for connecting and functioning with auto dialer etc as required.	1	Job	15,000.00	15000.00
46	Supply, installation, testing and commissioning of auto dialer with all necessary accessories including connections, modules if any required for integrating with Addressable/Conventional Fire Alarm Panels etc complete as required	1	Job	7,000.00	7000.00
47	Supplying, installation, testing & commissioning fire alarm sounder with facility to make announcement, in weather proof box with hinged cover plate & suitable for operation with amplifier i/c line matching transformer etc. complete as required.	1	Job	3500.00	3500.00
Water Cooler, Pumps and allied works					
48	SITC of Water dispensers of capacity 75 LPH (or) better with 3 nos Faucets for Normal , Cold and hot water, SS body, suitable for operation on single phase, 230V, 50HZ AC power supply, with stainless steel tank, energy efficient compressor, condenser fan, heat transfer coil with aluminium fins, thermostat etc, provided with inbuilt UV purification system of capacity 25 LPH (or) better with minimum six stage purification including other accessories like auto flush, low pressure switch, automatic level control etc as required.	1	Job	45,000.00	45000.00
49	Supply of water proof PVC insulated PVC sheathed copper conductor flat cable of 3 Core x 4.00 sq. mm of 1.1KV grade suitable for laying along with GI pipe for inter connecting submersible pump etc., complete as required.	120	Mtr	90.00	10800.00
50	Supply of 50 mm dia B class GI pipe	200	Mtr	410.00	82000.00

Sl No	Item Description	Qty	Unit	Rate	Amount
51	SITC of 3.00 HP/2.2 KW multistage submersible motor pump set consisting of submersible water filled squirrel cage motor suitable for operation on 440V, 50Hz, 3 Phase AC supply with impellers, water lubricated bearings, tie-bars on studs bolts for connecting the pumps together suction casing, sleeve coupling to connect motor shaft to the pump shaft, installation lowering of submersible pump alongwith GI pipe (departmentally supplied) of appropriate length as per site conditions with all including necessary couplings, accessories, laying of 3 core 4 sq.mm flat cable of departmentally supplied, providing borewell cover etc. , installing the sluice valve of suitable dia complete as required to give a minimum discharge of 24 LPM at a total head of 220 Meters or as per site conditions along with all accessories complete as required (Make : KSB Model No. KS4H-3007 or its equivalent from approved makes).	1	Job	35000.00	35000.00
52	SITC of DOL starter in CRCA enclosure suitable for 3.00 HP submersible pump with start stop button, Over Load relay, single phase preventer, dry run protector, Water level controller, Ammeter with selector switch, indication lamp for RYB and Motor ON along with interconnections, cabling with suitable length copper armoured cable of 4 x 10 Sq.mm from the panel to pump panel, including all civil works etc., as required.	1	Job	8280.00	8280.00
				Total	3512345.00

(Rupees Thirty Five Lakhs Twelve Thousand Three Hundred and Forty Five Only)

(Excluding GST @ 18%)


12/08/2020
Jt.Gen. Manager (E-E)

Signature Not Verified

Digitally signed by SHIVA KUMAR GUNDA
Date: 2021.06.28 16:21:14 IST
Location: eProcurement System for Central PSUs