



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
TRICHY AIRPORT



No:AAI/TRY/ENGG(C)/CSR/ANNAI SCHOOL(C.WALL)/20-21/30

Date: 08-06-2020

To

M/s.M. Mani,

9/3A, 6th Street, Palani Nagar, K.K. Nagar (P.O), Trichy - 620021.

Email : mmconstn@gmail.com, Mobile : 94439 49007.

Name of work: Construction of Boundary wall (Under CSR) at Annai Higher secondary school, Wireless road, Trichy Airport - reg.

Ref: Your e-Bid Ref No.AAI/TRY/ENGG(C)/CSR/ANNAI SCHOOL(C.WALL),
Tender ID : 2020_AAI_44010_1 opened on 27-05-2020.

Dear Sir,

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the Item Rates quoted by you totaling to **Rs.7,03,278/- (Rupees Seven Lakhs Three Thousand Two Hundred and Seventy Eight only) Plus applicable GST.**
2. The Asst. General Manager (Engg-Civil), AAI, Trichy Airport shall be the Engineer-In-Charge of the work. You are requested to attend the office of Asst. General Manager (Engg-Civil) on (or) before 18-06-2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. The Earnest Money amount of Rs.20,000/- (Rupees Twenty Thousand only) received along with your tender in the form of Demand Draft will be treated as part of Security Deposit as per Clause 1 A of Clauses of Contract on Page No.36 of contract document. Please deposit Rs.50,500/- (Rupees Fifty Thousand and Five Hundred Only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1 A of Clauses of Contract on Page No.36 of contract document.
4. You are requested to comply with the Provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and minimum wages Act & Rules there of Central and State Governments.
5. You are requested to comply with all provisions of the Employees Provident Fund and miscellaneous provisions Act 1952 and Employees State Insurance Act 1948, amended from time to time and rule framed there under wherever applicable.




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
TRICHY AIRPORT



6. You are also directed to contact Manager (Engg-Civil) immediately who will arrange to hand over the site to you for the commencement of work.
7. The letters under reference shall form part of Agreement.
8. Please note that the time allowed for carrying out the work shall be **02(Two) Months only** and **same shall be reckoned from the 10th day after issue of this letter.**
9. Any further correspondence in connection with contract should normally be addressed to the Engineer-In-Charge.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Thanking you,

Yours faithfully,


8/6/2020

(A. Venkateshiah),
AGM (Engg-Civil),
For and On Behalf of Chairman,
Airports Authority of India.

Encl: Schedule of Quantities.

सहायक प्रमुख (इंजी-सिविल) / Asst. General Manager (E-C)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
त्रिचय एअरपोर्ट / Trichy Airport
त्रिचय / Trichy - 620 007

Item Rate BoQ

Tender Inviting Authority: Assistant General Manager (Engg-Civil)

Name of Work: Construction of Boundary wall (Under CSR) at Annai Higher secondary school, Wireless road, Trichy Airport.

Contract No: Tender Ref No : AAI/TRY/ENGG(C)/CSR/ANNAI SCHOOL(C.WALL), Tender ID: 2020_AAI_44010_1)

Name of the Bidder/ Bidding Firm / Company :	M MANI TRICHY					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Providing and erecting 2.00 metre high temporary barricading at site as per drawing/ direction of Engineer-in-Charge which includes writing and painting, arrangement for caution such as "Caution -work in Progress" during construction at site for day and night, glow lamps, reflective signs, marking, flags, caution tape as directed by the Engineer-in- Charge. The barricading provided shall be retained in position at site continuously i/c shifting of barricading from one location to another location as many times as required during the execution of the entire work till its completion. Rate include its maintenance for damages, painting, all incidentals, labour materials, equipments and works required to execute the job. The barricading shall not be removed without prior approval of Engineer-in-Charge. (Note :- One time payment shall be made for providing barricading from start of work till completion of work i/c shifting. The barricading provided shall remain to be the property of the contractor on completion of the work).	45.00	meter	1260.00	56700.00	INR Fifty Six Thousand Seven Hundred Only
2	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge a) In cement mortar	19.00	Cum	810.00	15390.00	INR Fifteen Thousand Three Hundred & Ninety Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
3	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. a) In cement mortar	6.00	Cum	900.00	5400.00	INR Five Thousand Four Hundred Only
4	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) All kinds of soil	50.00	Cum	243.00	12150.00	INR Twelve Thousand One Hundred & Fifty Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) / M-Sand : 8 graded stone aggregate 40 mm nominal size)	3.00	Cum	4500.00	13500.00	INR Thirteen Thousand Five Hundred Only
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	2520.00	Kg	70.20	176904.00	INR One Lakh Seventy Six Thousand Nine Hundred & Four Only
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level a) Thermo-Mechanically Treated bars of grade Fe-500 D or more.	240.00	Kg	70.20	16848.00	INR Sixteen Thousand Eight Hundred & Forty Eight Only
8	Centering and shuttering including strutting, propping etc. and removal of form for all heights. a) Foundations, footings, bases of columns, etc. for mass concrete.	87.00	Sqm	270.00	23490.00	INR Twenty Three Thousand Four Hundred & Ninety Only
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights. a) Lintels, beams, plinth beams, girders, bressumers and cantilevers.	23.00	Sqm	360.00	8280.00	INR Eight Thousand Two Hundred & Eighty Only
10	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a) 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) / M-Sand : 3 graded stone aggregate 20 mm nominal size).	22.00	Cum	6300.00	138600.00	INR One Lakh Thirty Eight Thousand Six Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
11	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	29.00	Cum	126.00	3654.00	INR Three Thousand Six Hundred & Fifty Four Only
12	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement a) 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) / M-Sand : 3 graded stone aggregate 20 mm nominal size).	2.00	Cum	7200.00	14400.00	INR Fourteen Thousand Four Hundred Only
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand / M-Sand)	8.00	Cum	5400.00	43200.00	INR Forty Three Thousand Two Hundred Only
14	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : a) Cement mortar 1:6 (1 cement : 6 coarse sand / M-Sand)	11.00	Cum	5760.00	63360.00	INR Sixty Three Thousand Three Hundred & Sixty Only
15	Centering and shuttering including strutting, propping etc. and removal of form for all heights. a) Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	12.00	Sqm	360.00	4320.00	INR Four Thousand Three Hundred & Twenty Only
16	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : a) 1:2:4 (1 Cement : 2 coarse sand / M-Sand : 4 graded stone aggregate 20 mm nominal size).	2.00	Cum	6300.00	12600.00	INR Twelve Thousand Six Hundred Only
17	15 mm cement plaster on rough side of single or half brick wall of mix: a) 1:6 (1 cement: 6 coarse sand / M-Sand)	101.00	Sqm	243.00	24543.00	INR Twenty Four Thousand Five Hundred & Forty Three Only
18	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 coarse sand / M-Sand)	101.00	Sqm	225.00	22725.00	INR Twenty Two Thousand Seven Hundred & Twenty Five Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
19	6 mm cement plaster of mix : a) 1:3 (1 cement : 3 fine sand / M-Sand)	42.00	Sqm	225.00	9450.00	INR Nine Thousand Four Hundred & Fifty Only
20	Finishing walls with Acrylic Smooth exterior paint of required shade : a) New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	244.00	Sqm	81.00	19764.00	INR Nineteen Thousand Seven Hundred & Sixty Four Only
21	Conducting soil test SPT at two location of the proposed site, accessing the soil strata and finding SBC (Soil bearing capacity) of the soil. Submission of soil investigation report of SBC from ,National Institute of Technology (NIT),Trichy	1.00	Job	18000.00	18000.00	INR Eighteen Thousand Only
Total in Figures					703278.00	INR Seven Lakh Three Thousand Two Hundred & Seventy Eight Only
Quoted Rate in Words		INR Seven Lakh Three Thousand Two Hundred & Seventy Eight Only				

Signature Not Verified

Digitally signed by VENKATASESHIAIAH A
Date: 2020.06.08 14:07:02 IST
Location: eProcurement System for Central PSUs

