



संख्या: भा0वि0प्रा0/वारा0/स0म0प्र0अभि0(विद्युत)/W-2/2020-21/6535-43/
Ref :- AAI / VNS / AGM Engg.(E) /W-2/2020-21 /

दिनांक: 03.08.2020
Date: 03.08.2020

सेवा में,

मेसर्स सौरभ इन्टरप्राइजेज,
पुरा-रघुनाथपुर, बाबतपुर,
वाराणसी-221006.

To,

M/s Saurabh Enterprises,
Pura-Raghunathpur, Babatpur,
Varanasi-221006.

कार्य का नाम:- प्रॉविजन ऑफ कोल्ड स्टोरेज फॅसिलिटी एण्ड मिसलिनियस इलेक्ट्रिकल वर्क्स ईटीसी. कार्गो कामप्लेक्स ऐट एल.बी.एस.आई. एयरपोर्ट वाराणसी।

Name of work:- Provision of Cold storage facility & Miscellaneous Electrical works etc cargo Complex at LBSI Airport Varanasi.

संदर्भ:-ई-निविदा (2020_AAI_44745_1) खोलने का दिनांक 20.05.2020

Ref:- Your Tender ID (2020_AAI_44745_1) opened on 20.05.2020

प्रिय महोदय, Dear Sir,

- उपरोक्त कार्य के लिए रुपये 22,21,220.00 (जीएसटी रहित) (रुपये बाईस लाख इक्कीस हजार दो सौ बीस मात्र) की मद दर निविदा, जो कि कार्य की (न्याय संगत) लागत रुपये 22,96,420.00 (रुपये बाईस लाख छानबे हजार चार सौ बीस मात्र) से 3.27% (तीन दशमलव दो सात प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।
- Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you, totaling to Rs. 22,21,220.00 (excluding GST) (Rupees Twenty Two Lacs Twenty One Thousand Two Hundred & Twenty Only) which is 3.27% (Three Point Two Seven Percent) below the justified cost of Rs. 22,96,420.00 (Rupees Twenty Two Lacs Ninety Six Thousand Four Hundred Twenty Only)
- संयुक्त महाप्रबन्धक (अभि0-वि0) भा.वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय हवाई अड्डा, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा सहायक महाप्रबन्धक (अभि0-वि0)/प्रबन्धक (अभि0-वि0) उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 10 अगस्त 2020 तक संयुक्त महाप्रबन्धक (अभि0-वि0) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।
- Jt. General Manager (Engg.-E) AAI, LBSI Airport, Varanasi shall be the Engineer-in-charge of the work and Asstt. General Manager (Engg.-E) / Manager (E-E), shall be the authorized representative of Engineer-in-charge. You are requested to attend the office of Jt. General Manager Engg. (E) AAI, LBSI Airport, Varanasi by 10.08.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100.00 (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.

शेष पृष्ठ 2 पर



पृष्ठ - 2 / 3

3. निविदा के साथ प्राप्त धरोहर राशि रुपये 45,928.00 (रुपये पैतालीस हजार नौ सौ अठाईस मात्र) संविदा प्रपत्र के अनुच्छेद अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 1,76,194.00 (रुपये एक लाख छिहत्तर हजार एक सौ चौरनबे मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की पृष्ठ संख्या 16 के शर्त संख्या 1ए के अनुसार चालू लेखा बिलो से की जाएगी।
3. The earnest money amount of Rs.45,928.00 (Rupees Forty Five Thousand Nine Hundred Twenty Eight Only) received along with your tender will be treated and converted as a part of Security Deposit. Please deposit Rs.1,76,194.00 (Rupees One Lac Seventy Six Thousand One Hundred Ninety Four Only) towards balance Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bill as per conditions of clause no. 1A on page 16 of Clause of Contract of contract document.
4. आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
4. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments with upto date amendments.
5. आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से प्रबन्धक (अभि0-वि0), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय हवाई अड्डा, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौपने की व्यवस्था करेंगे।
5. You are also directed to contact Manager (Engg.-E), AAI, LBSI Airport, Varanasi immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि तीन (03) माह है जो कि 12/08/2020 से प्रभावी मानी जाएगी।
6. Please note that the time allowed for carrying out the work period is Three (03) months and the same shall be reckoned from 12/08/2020.
7. संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः संयुक्त महाप्रबन्धक (अभि0-वि0), भा. वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय हवाई अड्डा, वाराणसी को सम्बोधित करें।
7. Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (E-E), AAI, Lal Bahadur Shastri International Airport, Varanasi.
8. कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

शेष पृष्ठ 3 पर

ओवर्



पृष्ठ - 3/ 3

- 9 उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
9 In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

संलग्नक- यथोपरि

Encl:- As above I

भवदीय

03/08/2020

कृते अध्यक्ष

सहायक महाप्रबंधक (अभि0-विद्युत)

For and on behalf of the chairman, AAI

Asstt. General Manager (Engg,-E)

सहायक महाप्रबंधक अभियांत्रिकी (विद्युत)

Asstt. General Manager Engg. (E)

भा.वि.प्रा., ला.ब.शा. अन्तर्राष्ट्रीय हवाई अड्डा, वाराणसी

A.A.I., L.B.S. International Airport, Varanasi

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: Asstt. General Manager (Engg.-E), LBSI Airport Varanasi.

Name of Work : Provision of Cold storage facility & Miscellaneous Electrical works etc cargo Complex at LBSI Airport Varanasi.

Contract No: 2020_AAI_44745_1

Name of the Bidder/ Bidding Firm / Company :		SAURABH ENTERPRISES PURA-RAGHUNATHPUR BABATPUR VARANASI.				
<u>PRICE SCHEDULE</u> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE in Figures excluding GST (To be entered by the Bidder) Rs. P.	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	SITC of cold storage facility at Varanasi Airport as per following specifications Cold Room size: Cold Room size shall be nominal dimension of Approx 4.7mtr length x 4.7mtr width x 3.6 mtr height capable of storage of average 5000kg/day. Products to be stored: The cold room shall be suitable for storage of Vegetables, Fruits & Flowers Desired temperature to be achieved in the cold room: The cold room temperature is to be maintained between +2°C to +8°C while the ambient temperature is 45°C. The pull down time shall be 24 hrs. Digital temperature indicator cum controller shall be provided Insulation: The wall and ceiling panel shall be of 60mm thick cyclopentane PUF insulated panels with prepainted G.I finish. The floors shall be of 60 mm thick floor panel with Marine ply 12 mm & AL. chaqured plate 1.2mm Refrigeration: The refrigeration units shall have 40000 BTU/Hr capacity 2 number(One working and 01 standby) to maintain the desired temperature of +2°C as required for number of door opening approx 10-20 times per hour each for 15 to 30 sec. The refrigeration used shall be of R-404A. The condensing unit shall be of outdoor air cooled with required copper piping and to be fixed either in the outer wall of walk in cooler unit or as per site requirement Power supply suitable for operation of 4wire 3phase 415V, 50Hz: The power supply will be provided by the AAI upto the brick wall near the walk in cooler unit. The necessary power cord shall be supplied by the successful tenderer upto the cooling units (approx. 5mtrs) Internal Lighting: Required number of lights shall be provided inside the walk in cooler with suitable switch arrangements for ON/OFF. Earthing: The walk in cooler units should be properly earthed with nearest available earth point ITC: The job includes installation, testing and commissioning of standalone type walk-in cold storage panels along with installation support for condensing unit/evaporating unit including zero Level flooring for panel erection fixing of copper pipes, charging of gas, cabling, termination, etc complete as required.	1	Job	825000.00	825000.00	INR Eight Lakh Twenty Five Thousand Only
2	Supply of following 1.1KV grade aluminim conductor XLPE insulated/PVC sheathed armoured cable as per IS 7098 (Part I) 1988 as required. a) 4C X 25 Sqmm	500	Mtr	160.00	80000.00	INR Eighty Thousand Only

Signature


NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE In Figures excluding GST (To be entered by the Bidder) Rs. P.	TOTAL AMOUNT Rs. P.	TOTAL AMOUNT In Words
3	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. a) 4C X 25 sq. mm.	2	Each	350.00	700.00	INR Seven Hundred Only
4	Supplying and fixing 4 way, MCCB+12 module Double door prewired vertical type TP&N distribution board(x.160 h3 MCCB incomer) of steel sheet for 415 volts on surface/ recess complete with, dust protected, duly powder painted, inclusive of 160 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's, terminal connectors for all incoming and outgoing circuits, duly prewired with adequate size of FR PVC insulated copper conductor upto the terminal connector/ neutral link, earthing etc as required (But without MCCB/ RCCB/ Isolator)	1	Each	10000.00	10000.00	INR Ten Thousand Only
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. a) Upto 35 sq. mm	36	Mtr	10.00	360.00	INR Three Hundred & Sixty Only
6	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. a) Upto 35 sq. mm	26	Mtr	10.00	260.00	INR Two Hundred & Sixty Only
7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/HDPE pipe as required. a) Upto 35 sq. mm	250	Mtr	10.00	2500.00	INR Two Thousand Five Hundred Only
8	Laying of HDPE/MS Pipe direct in underground at depth of upto 60 cm below ground level including excavation and refilling of soil/concrete and refilling it as required at site.	200	Each	50.00	10000.00	INR Ten Thousand Only
9	Supplying and fixing 100 amps rating, four pole, 415 volts, 25KA thermal magnetic MCCB in the existing MCCB DB complete with connections, testing and commissioning etc. as required.	1	Each	4800.00	4800.00	INR Four Thousand Eight Hundred Only
10	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole(5to 32A)	6	Each	200.00	1200.00	INR One Thousand Two Hundred Only
11	Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple pole(32A)	2	Each	800.00	1600.00	INR One Thousand Six Hundred Only

Signature

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE In Figures excluding GST (To be entered by the Bidder) Rs. P.	TOTAL AMOUNT Rs. P.	TOTAL AMOUNT In Words
12	Supply and fixing of 3phase 4wire KWh / energy meter counter type with a rating of 50-100A suitable for 415 volts on surface mounted complete with all accessories etc. as required.	1	Each	3800.00	3800.00	INR Three Thousand Eight Hundred Only
13	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required.	2	Each	4000.00	8000.00	INR Eight Thousand Only
14	Providing & fixing of 6 SWG GI wire on surface or in the recess for loop earth.	40	Mtr	20.00	800.00	INR Eight Hundred Only
15	Supply of 3core 4Sqmm Flexible Cu Cable complete as per site Requirement.	500	Mtr	110.00	55000.00	INR Fifty Five Thousand Only
16	Supply of (BEE 5 Star) 2.0 TR high wall type split Inverter Air Conditioner unit with rotary compressor operating on refrigerant R-32/Non CFC & Copper condensor coil of outdoor unit & having cordless LCD remote,auto restart operation with copper refrigerant gas pipeline insulated with nitrile/polythene foam i/c electrical cable of suitable size copper conductor from indoor to outdoor unit (both upto 3 mtr) i/c standard drain pipe,MS base frame / platform duly epoxy painted for outdoor units for operation on 230V , 50 Hz single phase AC supply and capable of performing such standard function like cooling, dehumidifying,air circulating, filtering etc complete as required.	15	Each	44000.00	660000.00	INR Six Lakh Sixty Thousand Only
17	Supply of (BEE 5 Star) 1.5 TR high wall type split Inverter Air Conditioner unit with rotary compressor operating on refrigerant R-32/Non CFC & Copper condensor coil of outdoor unit & having cordless LCD remote,auto restart operation with copper refrigerant gas pipeline insulated with nitrile/polythene foam i/c electrical cable of suitable size copper conductor from indoor to outdoor unit (both upto 3 mtr) i/c standard drain pipe,MS base frame / platform duly epoxy painted for outdoor units for operation on 230V , 50 Hz single phase AC supply and capable of performing such standard function like cooling, dehumidifying,air circulating, filtering etc complete as required.	9	Each	36000.00	324000.00	INR Three Lakh Twenty Four Thousand Only
18	Supply Installation, Testing & commissioning of 5 KVA automatic voltage stabilizer for given output voltage of single phase 230+/- 10%, AC supply for the input single phase supply voltage range of 170 V to 270 V, single phase, 50 Hz, AC supply.	24	Each	2800.00	67200.00	INR Sixty Seven Thousand Two Hundred Only
19	Supplying & installation of 25 mm dia PVC hard Drain pipe complete with all accessories and fittings etc. as required.	200	Mtr	120.00	24000.00	INR Twenty Four Thousand Only

अभि

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE In Figures excluding GST (To be entered by the Bidder) Rs. P.	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
20	Installation, Testing & Commissioning of up to 1.5/2.0 TR capacity split Air-Conditioners comprising of wal / floor mounting type indoor evaporator unit, outdoor condensor unit and fixing of refrigerant piping with insulation, suitable size power cable between indoor and outdoor unit (upto length of 3 metre) and including initial charging of refrigerant gas etc as required.	24	Each	1500.00	36000.00	INR Thirty Six Thousand Only
21	Supply fixing of Extra copper piping(beyond 3.0 meter) between the indoor and outdoor units with insulation, gas charging etc. complete as required.	75	Mtr	600.00	45000.00	INR Forty Five Thousand Only
22	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required (2 X 4 sq. mm + 1 X 4 sq. mm earth wire)	100	Mtr	220.00	22000.00	INR Twenty Two Thousand Only
23	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	24	Each	1000.00	24000.00	INR Twenty Four Thousand Only
24	Supply of 50 mm outer dia PE-80 HDPE Pipe suitable to lay in underground as per IS 4984/95 duly ISI marked. Should withstand minimum pressure of 6 Kg/cm ² .	200	Mtr	75.00	15000.00	INR Fifteen Thousand Only
Total in Figures					2221220.00	INR Twenty Two Lakh Twenty One Thousand Two Hundred & Twenty Only
Quoted Rate in Words		INR Twenty Two Lakh Twenty One Thousand Two Hundred & Twenty Only				


 03/08/2020
 सहायक महाप्रबन्धक अभियांत्रिकी (विद्युत)
 Asstt. General Manager Engg. (E)
 भा.वि.प्रा., ला.ब.शा. अन्तर्राष्ट्रीय हवाई अड्डा, वाराणसी
 A.A.I., L.B.S. International Airport, Varanasi

Signature Not Verified

Digitally signed by RAMESHWAR GAUTAM
 Date: 2020.08.04 16:11:04 IST
 Location: eProcurement System for Central PSUs

