



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या : भा.वि.प्रा/उ.पू.क्षे./व.प्रबंधक(अभि-सि)/चौड़ी सड़क/जोरहाट/वर्क अर्डर- /20-21
Ref. No.: AAI/NER/SM(E-C)/Widening Road/JHT/W. O- 6 /20-21 / 8086

दिनांक:
Date: 24.07.2020

सेवा मे, / To,

मेसार्स: येरूल हुसैन
M/s. Yerool Hussain
चिन्मय पथ / Chinmay Path
लखीमी नगर / Lakhimi Nagar
हतीगाँव, कामरूप (M) / Hatigaon, Kamrup(M)
गुवाहाटी, असम / Guwahati, Assam
पिन / PIN- 781006

विषय:- "जोरहाट एयरपोर्ट के एयर साइड में व्हीकलिक लेन और विविध सिविल कार्य का चौड़ीकरण।"
Sub: - " Widening of Vehicular Lane & miscellaneous civil works at Air side of Jorhat Airport."

निविदा आई. दि: / Tender ID: 2020_AAI_45261_1

आपकी संदर्भ तकनीकी बोली 18.06.2020 और वित्तीय बोली 26.06.2020 को CPP पोर्टल के माध्यम से खोली गई।
Reference your technical bid opened on 18.06.2020 and financial bid opened on 26.06.2020 through CPP Portal.

महोदय /Sir (s),

- उपर्युक्त विषय से संबंधित कार्य के लिए आपकी निविदा, इसके अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के द्वारा संलग्न अनुसूची के अनुसार आपके द्वारा उद्धृत मददर जिसकी कुल राशि रु 37,10,271/- (जी. एस. टी के बिना)(रुपये छियालीस लाख छियासी हजार नौ सौ पंचानवे मात्र) जो कि टेंडर डाला गया अनुमानित राशि रु 42,08,000/- से 15.22% (प्रतिशत) कम है, इस पत्र द्वारा स्वीकार की जाती है।
Your Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at item rates quoted by you totaling to **Rs. 37,10,271/- (Excl. GST)** (Rupees Forty-Six Lakh Eighty-Six Thousand Nine Hundred Ninety-Five only) which is **15.22% below** the estimated cost of **Rs. 42,08,000/-** put to tender.
- वरिष्ठ प्रबंधक (अभि-सि), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र, इस कार्य के इंजीनियर प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु इस पत्र के जारी किये जाने के 10 (पंद्रह) दिनों के भीतर वरिष्ठ प्रबंधक (अभि-सि), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र के कार्यालय में उपस्थित हों। संविदा करार रु.100/- (सौ रुपये मात्र) के न्यायिकेतर (नॉन ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।
Sr. Manager (E-C), AAI, RHQ, NER, shall be the Engineer-in-Charge of the work. You are requested to attend office of the Engineer-in-charge i.e. **Sr. Manager (E-C)**, AAI, RHQ, NER **within 10 (Ten) days** from the date of issue of this letter, to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
- आपके निविदा के साथ प्राप्त रु 84,160/- (रुपये चौरासी हजार एक सौ साठ मात्र) की अग्रिम धन राशि को संविदा दस्तावेज के पृष्ठ 16 एन आई टी पर जी सी सी पर दी गई शर्त 1 (A) के अनुसार सुरक्षा जमा के हिस्से के रूप में परिवर्तित कर दिया गया है। कृपया इस पत्र के जारी होने के 10 दिन के भीतर शेष प्रतिभूति जमा के रूप में रु 2,86,867/- (दो लाख छियासी हजार आठ सौ सड़सठ मात्र) जमा करें अन्यथा इस राशि की कटौती संविदा दस्तावेज (पृष्ठ 17) एन आई टी पर जी सी सी पर दी गई शर्त 1 (A) के अनुसार आपके चालु बिलों से काट ली जाएगी।
The earnest money amount of **Rs. 84,160/- (Rupees Eighty-Four Thousand One Hundred Sixty only)** received along with your Tender has been converted as part of security deposit as per Clause no. 1 (A) of GCC on page no. 17 of contract document. Please deposit **Rs. 2,86,867/- (Rupees Two Lakh Eighty-Six Thousand Eight Hundred Sixty-Seven only)** towards security deposit within 10 (Ten) days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause No. 1 (A) of GCC (page no. 17) in tender document.



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

4. आपसे अनुरोध है कि संविदा श्रमिक (विनियमन एवं समापन) अधिनियम 1970 और संविदा श्रमिक (विनियमन एवं समापन केन्द्रीय नियमावली 1971, अधिन, केन्द्रीय और राज्य सरकार के न्यूनतम मजदूरी अधिनियम और ई.पी.एफ.एक्ट, 1952 एवं ई. एस. आई. एक्ट नियमों का पालन करें।

You are requested to comply with provision of Contract Labour (Regulation and Abolition) Act of 1970 and contract (Regulation and Abolition) Central rules 1971, Minimum Wages Act & Rules, EPF Act, 1952 and ESI act thereof Central & State Governments.

5. आपको निर्देश दिए जाते हैं कि आप प्रबंधक (अभि-सिविल), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपर्द करने की व्यवस्था करेंगे।
You are also directed to contact Manager (E-C), AAI, RHQ, NER immediately who will arrange to hand over the site to you.

6. काम के प्रारंभ के लिए लामबंदी / तैयारी गतिविधियों को शुरू करने के लिए आपसे अनुरोध कर रहे हैं। कृपया यह नोट कर लें कि काम करने का समय 5 (पांच) दिन मानसून के मौसम के लिए 02 (दो) महीने शामिल हैं, जिसे इस पत्र के जारी होने की तारीख से 3 दिन बाद से गिना जाएगा।
You are here by requested to start mobilization/preparatory activities for the commencement of work. Please note that the time allowed for carrying out the work shall be 5 (Five) Months i/c 02 (Two) months for Monsoon season, and the same shall be reckoned from the 10th day from the issue of this letter.

7. संविदा के संबंध में आगे किया जाने वाला पत्राचार सामान्यतः इंजीनियर प्रभारी से किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत हस्ताक्षर करके हमें वापस भेजें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.
9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।
In case any discrepancy is found, then English version will be taken as correct.

धन्यवाद/ Thanking you.

भवदीय / Yours faithfully,

22/07/2020

Encl:

1. Schedule of Quantities
ऑफ क्वान्टिटी

अजीत कुमार साहा) / (Ajit Kumar Saha)
वरिष्ठ प्रबंधक (अभि-सि) / Sr. Manager (E-C)
भा. वि. प्रा., क्षे.मु. उ.पू. क्षे. गुवाहाटी . शिञ्जुल
AAI, RHQ, NER, Guwahati.

Schedule of Quantity

Name of work: "Widening of Vehicular Lane & miscellaneous civil works at Air Side of Jorhat Airport."

Item No	Description of item	Unit	Qty.	Quoted Rate (Rs) Exclusive GST	Amount (Rs)
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	Sqm	460.00	199.00	91540.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil	Cum	210.00	189.00	39690.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level: a) 1:5:10 (1 Cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	Cum	35.00	5119.00	179165.00
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : a) 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	4.00	7999.00	31996.00
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	Cum	15.00	7999.00	119985.00
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :	Cum	3.00	7999.00	23997.00
7	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete	Sqm	45.00	100.00	4500.00
8	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	30.00	399.00	11970.00
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	70.00	399.00	27930.00
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	1900.00	69.00	131100.00
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	400.00	79.00	31600.00
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	125.00	8199.00	1024875.00
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in super structure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	16.00	8199.00	131184.00
14	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	Sqm	100.00	449.00	44900.00
15	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	Sqm	135.00	229.00	30915.00
16	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	Sqm	150.00	249.00	37350.00
17	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	Sqm	300.00	299.00	89700.00
18	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and i/c priming coat of exterior primer applied @ 2.20 kg/10 sqm).	Sqm	300.00	179.00	53700.00
19	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	Cum	25.00	6999.00	174975.00
20	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in- Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	Cum	45.00	3129.00	140805.00
21	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification i/c premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of EIC.	Cum	45.00	5499.00	247455.00

21/07/20
SMCC

Item No	Description of item	Unit	Qty.	Quoted Rate (Rs) Exclusive GST	Amount (Rs)
22	Construction of dry lean cement concrete sub base over a prepared subgrade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10Mpa at 7days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of EIC	Cum	30.00	5699.00	170970.00
23	Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building, for all heights and all levels etc. i/c a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium items. The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete, as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the EIC. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm.	Sqm	120.00	1899.00	227880.00
24	Providing and laying 400 micron thick polythene white sheet antifriction layer on the base course complete as per specification with specified overlap between adjacent strip and transverse joints as per direction of Engineer-in-charge	Sqm	270.00	89.00	24030.00
25	Providing, laying and fixing in position closed -cell, cross linked, pre-moulded, compressible, high performance joint filler board at expansion joints in concrete slab wherever specified and shown in the drawing as per specifications and direction of the EIC, complete in all respects- 20 mm thick	Sqm	6.00	399.00	2394.00
26	Providing and filling expansion joints with approved polysulphide joint sealing compound (confirming to grade BS:5212-1983) i/c painting the sides of slab upto a depth of 20mm with approved appropriate primer to receive the specified sealing compound, providing and applying bond breaking tape on top edges of joint to prevent accident spillage of sealant on top surface and to give a neat finish to the sealant has been applied and tooled, all complete as per specification and direction of EIC.	Metre	15.00	449.00	6735.00
27	Providing and laying pavement quality concrete of producing by batching plant having a minimum work test beam flexural strength of 41kg/cm ² at 28 days using not less than 340 Kg of Cement per cum of concrete, coarse sand and graded stone aggregates of 40mm nominal size in appropriate proportions as per specified design criteria and job mix formula approved by the EIC, in airfield pavements laid in panels with necessary dummy/construction/expansion joints as per drawing or as directed by EIC, mechanically vibrated using fixed form paver or steel form work sturdy channels as per technical specification and providing 400 microns thick polythene sheet as antifriction layer over 6mm thick fine sand layer, curing and providing & filling construction joints and dummy joints with approved polysulphide joint sealing compound (conforming to grade BS:5212, 1983) i/c rounding off edges, priming the concrete surface with approved primer and filling the groove 10mm X 10mm deep at top for construction joints and 10mm X 10mm deep at top for dummy joints with approved polysulphide joint sealing compound, the balance depth of dummy joint if any, being filled with expanded polyethylene filler board (Armour board) i/c providing and applying bond breaker (Polyethylene tape) on Armour board top surface, i/c preparing the surface and applying masking tape on front edge of joint to prevent accidental spillage of sealant on top surface and to give neat finish to the sealant and removing the masking tape after sealant has been applied and tooled and necessary arrangements for expansion joints etc. complete. Note: - Antifriction layer and expansion joint to be paid for separately.	Cum	70.00	8699.00	608930.00
	Sub Total of Revenue Works				37,10,271.00
	Grand Total				37,10,271.00

(Rupees Thirty Seven Lakh Ten Thousand Two Hundred Seventy One only.)

Signature Not Verified

Digitally signed by AJIT KUMAR SAHA
Date: 2020.07.28 13:21:05 IST
Location: eProcurement System for Central PSUs