



Ref. No: AAI/HUB-BLY/ENGG-E/AC/2020-21/WO-01/1243-54

Date: 01.08.2020

सेवा में/To

मेसर्स वोल्क एनर्जी प्राइवेट लिमिटेड, / M/s. Volks Energie Pvt. Ltd,  
306, बखशी हाउस 40-41, / 306, Bakshi House 40-41,  
नेहरू प्लेस, दिल्ली / Nehru Place, Delhi,  
दिल्ली - 110019 / Delhi-110019.


कार्यकानाम/ Name of Work:- एमएसएसआर स्टेशन बेल्लारी में नए प्रतिष्ठानों के लिए एसी यूनिट, आरओ वाटर प्यूरीफायर इनबिल्ट वाटर कूलर का प्रावधान। / Provision of AC Units, RO water Purifier with inbuilt water cooler for new installations at MSSR Station Bellary.

संदर्भ/ Ref: 1) AAI Tender Id :-2020\_AAI\_47958\_1

2) Your E-Tender (Financial Bid) opened on 25.06.2020

महोदय/Dear Sir,

1. अध्यक्ष, भा वि प्रा की ओर से उपरोक्त कार्य हेतु आपकी निविदा को कुल बातचीत की गई राशि रु. 4,44,000.00 (Excluding GST) (केवल चार लाख चवालीस हजार रुपए), जीएसटी छोड़कर जो अनुमानित लागत रु.4,82,488 लाख से 7.97% नीचे है, एतद् द्वारा स्वीकार किया जाता है।  
Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 4,44,000.00 (Rupees Four Lakhs Forty-Four Thousand Only) which is **7.97% Below** the estimated cost put to tender of Rs. 4,82,488.00 (Rupees Four Lakhs Eighty-Two Thousand Four Hundred and Eighty-Eight Only) Excluding GST.
2. सहायक महाप्रबंधक (इंजिनियरिंग-विद्युत) एएआई, हुबल्लि हवाई अड्डा इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने के लिए निर्धारित दिनांक 12.08.2020 तक सहायक महाप्रबंधक (इंजी- विद्युत) भा.वि.प्रा, हुबल्लि हवाईअड्डा, हुबल्लि के कार्यालय में उपस्थित हों। संविदा करार को रुपये 100/- (केवल एक सौ रुपए) मूल्य के एक गैर न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर के मूल्य को आपके द्वारा वहन किया जाएगा

  
01/08/2020



Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi shall be the Engineer -In-Charge of the work. You are requested to attend the office of Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi by 12.08.2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees Hundred Only) and the cost of the stamp paper shall be borne by you.

3. रुपये 9,650.00 की बयाना राशि (केवल नौ हजार छह सौ पचास रुपये) जो आपकी निविदा के साथ प्राप्त हुयी है को संविदा दस्तावेज़ के पृष्ठ संख्या एनआईटी-2 खंड सं. 14 की शर्त के अनुसार प्रतिभूति राशि के भाग के रूप में परिवर्तित कर लिया जाएगा। इस पत्र के जारी होने की तारीख के बाद दस दिनों के भीतर सुरक्षा जमा की ओर रु. 34,750.00 की कुल जमा करें, अन्यथा अनुबंध दस्तावेज़ के पृष्ठ संख्या जीसीसी-16 पर अनुबंध के खंड 1-ए के अनुसार बकाया सुरक्षा राशि को चालू बिलों में से काटा जायेगा

The Earnest Money Amount of Rs.9,650.00 (Rupees Nine Thousand Six Hundred and Fifty Only) received along with your tender will be treated and converted as part of security deposit as per Clause 9 of SCC of page No SCC-2 of contract document. Please deposit Rs.34,750.00 (Rupees Thirty-Four Thousand Seven Hundred and Fifty Only) towards security deposit within 10 days after the date of issue of this letter, failing which the same will be deducted as per condition of Clause 1-A of page GCC-19 of contract document.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970, ठेका श्रम (विनियमन एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार और विनियमन का अधिनियम) के प्रावधानों का पालन करने का अनुरोध किया जाता है सेवा की शर्तें) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण अधिनियम 1996, जैसा कि केंद्र और राज्य सरकारों के निविदा और 55 जीसीसी के नियमों के पृष्ठ संख्या 49 पर खंड - 19 में निर्दिष्ट है।

You are requested to comply with the provisions of contract labor (Regulation and abolition) act of 1970 and contract labor (Regulation and abolition) Central rules 1971, Child labor (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other construction workers welfare Cess Act 1996 as specified in Clause-19 on Page No.54 to 60 of GCC of tender and rules of Central and State Governments.

21/08/2020



5. आपको यह भी निदेश दिए जाते हैं कि आप सहायक महाप्रबंधक (इंजिनियरिंग-विद्युत), हुबबल्ली हवाई अड्डा, हुबबल्ली से तुरंत संपर्क करें जो आपको साइट सौंपने के लिए व्यवस्था करे  
You are also directed to contact Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि इस कार्य को पूरा करने की अवधि **02 (दो) महीने** होगी जो इस पत्र के जारी होने की तारीख के बाद 10 वें दिन से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be **02 (Two) Months** and same shall be reckoned from the 10<sup>th</sup> day after issue of this letter.

7. अनुबंध के संबंध में किसी भी अन्य पत्राचार को आम तौर पर प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineering-In-charge.

8. कृपया पावती भेजें एवं इस पत्र के साथ संलग्न इसकी प्रतिलिपि पर हस्ताक्षर करते हुए उसे स्वीकृति के तौर पर अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as token of acceptance.

भवदीय/Yours faithfully,

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg. – Elect)  
कृते एवं अध्यक्ष की ओर से/ For and on behalf of the Chairman,  
भा.वि.प्रा/ Airports Authority of India,  
हुबबल्ली हवाई अड्डा/ Hubballi Airport, Hubballi

संलग्न/ Encl:

1. Schedule-

## Schedule of Quantity

**कार्यकानाम/ Name of work :** एमएसएसआर स्टेशन बेल्लारी में नए प्रतिष्ठानों के लिए एसी यूनिट, आरओ वाटर प्यूरीफायर इनबिल्ट वाटर कूलर का प्रावधान।/ Provision of AC Units , RO water Purifier with inbuilt water cooler for new installations at MSSR Station Bellary.

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Qty. | Rate     | Amount    |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|----------|-----------|
| 1        | Supply, Installation, Testing and Commissioning of 1.5TR Inverter type 5 star rated Split Air-conditioner of wall mounting type with indoor unit made of low smoke, non-flammable material, consisting of non-ductable type room units (fan coil) with cord less LCD type remote control and one number out door condensing unite suitable for operation on single phase, 230 +/- 10% volts, 50HZ, AC supply including fixing the outdoor unit on a fabricated MS stand/wall Bracket/Brick foundation as per the site requirement and fixing of Indoor room unit. Providing and making interconnections between room unit and condensing unit upto a length of 05 mtrs. Comprising of the following including first charge of refrigerent etc, as required. (Note: as per AAI approved make)<br>a) 1/2" dia. Insulated copper pipe - Liquid line<br>b) 1/4" dia. Insulated copper pipe - Suction line<br>c) 4 x2.5sqmm copper conductor cable between indoor and outdoor units.<br>d) 1" drain PVC pipe<br>e) Suitable size of PVC flexible pipe for covering the refrigerant line of above (a) , (b) & (c) | Each | 7    | 42000.00 | 294000.00 |
| 2        | Supply and fixing additional set of 1/2" and 1/4" copper pipe line and 4X2.5 Sqmm PVC insulated PVC sheathed copper conductor cable from the indoor units to outdoor on the wall surface/cable tray using suitable clamp etc. complete as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Mtr. | 35   | 600.00   | 21000.00  |
| 3        | Supplying,installations, Testing and commissioning of wall mounting type , 4 KVA capacity ,single phase ,automatic line volatage stablizer suitable for operation on 170 volts to 270 volts AC Input,200 to 240 Volts AC out put single phase, 50Hz AC power supply with built in time delay , cut off and low voltage cut off, input/out put/trip indications and suitable for operation of 1.5 Ton Air conditioning Unit etc as required.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Each | 7    | 2000.00  | 14000.00  |

  
01/08/2020

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Qty. | Rate     | Amount   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|----------|----------|
| 4        | Supply of RO water purifier (RO+UV+UF) Domestic model with 45litre per hour filtering capacity and having 10-12 litre water storage capacity . with inbuilt water cooler with Hot, Cold and Normal Water Dispenser Suitable for operation on 240 V AC, 50HZ and recommended to use for Municipal water, Borewell water, Water from tankers (Make:Aquaguard Hot & Cold RO+UV Water Purifier/ or equivalent ) | Each | 2    | 38000.00 | 76000.00 |
| 5        | Supplying and fixing 20 Amps., 240 volts, SPN industrial type, socket outlet, with 2 pole and earth metal enclosed plug top alongwith 20 Amps., 'C' Series, SP MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet, and complete with connections, testing and commissioning etc. as required. (Note: as per AAI approved make)                          | Each | 7    | 2000.00  | 14000.00 |
| 6        | Wiring for light / power plug with 2x4 sq.mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1no. 4 sq.mm FRLC PVC insulated copper conductor single core cable for loop earthing as required.                                                                                                                                                           | Mtr. | 100  | 250.00   | 25000.00 |

**Total Amount (Excluding GST) 444000.00**

**(Rupees Four Lakhs Forty Four Thousand Only)**

**Note: Terms and conditions as per Work Order.**

  
01/10/2020

**सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg. – Elect)**

**भा.वि.प्रा/ Airports Authority of India,**

**हुबबल्ली हवाई अड्डा/ Hubballi Airport, Hubballi**

**Signature Not Verified**

Digitally signed by ANILDAS BEKAL  
Date: 2020.10.28 15:13:03 IST  
Location: eProcurement System for Central PSUs