



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



No:AAI/TRY/ENGG(C)/ILS/20-21/103

Date: 26-08-2020

To

M/s.M. Soundararajan Contractor,

2/42A, Lal Bagathur Sasthiri Street, Gandhi Salai, South Kattur,
Trichy - 620 019.

Mobile: 80724 38375, Email: msoundar69@gmail.com

Name of work: Construction of Glide path Hut, Localizer Hut, Localizer Plat form and other associated Civil works at operational area in Trichy Airport.

S.H: Civil works - reg.

Ref: Your e-Bid Ref No.AAI/TRY/ENGG(C)/ILS/20-21, Tender ID: 2020_AAI_51537_1 opened on 18-08-2020.

Dear Sir,

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the Item Rates quoted by you totaling to **Rs.40,10,395/- (Rupees Forty Lakhs Ten Thousand Three Hundred and Ninety Five only) Plus applicable GST.**
2. The Asst. General Manager (Engg-Civil), AAI, Trichy Airport shall be the Engineer-In-Charge of the work. You are requested to attend the office of Asst. General Manager (Engg-Civil) on (or) before 05-09-2020 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. The Earnest Money amount of Rs.1,03,100/- (Rupees One Lakh Three Thousand and One Hundred only) received along with your tender in the form of Demand Drafts will be treated and converted as part of Security Deposit as per Clause 1 A of Clauses of Contract on Page No.36 of contract document. Please deposit Rs.2,98,000/- (Rupees Two Lakhs Ninety Eight Thousand Only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1 A of Clauses of Contract on Page No.36 of contract document.
4. You are requested to comply with the Provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and minimum wages Act & Rules there of Central and State Governments.



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



5. You are requested to comply with all provisions of the Employees Provident Fund and miscellaneous provisions Act 1952 and Employees State Insurance Act 1948, amended from time to time and rule framed there under wherever applicable.
6. You are also directed to contact Manager (Engg-Civil) immediately for the commencement of work.
7. The letters under reference shall form part of Agreement.
8. Please note that the time allowed for carrying out the work shall be **05 (Five) months only** and **same shall be reckoned from the 10th day after issue of this letter.**
9. Any further correspondence in connection with contract should normally be addressed to the Engineer-In-Charge.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Thanking you,

Yours faithfully,
/ Sd /-
(R. Prabakaran),
AGM (Engg-Civil),
For and On Behalf of Chairman,
Airports Authority of India.

Encl: Schedule of Quantities.

N.O.O:

Copy to: For Information please.

1. GM (Engg-Civil), AAI, SR, Chennai - 27.
2. Airport Director, AAI, Trichy - 07.
3. Jt. GM (Vigilance), AAI, SR, Administrative Building, Chennai - 27.
4. Jt. GM (Engg-Civil), AAI, SR, Chennai - 27.
5. DGM (CNS), AAI, Trichy - 07.
6. AGM (Engg-Elect), AAI, Trichy - 07.
7. SM (Fin), AAI, Trichy - 07.
8. Manager (Engg-Civil), AAI, Trichy - 07.
9. JE(Engg-Civil), AAI, Trichy - 07.
10. Labour Enforcement Officer, Office of Labour Enforcement,
510/A, McDonalds Road, Trichy - 620 001.

P. Prabakaran
(R. Prabakaran),
AGM (Engg-Civil),
For and On Behalf of Chairman,
Airports Authority of India.

सहायक महाप्रबंधक (इंजी-सिविल) / Asst. General Manager (Engg-Civil)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
त्रिचिवी इवाई अड्डा / Trichy Airport
त्रिचिवी / Trichy - 620 007

Item Rate BoQ

Tender Inviting Authority: Assistant General Manager (Engg-Civil), AAI, Trichy International Airport, Trichy - 620 007.

Name of Work: Construction of Glide path Hut, Localizer Hut, Localizer Platform and Other associated Civil works at operational area in Trichy Airport. SH: Civil works.

Contract No: Tender Ref No: AAUTRY/ENGG(C)/ILS/20-21, Tender ID: 2020_AAI_51537_1

M.SOUNDARARAJAN CONTRACTOR TRICHY											
PRICE SCHEDULE											
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)											
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	RATE Excluding GST in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words					
1	2	3	4	5	6	7					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) All kinds of soil	310.00	Cum	190.00	58900.00	INR Fifty Eight Thousand Nine Hundred Only					
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	205.00	Cum	210.00	43050.00	INR Forty Three Thousand & Fifty Only					
3	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	25.00	Cum	1250.00	31250.00	INR Thirty One Thousand Two Hundred & Fifty Only					
4	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 mAll kinds of soil.	500.00	Sqm	65.00	32500.00	INR Thirty Two Thousand Five Hundred Only					
5	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	1800.00	Sqm	5.00	9000.00	INR Nine Thousand Only					

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. p	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)..	15.00	Cum	5500.00	82500.00	INR Eighty Two Thousand Five Hundred Only	
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	200.00	Cum	5250.00	1050000.00	INR Ten Lakh Fifty Thousand Only	
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	200.00	Cum	4700.00	940000.00	INR Nine Lakh Forty Thousand Only	
9	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	100.00	per 50 kg cement	45.00	4500.00	INR Four Thousand Five Hundred Only	
10	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a) 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	13.00	Cum	6350.00	82550.00	INR Eighty Two Thousand Five Hundred & Fifty Only	
11	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Foundations, footings, bases of columns, etc. for mass concrete.	250.00	Sqm	350.00	87500.00	INR Eighty Seven Thousand Five Hundred Only	
12	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Suspended floors, roofs, landings, balconies and access platform	30.00	Sqm	380.00	11400.00	INR Eleven Thousand Four Hundred Only	
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	1350.00	Kg	87.00	117450.00	INR One Lakh Seventeen Thousand Four Hundred & Fifty Only	
14	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in: a) cement mortar 1:4 (1 cement : 4 coarse sand)	120.00	Sqm	520.00	62400.00	INR Sixty Two Thousand Four Hundred Only	

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE Excluding GST in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	
15	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	55.00	Kg	125.00	6875.00	INR Six Thousand Eight Hundred & Seventy Five Only	
16	Providing and fixing bolts including nuts and washers complete.	55.00	Kg	135.00	7425.00	INR Seven Thousand Four Hundred & Twenty Five Only	
17	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete. a) Size of Tile 500x500 mm	65.00	Sqm	1210.00	78650.00	INR Seventy Eight Thousand Six Hundred & Fifty Only	
18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes a) 110 mm diameter	5.00	metre	350.00	1750.00	INR One Thousand Seven Hundred & Fifty Only	
19	15 mm cement plaster on rough side of single or half brick wall of mix: a) 1:6 (1 cement: 6 coarse sand)	120.00	Sqm	182.00	21840.00	INR Twenty One Thousand Eight Hundred & Forty Only	
20	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	25.00	Cum	825.00	20625.00	INR Twenty Thousand Six Hundred & Twenty Five Only	
21	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. a) In cement mortar.	3.00	Cum	620.00	1860.00	INR One Thousand Eight Hundred & Sixty Only	
22	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	310.00	Sqm	152.00	47120.00	INR Forty Seven Thousand One Hundred & Twenty Only	

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
SL. No.	Item Description	Quantity	Units	RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	
23	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	700.00	Sqm	725.00	507500.00	INR Five Lakh Seven Thousand Five Hundred Only	
24	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	130.00	Sqm	125.00	16250.00	INR Sixteen Thousand Two Hundred & Fifty Only	
25	Providing and fixing pre-fabricated structure puf Panels of 60mm thick in wall and 50mm thick in roof with core of rigid foam of density 40kg/m and joints of panels sealed with a bead of silicone including truss, pillar, purlin at 1 meter span, etc complete as per enclosed drawing and the directions of Engineer in-charge. (Area of Wall and roof to be measured.)	250.00	Sqm	2750.00	687500.00	INR Six Lakh Eighty Seven Thousand Five Hundred Only	
Total in Figures					4010395.00	INR Forty Lakh Ten Thousand Three Hundred & Ninety Five Only	

Signature Not Verified

Digitally signed by PRABAKARAN R

Date: 2020.08.27 14:30:56 IST

Location: eProcurement System for Central PSUs