



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं:- भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर/2020-21

दिनांक: 30/09/2020

सेवा में,

मैसर्स सोगानी इलेक्ट्रिकल्स,
753, आचार्यों का रास्ता,
किशनपोल बाजार,
जयपुर - 302003
ई-मेल - sele753@yahoo.co.in

M/s Sogani Electricals,
753, Achariyon Ka Rasta,
Kishanpole Bazar,
Jaipur -302003
E-mail - sele753@yahoo.co.in

विषय :- अदर मिसलेनियस इलेक्ट्रीकल वर्क एट किशनगढ़ एयरपोर्ट, अजमेर।
Subject:- "Other Miscellaneous Electrical Work at Kishangarh Airport, Ajmer."

संदर्भ:- दिनांक 14/08/2020 को खोली गई आपकी ई-निविदा (वित्तिय बिड)।
Ref:- Your E-Tender opened on dated 14/08/2020 (Financial Bid).

महोदय,

1. Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 4,43,650/-** (Rupees Four Lac Forty Three Thousand Six Hundred Fifty only) which is **16.51% below** the justified cost of **Rs. 5,31,409/-**
2. Asstt. General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Asstt. G.M. (Engg-E) by **29.10.2020** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of **Rs. 100/-** (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
3. The earnest money amount of **Rs. 10,630/-** (Rupees Ten Thousand Six hundred Thirty only) received along with your E-tender has been converted as part of security deposit as per clause 1A of tender document. Please deposit **Rs. 33,735/-** towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of the tender document.
4. You are requested to comply with the provision of Contract Labour (Regulation & abolition) Act of 1970, Contract Labour (Regulation & abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.
5. You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.

30/09



6. Please note that the time allowed for carrying out the work shall be **Three Months** & same shall be reckoned from 10th day after the date of issue this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

Enclosure :- BOQ Page 1 to 3.

भवदीय / Yours Faithfully,

[Handwritten Signature]
30/09/2020

(आर.के. मीणा) / (R.K. Meena)

सहायक महाप्रबंधक (अभि०-वि०) / Asstt. Gen. Mgr. (Engg.-E)
कृते तथा ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

प्रतिलिपि:

1. निदेशक विमानपत्तन, भा.वि.प्रा., किशनगढ़ हवाईअड्डा, अजमेर ।
2. संयुक्त महाप्रबंधक (अभि.-वि.), भा.वि.प्रा., जयपुर हवाई अड्डा, जयपुर।
3. वरिष्ठ महाप्रबंधक (वित्त), भा.वि.प्रा., जयपुर हवाई अड्डा, जयपुर।
4. प्रबंधक (अभि.-वि.), भा.वि.प्रा., किशनगढ़ हवाईअड्डा, अजमेर।

Tender Inviting Authority: Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work: Other miscellaneous electrical work at Kishangarh Airport, Ajmer.

Tender ID: 2020_AAI_53217_1

Name of the Bidder/ Bidding Firm /		M/S SOGANI ELECTRICALS, JAIPUR								
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)										
NUMBER #	TEXT #	Quantity	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	TEXT #	
1	2	4	5	13		53			55	
1	Design and supply of taxiway guidance sign board of various sizes made out of 2 mm thick anodised aluminium frame with suitable angle support, 1.5 mm thick aluminium backcover, 4 mm thick polycarbonate sheet with glare free face, screen printed letter & symbol on self adhesive vinyl film with required colouring & applied on the inside face of polycarbonate sheet, frangible legs, breakable coupling, mounting plates, clamps, uniformly internally illuminated with required LEDs to achieve illumination level, converter suitable for operation on 2.8 A to 6.6 A series airfield lighting circuit without flickering, change over circuit, internal wiring, water tight & locking arrangement etc, grouting of each mounting leg by providing & laying 1:2:4 (1 Cement : 2 Coarse sand : 3 graded stone aggregate 20mm nominal size) cement concrete foundation of size 400 mm (L) x 400 mm(W) x 400 mm(D) including excavation, shuttering & centering, refilling, leveling etc, fixing of coupling through anchor bolts, secondary cable laying, connection to isolating transformer, testing and commissioning etc complete as required and meeting ICAO Annex 14 specifications. (Isolating transformer and secondary cable shall be supplied by AAI).	3	Sqmt	51000.00		153000.00	INR One Lakh Fifty Three Thousand	Only		

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2	Design and supply of three sided aircraft stand identification sign board of approximate size 800mm x 600mm made out of 2 mm thick aluminium frame with suitable angle support, 1.5 mm thick aluminium backcover, 4 mm thick polycarbonate sheet with glare free face, screen printed letter & symbol on self adhesive vinyl sheet applied on the inside face of polycarbonate sheet, water tight & locking arrangement, uniformly internally illuminated with required LEDs to achieve illumination level, convertor/driver, operate without flickering on single phase 230 V, 50 Hz AC supply, installation of sign on existing GI pole with help of supporting structure, connection, testing and commissioning etc complete as required and meeting ICAO Annex 14 specifications.	2	Each	24000.00	48000.00	INR Forty Eight Thousand Only
3	Design and supply of aircraft stand coordinates sign board of approximate size 1000mm x 500mm made out of 2 mm thick aluminium frame with suitable angle support, 1.5 mm thick aluminium backcover, 4 mm thick polycarbonate sheet with glare free face, screen printed letter & symbol on self adhesive vinyl sheet applied on the inside face of polycarbonate sheet, water tight & locking arrangement, uniformly internally illuminated with required LEDs to achieve illumination level, convertor/driver, operate on single phase 230 V, 50 Hz AC supply without flickering, installation of sign on existing GI pole with help of supporting structure, connection, testing and commissioning complete as required and meeting ICAO Annex 14 specifications.	2	Each	20000.00	40000.00	INR Forty Thousand Only
4	Supply of weather proof IP66 thermoplastic cable junction box suitable for termination of 2x6 sqmm armoured cable including one number 6 A, 10 kA, DP MCB, connector kit etc and fixing on 4" dia existing GI pole by clamps, bolts, nuts etc complete as required.	3	Each	4800.00	14400.00	INR Fourteen Thousand Four Hundred Only
5	SITC of LED illuminated (Kishangarh in English) fascia signage for air side of Kishangarh Airport made out of 3mm thick acrylic sheet, 3mm thick ACP sheet cut letters of 36" height, laser cutting, embossing, pasting, transportation etc. complete as per site requirement.	1	Job	80000.00	80000.00	INR Eighty Thousand Only
6	SITC of LED illuminated fascia "AAI logo" signage for air side of Kishangarh Airport made out of 3mm thick double acrylic cut logo of 36" height, laser cutting, embossing, pasting, transportation etc. complete as per site requirement.	1	Job	25000.00	25000.00	INR Twenty Five Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	TEXT #		
7	SITC of LED illuminated mandatory and informative signages for "Drinking Water" of 30"x12" size made out of acrylic sheet with vinyl, machine cutting box type in matching with existing LED signages complete as per site requirement.	3	Each	4800.00	14400.00	INR Fourteen Thousand Four Hundred Only			
8	Supply of 2 C 6 Sq.mm, 1.1 KV grade XLPE insulated, PVC sheathed, armoured aluminium conductor power cable conforming to IS 7098 (Part I) amended upto date.	150	Mtr	75.00	11250.00	INR Eleven Thousand Two Hundred & Fifty Only			
9	Supply and laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) DWC HDPE pipe ISI marked alongwith all accessories like socket, bend, couplers etc. conforming to IS 14930, part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	200	Mtr	160.00	32000.00	INR Thirty Two Thousand Only			
10	Laying of one number PVC insulated and PVC sheathed / XLPE power / AFL cable of 1.1/5 KV grade of following size in the existing RCC/ HUME/ METAL/ HDPE pipe as required. Upto 35 sqmm.	200	Mtr	18.00	3600.00	INR Three Thousand Six Hundred Only			
11	Supplying and making end termination with brass compression gland and aluminium lugs for 2C 6 sqmm PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	6	Each	100.00	600.00	INR Six Hundred Only			
12	Supply and erection of 100 mm Dia medium class GI pole of 3 meter height, duly painted with aluminium paint of approved brand and having MS base plate of suitable size, in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	2	Each	5200.00	10400.00	INR Ten Thousand Four Hundred Only			
13	Supplying & Drawing of 3 C 2.5 sqmm 1.1 KV grade PVC insulated, PVC sheathed, copper conductor flexible power cable in pipe/surface etc completed as required.	50	Mtr	120.00	6000.00	INR Six Thousand Only			
14	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	200	Mtr	25.00	5000.00	INR Five Thousand Only			
Total in Figures					443650.00	INR Four Lakh Forty Three Thousand Six Hundred & Fifty Only			
Quoted Rate in Words						INR Four Lakh Forty Three Thousand Six Hundred & Fifty Only			