



चंडीगढ़ इंटरनेशनल एयरपोर्ट लिमिटेड

Chandigarh International Airport Limited

संदर्भ :- चियाल/अभि. (वि.) / पेरिशेबल कार्गो / डब्ल्यू.ओ.-08/2020-21/19345-353
Ref. No.: CHIAL/Engg.(E)/Perishable Cargo/WO-08/2020-21/

दिनांक: 02.12.2020

Date : 02.12.2020

Speed Post

सेवा में,

मैसर्स स्मार्ट कूल सिस्टम्स प्रा. लि.,
एस.सी.एफ. नं.- 23, फर्स्ट फ्लोर, फेस- 6,
सेक्टर- 56, एस.ए.एस. नगर,
मोहाली, पंजाब।

To,

M/s Smart Cool systems pvt. Ltd.
SCF no. 23, First Floor, Phase 6,
Sector 56, SAS Nagar,
Mohali, Punjab.

Name of Work :- SITC of refrigeration units for Perishable Cargo building at Chandigarh International Airport Limited, Mohali(2020-21).

Ref. i) Your e-tender opened on **02.11.2020 (Tender ID No. 2020_AAI_59637_1)**.

Sir,

1. Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Chandigarh International Airport, Mohali at the item rates quoted by you totaling to **Rs. 19,89,667/- (Rs. Nineteen Lacs Eighty Nine Thousand Six Hundred and Sixty Seven Only)** (exclusive of GST), which is 11.98% below the justified cost put to tender for **22,60,543/- (Exclusive of GST)**.
2. HOD (Engg/Elect), Chandigarh International Airport Ltd. (Mohali) shall be Engineer-in-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf and attend the office of the Asstt. General Manager (Engg-Elect), Chandigarh International Airport, (Mohali) by within 15 days to sign and complete the agreement. The contract agreement shall be executed on a non – judicial stamp paper of value Rs.100/- and the cost of the stamp paper shall be borne by you.
3. The earnest money amount of Rs. 45,300/- (Rs. Forty Five Thousand and Three Hundred Only) received along with your EMD has been converted as part of security deposit as per terms and conditions of the contract document. Please deposit Rs. 1,53,667/- (Rupees One Lacs Fifty Three Thousand Six Hundred and Sixty Seven Only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your bills as per condition of the contract document.
4. You are requested to comply with the provision of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof central and state governments with up to date amendments.
5. You are also directed to contact Asstt. General Manager (Engg-Elect), Chandigarh International Airport Ltd, Mohali (PB) immediately. Please note that the time allowed for completion of work will be **03 (Three) Months**, which shall be reckoned from the Tenth day from the date of issue of this letter.

अश्विन

02/12/2020

अश्विन कुमार सिंह / ASHWIN K.R. SINGH

सहायक महाप्रबंधक (आर-ए) / AGM (ENGGE)

चंडीगढ़ इंटरनेशनल एयरपोर्ट लिमिटेड

1/5

Registered Office: Room No. 1, Project Office Building, Civil Airport, Chandigarh- 160003

Corporate Office: New Civil Air Terminal, Jhurheri, Mohali (Punjab) 160004

Civil Airport, Chandigarh

02/12/2020
M(E-E)

Racal
21/12/2020



चंडीगढ़ इंटरनेशनल एयरपोर्ट लिमिटेड Chandigarh International Airport Limited

6. Any further correspondences in connection with the contract should normally be addressed to the Asstt. General Manager (Engg-Elect), Chandigarh International Airport Ltd., Mohali (PB).
7. The defect liability period is **12 (Twelve)** Months from the date of completion.
8. You are requested to carry out the work as per schedule of quantity and agreement.
9. You are requested to generate Invoice and mentioned GST Number of Chandigarh International Airport as per details given below:-

Chief Executive Officer,
Chandigarh International Airport, Chandigarh
Mohali (PB)
GST No:- 03AADCC8570B1Z2

10. Please acknowledge the receipts and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl:-Schedule of Quantity

भवदीय / Yours Faithfully

Signature
02/12/2020
M (E-E)

अश्विन
02/12/2020
(अश्विन कुमार सिंह)
(Ashvin Kumar Singh)
सहा. महाप्रबन्धक (इन्जी. वि.)
(Asstt. General Manager (Engg-Elect))
For and on behalf of the Chairman
Chandigarh International Airport
अश्विन कुमार सिंह / ASHVIN K.R. SINGH
सहायक महाप्रबन्धक (अ.वि. ई.वि.) / AGM (ENGG-E)
चंडीगढ़ इंटरनेशनल एयरपोर्ट लिमिटेड
Chandigarh International Airport Ltd
सिविल एयर टर्मिनल, चंडीगढ़
Civil Air Terminal, Chandigarh

2/5

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Asstt. General Manager (Engg- Elect.), Chandigarh International Airport Ltd.(CHIAL), Mohali (PB)

Name of Work: SITC of Refrigeration units for Perishable Cargo building at Chandigarh International Airport, Mohali.

Contract No: 0172-2242404, 0172-2242434

Name of the Bidder/ Bidding Firm / Company : SMARTCOOL SYSTEMS PRIVATE LIMITED, Plot no. B-24 Industrial Area Phase 3 Mohali - 9914999333 & 9815529676

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (EXCLUDING GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (EXCLUDING GST) in Rs. P	TOTAL AMOUNT (EXCLUDING GST) In Words
1	2	3	4	5	6	7
1	SITC of refrigeration units suitable for maintaining Indoor temperature range from 10 Deg. C to 18 Deg. C for prefabricated Walk in Store Room (10m x 12m x 3.3m) of newly constructed Cargo, complete as required as per technical specification. The refrigeration units are inclusive of : i) Outdoor unit- Minimum refrigeration capacity of 8.55KW. Hermetic scroll type compressor. Refrigerant R-134a / R- 404a Power supply 415 V, 3 phase 50 Hz ii) Indoor Unit: Minimum refrigeration capacity of 9.75KW. Power supply 230 V, 1 phase 50 Hz or 415 V, 3 phase 50 Hz iii) All associated work like interconnected insulated copper piping upto 06 mtr., Drain piping, Electrical (power&control) cabling, Digital display of temperature at entrance, Gas charging with R134a, Pressure testing & vacuuming with Nitrogen with all adjunct work and supporting material/accessories for installation of Indoor and Outdoor units as per site conditions.	2	Job	211159.00	422318.00	INR Four Lakh Twenty Two Thousand Three Hundred & Eighteen Only

815

02/12/2022
BRANCH
CHANDIGARH INTERNATIONAL AIRPORT LTD.
(CHIAL), MOHALI (PB)

M. (e)

Sl. No.	Item Description	Quantity	Units	BASIC RATE (EXCLUDING GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (EXCLUDING GST) in Rs. P	TOTAL AMOUNT (EXCLUDING GST) In Words
2	SITC of refrigeration units suitable for maintaining Indoor temperature range from 10 Deg. C to 22 Deg. C for prefabricated Walk Perishable Room (12m x 20m x 3.3m) of newly constructed Cargo, complete as required as per technical specification. The refrigeration units are inclusive of: i) Outdoor unit- Minimum refrigeration capacity of 10.25 KW. Hermetic scroll type compressor. Refrigerant R-134a/ R- 404a Power supply 415 V, 3 phase 50 Hz ii) Indoor Unit: Minimum refrigeration capacity of 10.16 KW. Power supply 230 V, 1 phase 50 Hz or 415 V, 3 phase 50 Hz iii) All associated work like interconnected insulated copper piping upto 06 mtr., Drain piping, Electrical (power&control) cabling, Digital display of temperature at entrance, Gas charging with R134a, Pressure testing & vacuuming with Nitrogen with all adjunct work and supporting material/accessories for installation of Indoor and Outdoor units as per site conditions.	3	Job	211159.00	633477.00	INR Six Lakh Thirty Three Thousand Four Hundred & Seventy Seven Only
3	SITC of refrigeration units suitable for maintaining Indoor temperature range from - 5 Deg. C to 20 Deg. C for prefabricated Chiller cum freezer Rooms (5m x 4m x 3.3m)- 03 Rooms, of newly constructed Cargo, complete as required as per technical specification. The refrigeration units are inclusive of: i) Outdoor unit- Minimum refrigeration capacity of 5.60 KW. Hermetic scroll type compressor. Refrigerant R-134a / R- 404a Power supply 415 V, 3 phase 50 Hz ii) Indoor Unit: Minimum refrigeration capacity of 5.30 KW. Power supply 230 V, 1 phase 50 Hz or 415 V, 3 phase 50 Hz iii) All associated work like interconnected insulated copper piping upto 06 mtr., Drain piping, Electrical (power&control) cabling, Digital display of temperature at entrance, Gas charging with R134a, Pressure testing & vacuuming with Nitrogen with all adjunct work and supporting material/accessories for installation of Indoor and Outdoor units as per site conditions.	4	Job	221168.00	884672.00	INR Eight Lakh Eighty Four Thousand Six Hundred & Seventy Two Only

4/5

Signature
02/12/2020
K. R. SINGH
(ENGINEER)

Signature
(MICE)