

COMPARATIVE STATEMENT

Name of work : ARMO of E & M Installations at Rajahmundry Airport for the year 2020 - 21.

Sub-Head :Transformer Oil Filtration, Relay Testing and Calibration of Electrical Equipments.

Item No.	DESCRIPTION	QTY	UNIT	Justified Cost		M/s. Switchgear Controls, Vijayawada		M/s. Sai Rama Electricals, Visakhapatnam	
				Rate	Amount	Rate	Amount	Rate	Amount
1	Filtration of transformer oil to attain acceptable di-electric strength by hot streamline process including arranging plant, transportation etc. complete as required.	1550	Ltr.	8.00	12400.00	9.00	13950.00	14.00	21700.00
2	Testing of transformer oil sample including conducting BDV test & acidity test in reputed Govt. approved labs and producing test report etc complete as required.	2	Job	3500.00	7000.00	2500.00	5000.00	6000.00	12000.00
3	Calibration of different types of relays on 11 KV HT Panel viz., control relays of buchholz alarm and trip, oil temperature increase, winding temperature increase, master relay/Over current/earth fault relays, including submitting test report by OEM Service dealers/Government Approved Agencies etc complete as required.	16	Nos	2500.00	40000.00	2400.00	38400.00	3200.00	51200.00
4	Calibration & discrimination of different types of relays in the existing LT Panel board viz., IDMT relay, master trip relay, reverse power relay, over current/earth fault relays including submitting test certificates by OEM Service dealers/ Government Approved Agencies etc complete as required.	16	Nos	2400.00	38400.00	2000.00	32000.00	3300.00	52800.00
Total ₹				97800.00		89350.00		137700.00	
Say ₹				97800.00		89350.00		137700.00	

%ge w.r.t. Justified cost

-8.64%

40.80%

Status

Below

Above

L1

L2

Certified that I have personally conducted check of all tenders duly computed & Checked and satisfied my self that the checking work has been properly done and the

Jr. Executive (Engg-E)
AAI/Rajahmundry Airport

Manager(Engg-E)
AAI/Rajahmundry Airport

A.G.M. (Engg-E)
AAI/Rajahmundry Airport