



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA

सं.भाविप्रा/क्षेमु.उ.क्षे/एटीएस/अभि.(सिविल)/वॉटर लाइन/आईजीआईए/2021/1363  
No.: AAI/RHQ-NR/ATS/ENGG-CIVIL/WATER LINE/IGIA/2021/1363

दिनांक: 20/01/2021

Date: 20/01/2021

सेवा में,  
मैसर्स मुकेश कुमार वर्मा  
आरजैडएफ -907/06, राजनगर-II,  
पालम कॉलोनी,  
नई दिल्ली-110077

To,  
M/s Mukesh Kumar Verma  
RZF-907/06, Raj Nagar-II,  
Palam Colony,  
New Delhi-110077

विषय:- सभी उपयोगिताओं और खपत के लिए न्यूएटीएस कॉम्प्लेक्स से डीएटीएस कॉम्प्लेक्स तक पानी की आपूर्ति लाइन का विस्तार: सिविल कार्य।

Sub: Extension of water supply line from NATS Complex to DATS Complex for all utilities and consumption: Civil work.

निविदा आईडी: 2020\_एएआई\_63425\_1  
Tender ID: 2020\_AAI\_63425\_1

महोदय/Sir,

- 1) अध्यक्ष भारतीय विमानपत्तन प्राधिकरण द्वारा आपके ई-टेंडर को ऊपर दर्शाया गए कार्य के लिए आपके द्वारा दिए गए प्रतिशत दर पर जोकि कुल 9,79,025/- (रुपए नौ लाख उन्चासी हजार पच्चीस मात्र) (जीएसटी के बगैर) है जोकि निविदा के लिए लगाई गई अनुमानित लागत रूपए 15,47,200/- से 36.72% कम है (जीएसटी के बगैर) पर स्वीकार किया जाता है।

Your E- tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the percentage rates quoted by you totaling to Rs. 9,79,025/- (Rupees Nine Lacs Seventy Nine Thousand Twenty Five only) (excluding GST) which is 36.72% below the estimated cost put to tender of Rs. 15,47,200/- (excluding GST).

- 2) संयुक्त महाप्रबंधक अभि.(सिविल), कमरा न0 202, द्वितीय तल, भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उत्तरी क्षेत्र, प्रचालन कार्यालय, रंगपुरी, नई दिल्ली-110037, इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि अनुबंध करार को पूरा करने एवं हस्ताक्षर करने के लिए आप दिनांक 04/02/2021 तक संयुक्त महाप्रबंधक (अभि.-सिविल), क्षेत्रीय मुख्यालय, उत्तरी क्षेत्र के कार्यालय में उपस्थित हों। अनुबंध करार 100 (सौ रूपए) रूपए के गैर-न्यायिक स्टाम्प पेपर पर होगा एवं स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Jt. General Manager (Engg.-Civil), Room No.-202, 2nd Floor, AAI, Regional Headquarters, Northern Region, Operational Offices, Rangpuri, New Delhi-110037, shall be the Engineer-in-charge of the work. You are requested to attend the office of Jt. G.M (Engg.-Civil), RHQ-NR by 04/02/2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100 - (Rupees: One Hundred only) and the cost of the stamp paper shall be borne by you.

Contd....2

- 3) आपके टेंडर के साथ प्राप्त बयाना राशि ₹0 30,944/- (रुपये तीस हजार नौ सौ चवालीस मात्र) ठेके के दस्तावेज से खंड -12.2 पृष्ठ का NIT पेज नं० एनआईटी-3 पर दी गई शर्त के अनुसार जमानत राशि में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के अंदर जमानत राशि कि बकाया राशि ₹0 66,959/- (रुपये छियासठ हजार नौ सौ उनसठ मात्र) जमा कर दे, अन्यथा ठेके के दस्तावेज में दी शर्त के अनुसार इतनी ही राशि आपके रनिंग बिल से काट ली जाएगी।

The Earnest Money amount of Rs. 30,944/- (Rupees Thirty Thousand Nine Hundred Forty Four Only) received along with your tender will be treated and converted as part of Security Deposit as per condition Clause-12.2 of NIT Page No. NIT-3 of the tender document. Please deposit Rs.66,959/- (Rupees Sixty Six Thousand Nine Hundred Fifty Nine Only) towards balance Security Deposit within 10 days from the date of issue of this letter, failing which, the same shall be deducted from your running bills as per conditions of the contract document.

- 4) निवेदन है कि आप श्रम अनुबंध (विनियम एवं उन्मूलन) अधिनियम 1970 एवं श्रम अनुबंध (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (विनियम एवं निषेध) अधिनियम 1986, निर्माण मजदूर (रोजगार विनियम एवं सेवा शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण मजदूर कल्याण अधिनियम 1996 का पालन करेंगे, जोकि केन्द्र एवं राज्य सरकार के टेंडर के पृष्ठ संख्या 49 जीसीसी के अनुच्छेद 19 पर दर्शाए गए हैं।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 49 of GCC of tender and rules of Central and State Government.

- 5) आपको निर्देश दिए जाते हैं कि आप शीघ्रातिशीघ्र सहायक महाप्रबंधक (अभि.-सिविल), कमरा नं० 17, भू तल, भारतीय विमानपत्तन प्राधिकरण, एटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, नई दिल्ली-110037 से सम्पर्क करें जोकि आपको साइट को सौंपने का प्रबंध करेंगे।

You are also directed to contact Asstt. General Manager (Engg.-Civil), Civil Engineering wing, Room No. 17, Ground Floor, AAI, ATS Complex, IGI Airport, New Delhi-110037 immediately who will arrange to hand over the site to you.

- 6) कृपया ध्यान दें कि कार्य को पूरा करने का समय 03 (तीन) महीने होगा जोकि इस पत्र के जारी होने के 10 वें दिन से माना जाएगा या साइट पर सौंपने की तारीख के बाद भी यह माना जाएगा।

Please note that the time allowed for carrying out the work shall be 03 (Three) months and same shall be reckoned from the 10th day after issue of this letter or the date of handing over of site which ever is earlier.

- 7) इस करार के संबंध में भविष्य में होने वाले सभी पत्राचार प्रभारी अभियंता को संबोधित किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

- 8) कृपया इस पत्र की पावती भेजें एवं सलग्न प्रतिलिपी पर हस्ताक्षर करके स्वीकृति के प्रमाणस्वरूप अधोहस्ताक्षरी को वापिस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Contd....3

9) किसी भी विवाद की स्थिति में पाठ का अंग्रेजी रूप मान्य होगा।

If case of difference or ambiguity in Hindi and English version, the English version will prevail.


धन्यवाद,

Thanking you,

संलग्न:- मात्रा की अनुसूची (02 pages)

Enclosed:- Schedule of Quantities (02 pages)

भवदीय /yours faithfully



महेश कुमार/ Mahesh Kumar

संयुक्त महाप्रबंधक (अभि.-सिविल)/Jt.GM (Engg-Civil)

अध्यक्ष, ए ए आई की ओर से तथा उनके लिए /for and on behalf of the Chairman, AAI

**Name of Work : Extension of water supply line from NATS Complex to DATS Complex for all utilities and consumption: Civil work.**

**Tender ID : 2020\_AAI\_63425\_1**

**Schedule of Quantity (SOQ)**

| Sl. No. | DESCRIPTION OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit  | Qty.   | Rate without GST | Amount    |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|------------------|-----------|
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.                                                                                                                                                                                                                                                                                                                | cum   | 25.00  | 150.00           | 3750.00   |
| 2       | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.<br>Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | cum   | 52.00  | 700.00           | 36400.00  |
| 3       | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.<br>External work<br>50 mm nominal outer dia Pipes (SDR-11)                                                                                                                                                                                                                                                                                    | metre | 800.00 | 400.00           | 320000.00 |
| 4       | Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 450 mm dia RCC pipes.                                                                                                                                                                                                                                                                                                                                                                                                                                 | metre | 30.00  | 1200.00          | 36000.00  |
| 5       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)                                                                                                                                                                                                                                                                                                                                                                                                                                                   | cum   | 40.00  | 5500.00          | 220000.00 |
| 6       | Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 50 mm nominal bore                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | each  | 15.00  | 800.00           | 12000.00  |
| 7       | Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge. | hour  | 150.00 | 550.00           | 82500.00  |
| 8       | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge : External Work - Exposed on wall<br>50 mm nominal outer dia Pipes (SDR 11)                                                                                                                                                                                                                             | metre | 345.00 | 360.00           | 124200.00 |
| 9       | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-In-charge. In cement mortar                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | cum   | 5.00   | 600.00           | 3000.00   |

| Sl. No. | DESCRIPTION OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Unit       | Qty.  | Rate without GST | Amount    |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|------------------|-----------|
| 10      | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | cum        | 10.00 | 4200.00          | 42000.00  |
| 11      | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | cum        | 5.00  | 5000.00          | 25000.00  |
| 12      | 12 mm cement plaster of mix: 1:4 ( 1 cement : 4 fine sand )                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | sqm        | 25.00 | 200.00           | 5000.00   |
| 13      | 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | sqm        | 25.00 | 225.00           | 5625.00   |
| 14      | Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways , neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick , 100 mm wide MS sheet duly painted over priming coat , reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge. | sqm        | 5.50  | 1500.00          | 8250.00   |
| 15      | Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                | metre      | 60.00 | 680.00           | 40800.00  |
| 16      | Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | cum        | 5.00  | 800.00           | 4000.00   |
| 17      | Cartage of building rubbish / malba or waste materials by mechanical means outside AAI premises including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, for all leads including all lifts involved. Upto 5.5 cum/10 tonnes                                                                                                                                                                                                                                                                                                                                                                                                                            | each truck | 3.00  | 3500.00          | 10500.00  |
| Total   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |       |                  | 979025.00 |

(Rupees Nine Lacs Seventy Nine Thousand Twenty Five Only)

*[Signature]*  
20.1.2021  
Jt. GM(Engg-Civil)  
AAI, RHQ-NR

Signature Not Verified

Digitally signed by GANESH SHARMA  
Date: 2021.06.08 12:14:26 IST  
Location: eProcurement System for  
Central PSUs