



**भारतीय विमानपत्तन प्राधिकरण**  
**AIRPORTS AUTHORITY OF INDIA**

JAS-ANZ



**COIMBATORE INTERNATIONAL AIRPORT**

सं.सं.:भा.वि.प्रा/सीबीई/इ-वि/CW-03/LA OOTY/W-20/2020-21

Ref. No: AAI/CBE/E-E/CW-03/LA OOTY/W-20/2020-21

दिनांक: 23.02.2021

द्रुत डाक द्वारा  
BY SPEED POST

सेवा में /To

M/s Accuelec Power Solutions LLP

F207/3, 2<sup>nd</sup> floor, Ashish Complex, Plot No:3

New Rajadhani Enclave, New Delhi-110092

मेल आई.डी / Mail id: sales@accuelec.com

Name of Work : "Provision of Conventional Type Lightning Arrestor at Ooty, RCAG Station. SH: SITC of Conventional type Lightning Arrestor and Surge Protection System at Ooty, RCAG Station."

संदर्भ / Ref: 1) दि. 25.01.2021 को आपका वित्तीय बोली खोला गया। / Your Financial Bid Opened on

25.01.2021. (E-bid No: 2020\_AAI\_64512\_1)

महोदय/Dear Sir (s),

1. उपर्युक्त कार्य के संबंध में आपका निविदा को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया गया है, मद के लिए आपके द्वारा उद्धृत राशि कुल रू. 4,28,250.00 प्लस जी.एस.टी सेवा कर भी जो न्यायोचित राशि रू. 5,28,948.00. से 19.04 % नीचे। Your E-tender for the above mentioned work is accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 4,28,250.00 (Rupees Four Lakhs Twenty Eight Thousand Two Hundred and Fifty Only) excluding GST @ 18%, which is 19.04% below the estimated cost put to tender of Rs. 5,28,948.00 excluding GST.
2. भा.वि.प्रा, कोयंबतूर अंतरराष्ट्रीय हवाईअड्डा के सहायक संयुक्त महाप्रबंधक (इंजि-वि), इस कार्य के इंजिनियर प्रभारी है। आपसे अनुरोध है कि दि. 05.03.2021 को, भा.वि.प्रा, कोयंबतूर हवाईअड्डा संयुक्त महाप्रबंधक (इंजि-वि), के कार्यालय आए और करार को हस्ताक्षरित करके पूरा करें। अनुबंध एग्रीमेंट गैर न्यायिक स्टाम्प कागज मूल्य रू.100.00 (एक सौ मात्र) के लिए निष्पादित करना है और स्टैप कागज का मूल्य आपके द्वारा वहन किया जाएगा। Jt. Gen. Manager (Engg-Elect), AAI, Coimbatore International Airport shall be the Engineer-In- Charge of the work. You are requested to attend the office of the Jt.Gen.Manager (Engg-Elect), AAI, Coimbatore Airport on or before 05.03.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100.00 (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.
3. अनुबंध निविदा के पृष्ठ 16 पर धारा के मुताबिक, आपके निविदा के साथ रू. 10,579.00 की अग्रिम राशि पर विचार किया जाएगा और उसे सुरक्षा जमा के एक हिस्से में परिवर्तित कर दिया जाएगा.आपके द्वारा निविदा के साथ सुरक्षा जमा राशि के भाग के रूप में माना जाएगा। यह पत्र जारी के 10 दिनों के अंदर रू. 32,246.00 को कृपया सुरक्षा राशि के रूप में जमा करें, जमा नहीं किया तो चालू बिलों से उपर्युक्त राशि की कटौती की जाएगी। The Earnest money amount of Rs.10,579.00 (Rupees Ten Thousand Five Hundred

**COIMBATORE INTERNATIONAL AIRPORT, COIMBATORE - 641 014**

**PHONE/FAX: 0422-2571668**

**Web Site: [www.airportsindia.org.in](http://www.airportsindia.org.in)**



**भारतीय विमानपत्तन प्राधिकरण**  
**AIRPORTS AUTHORITY OF INDIA**



**COIMBATORE INTERNATIONAL AIRPORT**

and Seventy Nine Only) received along with your tender will be treated and converted as part of security deposit as per clause 13 on page no.18 of contract document. Please deposit Rs 32,246.00 (Rupees Thirty Two Thousand Two Hundred and Fourty Six Only) as Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills.

4. कृपया ध्यान दें कि कार्य को करने के लिए अनुमत समय 3 महीने का होगा और इस पत्र के जारी होने के 10 वें दिन से इसे फिर से लिया जाएगा।/ Please note that the time allowed for carrying out the work shall be 3 (Three) Months and same shall be reckoned from the 10th day of issue of this letter.
5. कार्य की पूर्णता की तारीख से दोष देयता अवधि 12 (बारह) महीने होगी। The Defects Liability Period shall be 12 (Twelve) months from the date of completion of Work.
6. आपको वरिष्ठ प्रबंधक (इंजीनियरिंग-इलेक्ट्रिकल), भारतीय विमानपत्तन प्राधिकरण, कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे से तुरंत संपर्क करने के लिए निर्देशित किया जाता है, जो आपको साइट सौंपने की व्यवस्था करेगा। You are also directed to contact Sr.Manager (Engg-Elect), AAI, Coimbatore International Airport immediately who will arrange to handover the site to you.
7. आपसे अनुरोध है कि जीएसटीआईएन का जिक्र करते हुए जीएसटी अधिनियम के अनुसार वैध जीएसटी चालान जमा करने का अनुरोध किया जाए, जो कि जीएसटी दरों को लागू करता है और इनपुट टैक्स क्रेडिट विवरण इंगित करता है यदि एआई कोयंबटूर जीएसटी का उल्लेख करने वाले बिलों को संसाधित करने के लिए कोई है। 33AAACA6412D1ZF/ You are requested to submit valid GST invoice as per GST act mentioning the GSTIN, indicating the GST rates applicable and input tax credit details if any for processing the bills mentioning the AAI Coimbatore GST no.33AAACA6412D1ZF.
8. अनुबंध के संबंध में कोई और पत्राचार आम तौर पर सहायक को संबोधित किया जाना चाहिए संयुक्त महा प्रबंधक (इ-वि), कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे। Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (Engg-Elect), AAI, Coimbatore International Airport.
9. कृपया इस कार्य आदेश की प्राप्ति को स्वीकार करें। Please acknowledge the receipt of this work order.

अनुलग्नक/Encl: अनुसूची/Schedule 'A'.

*(Signature)* 23/02/2024

संयुक्त महाप्रबंधक (इ-वि),  
Jt. Gen. Manager (Engg-Elect)

COIMBATORE INTERNATIONAL AIRPORT, COIMBATORE - 641 014

PHONE/FAX: 0422-2571668

Web Site: [www.airportsindia.org.in](http://www.airportsindia.org.in)

**Name of Work: Provision of Conventional Type Lightning Arrestor at Ooty, RCAG Station. SH: SITC of Conventional type Lightning Arrestor and Surge Protection System at Ooty, RCAG Station.**

**Schedule A**

**Schedule of Quantities**


| S.No. | Description of Items                                                                                                                                                                                                                                                                                            | Qty | Unit | Rate    | Amount   |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|---------|----------|
|       | Supply and Installation of Vertical air terminal 1.5m with mounting accessories, providing of air terminals as per IS/IEC - 62305 part - 3, Solid copper Air terminal rod material of 16mm dia rod tapered to 10mm dia (Franklin Rod) and the Copper purity - Not less than 90%, etc. including all accessories | 2   | Nos  | 4500.00 | 9000.00  |
| 2     | Supply of following size multi stranded bare copper conductor XLPE insulated and PVC sheathed unarmoured power cable of 1.1 KV grade conforming to relevant IS with upto date amendments.<br>16 Sq.mm                                                                                                           | 50  | Mtrs | 250.00  | 12500.00 |
| 3     | Supply of following size multi stranded bare copper conductor XLPE insulated and PVC sheathed unarmoured power cable of 1.1 KV grade conforming to relevant IS with upto date amendments.<br>35 Sq.mm                                                                                                           | 50  | Mtrs | 375.00  | 18750.00 |
| 4     | Supply of following size multi stranded bare copper conductor XLPE insulated and PVC sheathed unarmoured power cable of 1.1 KV grade conforming to relevant IS with upto date amendments.<br>70 Sq.mm                                                                                                           | 100 | Mtrs | 625.00  | 62500.00 |
| 5     | Supply and Installation of Support Mast of 50 mm dia of length 4 mtr GI + 1m FRP with GI base plate of 300 X 300 X 3 mm base installed on the existing Terrace roof with 4 Nos of SS bolts of suitable dimensions                                                                                               | 2   | Nos  | 7500.00 | 15000.00 |

| S.No. | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty | Unit | Rate      | Amount    |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|-----------|-----------|
| 6     | Supply and Installation of 25 X 3 mm Copper Conductor (strip) for interconnection of lightning arrester etc complete as required                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 30  | Mtrs | 750.00    | 22500.00  |
| 7     | Supply, installation, testing and commissioning of AC surge protection device (SPD) Block MOV based plug-in type Surge Divertor capable of carrying nominal discharge of 100 KA (BMOVSD), 8/20 micro second surge, protection level of 1.5 kV with necessary visual indications, suitable for 3 phase, 4 Wire with neutral protection in pre - wired IP55 or above grade powder coated metal enclosure complete with sensing circuit, potential free contacts, necessary indications and alarm for Essential Panel connected in parallel as primary protection at the power entry point as first stage protection with safety circuit breaker, providing suitable wiring for all interconnections and accessories etc. as required for installation. ( Make: From List of approved makes) | 1   | No   | 65000.00  | 65000.00  |
| 8     | Supply, installation, testing and commissioning of 240KA surge protection device against the protection from Noises, ESD, EPR and abnormal electrical characteristics which enter from power and other service line and ensuring clear bonding potential (earth to Neutral voltage) less than 1.0V to be connected in parallel to the circuit. Confirming to CE, tested and certified as per latest certification (IEC - 61643 - 1, IEC - 61000-4 - 5, IEC - 61000 - 6 - 1, IEC - 61000 - 6 - 3) in pre-wired metal enclosure with pulverulent body painting including all accessories required for installation.(Connect to 5 KVA Ups input / output in parallel as secondary protection.) (Make : from List of approval makes)                                                          | 1   | No   | 165000.00 | 165000.00 |

| S.No. | Description of Items                                                                                                                                                                                                                                | Qty | Unit | Rate             | Amount           |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|------------------|------------------|
| 9     | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1KV grade of following size on wall surface as required.<br>Upto 35 sq. mm (clamped with 1mm thick saddle)                                                   | 100 | Mtrs | 100.00           | 10000.00         |
| 10    | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1KV grade of following size on wall surface as required.<br>Above 35 Sq.mm and upto 95 Sq.mm (clamped with 25 x 3mm MS flat clamp)                           | 100 | Mtrs | 150.00           | 15000.00         |
| 11    | Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required. | 2   | Set  | 16500.00         | 33000.00         |
|       |                                                                                                                                                                                                                                                     |     |      | <b>Total Rs.</b> | <b>428250.00</b> |

(Excluding GST)

(Rupees Four Lakhs Twenty Eight Thousand Two Hundred and Fifty Only)

  
23/02/2021

Jt. Gen. Manager (E-E)

Signature Not Verified

Digitally signed by SHIVA KUMAR  
GUNDA

Date: 2021.06.28 16:57:05 IST

Location: eProcurement System for  
Central PSUs