



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
कलिकट अंतर्राष्ट्रीय विमानपत्तन / CALICUT INTERNATIONAL AIRPORT
कलिकट विमानपत्तन(पो.ओ.) केरल / Calicut Airport (P.O.), Kerala - 673 647
दूरभाष/Phone : 0483 271 2630, फैक्स/Fax : 0483 2711406, ई-मेल/E mail : apd_calicut@aai.aero

Ref. No. AAI/CL/ENGG(E)/99/WO-78/010

By Regd.AD/E-mail

Date: 21.01.2021

M/s Nagasurya Contractors,
Door No.23-10-13/1,
Vinnakotavari Street,
Sajjapuram, TANUKU
West Godavari Dist. - 534211

Name of Work : Providing Power Supply for bird scarers Huts in various locations and Miscellaneous electrical works related separate room for UPS and batteries at Localizer 10 at Calicut Airport

Ref: : Your financial bid opened on 08.01.2021.

Dear Sir(s),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs.6,33,050/- (Rupees Six Lakhs Thirty Three Thousand and Fifty Only)** which is 12.67% below the justified cost.
2. Jt. Gen. Manager (Engg-Elect), AAI, Calicut International Airport shall be the Engineer-in-Charge of the work. You are requested to attend the office of Jt. Gen. Manager (Engg-Elect), AAI, Calicut International Airport by **29.01.2021** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.200/- (Rupees Two Hundred only)** and the cost of the stamp paper shall be borne by you.
3. The earnest money amount of **Rs.14,498/- (Rupees Fourteen thousand Four hundred and Ninety Eight only)** received alongwith your tender will be refunded against recovery of security deposit as per Clause No.1 A on Page No. GCC 17 of contract document. Please deposit **Rs.63,305/- (Rupees Sixty Three Thousand Three Hundred and Five only)** towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause No.1 A at page No.GCC17 of contract document
4. Within 30 days of issue of acceptance letter, you shall submit to AAI, a Performance Guarantee as per condition of clauseon page.....for an amount of **Rs.63,305/- (Rupees Sixty Three Thousand Three Hundred and Five only)** in the form of Bank Guarantee on the Proforma appended at Annexureof Contract Document (If it is applicable).



GMB 9001:2008 EMS 14001:2004 Certified

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

कलिकट अंतर्राष्ट्रीय विमानपत्तन / CALICUT INTERNATIONAL AIRPORT
कलिकट विमानपत्तन (पो.ओ.), केरल / Calicut Airport (P.O.), Kerala - 673 647
दूरभाष Phone : 0483 271 2630, फैक्स Fax : 0483 2711406, ई-मेल E mail : apd_calicut@aii.aero


-2-

5. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction of Works (Regulation of Employment and Condition of Services) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on Page No.50-56 of GCC of tender and rules of Central and State Government.
6. You are also directed to contact Asst. Gen. Manager (Engg-Elect)- I, AAI, Calicut International Airport immediately who will arrange to hand over the site.
7. Please note that the time allowed for carrying out the work shall be **02 (Two) Months** and same shall be reckoned from the 10th day of issue of this letter.
8. Any further correspondence in connection with the contract should normally be addressed to the Engineer- In- Charge.
9. Please note that the awarded rate is exclusive of GST and you are required to submit valid GST invoices for effecting payment.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Thanking you,

Encl: SOQ

Yours faithfully,


21/01/2021
Asst. General Manager (Engg-Elect) -I,
For and on behalf of the Chairman,
Airports Authority of India

Airports Authority of India
Engineering Wing (Electrical)
SR, Calicut International Airport, Calicut-673 647
SCHEDULE OF QUANTITIES

Name of work : Providing Power Supply for bird scarers huts in various locations and Miscellaneous electrical works related separate room for UPS and batteries at Localizer 10 at Calicut Airport

Sl. No	Item Description	Qty	Unit	Rate	Amount
1	Supplying and Laying of HDPE pipe of 50mm OD of PE 80 PN 6 IS marked along with all accessories like socket, bend, couplers etc. confirming to IS 4984, complete with fitting and cutting, jointing etc. direct in ground at a depth of 0.8m below the ground level i/c excavation and refilling the trench but excluding sand cushioning and protective etc as required.	900	Meter	190.00	1,71,000.00
2	Supplying of XLPE insulated, PVC sheathed, armoured Aluminium conductor Power Cable of 1.1 KV grade of following size etc as per IS 7098 Part-I 1988 with upto date amendments etc as required 4 C x 25 sq mm	950	Meter	180.00	1,71,000.00
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 5/1.1 KV grade of following size in the existing RCC/HUME/STONEWARE/METAL/DWC Pipe as required. [upto 35 Sq. mm]	900	Meter	40.00	36,000.00
4	Supplying and making end termination with brass single compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	4 core, 25 Sq. mm.	8	Set	250.00	2,000.00
5	Supply and fixing of Cable termination box sintex model GS JB 2520 or equivalent in other reputed makes along with necessary mounting arrangement including 4nos terminals for 25 sq. mm cable as required.	8	JOB	1,000.00	8,000.00
6	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	8	SET	5,500.00	44,000.00
7	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required. (Supply and fixing of 40 mm dia G.I. pipe is also included in this scope)	50	metre	550.00	27,500.00

Sl. No	Item Description	Qty	Unit	Rate	Amount
8	Supply of 2 Ton capacity 3-star rated Split type Air-conditioner unit fitted with rotary compressor operating on refrigerant R-22 suitable for high wall mounting , operating at 230V+/- 5%, 50+/-5% Hz, single phase AC supply, capable of performing the functions as cooling, dehumidifying, air circulating and filtering, complete with compressor, evaporators, air cooled condenser, connected refrigerant piping, electric wiring, all accessories etc.as per site requirement. Evaporator and condenser coils shall be of copper.	2	JOB	45,000.00	90,000.00
9	Installation testing and commissioning of the 2 TR split type air conditioner, including providing and fixing suitable MS stand for out door unit, including painting the MS stand with two coats of primer and enamel paint.	2	JOB	4,500.00	9,000.00
10	Providing & laying following size thermally Insulated copper pipe for refrigerant line suitable for the AC unit beyond the standard length received from the factory.	15	Metre	700.00	10,500.00
11	Providing & laying 1" Drain pipe for medium duty PVC pipe suitable for the AC unit, beyond the standard length received from the factory.	5	Metre	50.00	250.00
12	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class FRLS PVC conduit as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	20	Metre	200.00	4,000.00
13	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class FRLS PVC conduit as required. 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	5	Metre	120.00	600.00
14	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class FRLS PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. GROUP A	2	Point	500.00	1,000.00
15	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 4 way (4 + 12), Double door	1	Each	2,500.00	2,500.00

21/01/2021

Sl. No	Item Description	Qty	Unit	Rate	Amount
16	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with suitable DIN rail for mounting, connections, testing and commissioning etc. as required. 40 A	1	Each	650.00	650.00
17	Supplying and fixing 40 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple pole and neutral	1	Each	1,850.00	1,850.00
18	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	6	Each	200.00	1,200.00
19	Supply of PVC insulated and PVC sheathed / XLPE armoured aluminium power cable of 1.1 KV grade conforming to IS 7098 /1554 of following size. 4 C x 10 Sq.mm.	10	Metre	160.00	1,600.00
20	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	10	Metre	50.00	500.00
21	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	910	Metre	50.00	45,500.00
22	Supplying and fixing following size/ modules, PVC box alongwith modular base & cover plate for modular switches in recess etc as required. 3 Module (100mmX75mm)	5	Each	200.00	1,000.00
23	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 6 pin 15/16 amp socket outlet	5	Each	100.00	500.00
24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 15/16 A Switch	5	Each	100.00	500.00

[Signature]

Sl. No	Item Description	Qty	Unit	Rate	Amount
25	Supplying and fixing of 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	2	Each	1,200.00	2,400.00
	Total				6,33,050.00

(Rupees Six Lakhs Thirty Three thousand and Fifty Only)

12/03/2021
 Asst. General Manager (Engg-Elect) - I
 AAI, Calicut International Airport

Signature Not Verified

Digitally signed by PALLIPATTU RAVI
 HARI
 Date: 2021.03.03 15:37:26 IST
 Location: eProcurement System for Central
 PSUs