



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ सं / Ref. No. AAI/BD/Engg(C)/ACP Cladding/W.O.-06/20-21/1930-34 दिनांक / DATE22/02/2021.....

सेवा में/To

M/s Youngmen Traders,
P-27/1, Rashtraguru Avenue,
Dum Dum,
Kolkata – 700028

विषय/Sub: - Minor Capital Works at Bagdogra Airport during 2020-21. SH.: - ACP
Cladding for roof level chajjas and window chajjas in Terminal Building.

संदर्भ/Ref: - Your tender dated: - 25/01/2021.

महोदय/Dear Sir(s),

1. Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 9,48,601.50 (Rupees Nine Lacs Forty Eight Thousand Six Hundred One and Fifty Paise Only)** which is **52.13% below** the estimated cost put to tender of Rs. 19,81,450.00.
2. AGM (E-C), AAI, Bagdogra Airport, shall be the Engineer – in – charge of the work. You are requested to attend the office of AGM (E-C), AAI, Bagdogra Airport, Dist.: Darjeeling, Pin: - 734421 by **04/03/2021** to sign and complete the contract agreement. The contract agreement shall be executed on a non – judicial stamp paper of value **Rs. 100 (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.
3. Please deposit **Rs. 94,860.00 (Rupees Ninety Four Thousand Eight Hundred Sixty Only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of clause of **1A** on page **33** of the contract document.
4. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments.
5. You are also directed to contact **Manager (E-C)**, Bagdogra Airport immediately who will arrange to hand over the site to you.

9/c

6. Please note that the time allowed for carrying out the work shall be **Three Months** and same shall be reckoned from the 10th days after issue of this letter.

7. Any further correspondence in connection with the contract should normally be addressed to the Engineer – in – charge.

8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance

Thanking you.

संलग्न/Enclosure: - Schedule of Rates.

भवदीय /Yours faithfully



सहा. महा. प्रबंधक इंजी. (सिविल)/Asst. General Manager (E-C),
अध्यक्ष के लिए और उनकी तरफ से/For and on behalf of the Chairman,
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India,
बागडोगरा विमानपत्तन/Bagdogra Airport

N. O. O:

प्रतिलिपि/Copy to: -

1. महा. प्रबंधक (अभियांत्रिकी), भा.वि.प्रा., NSCBI विमानपत्तन, कोलकाता/GM (Engg), AAI, NSCBI Airport, Kolkata.
2. महा. प्रबंधक (वित्त), भा.वि.प्रा., NSCBI विमानपत्तन, कोलकाता/GM (F&A), AAI, NSCBI Airport, Kolkata.
3. निदेशक विमानपत्तन, भा.वि.प्रा., बागडोगरा विमानपत्तन/Airport Director, AAI, Bagdogra Airport.
4. उप. महा. प्रबंधक (सिविल), भा.वि.प्रा., NSCBI विमानपत्तन, कोलकाता/DGM Engg. (C), AAI, NSCBI Airport, Kolkata.
5. प्रबंधक इंजी. (सिविल), भा.वि.प्रा., बागडोगरा विमानपत्तन/Mgr. Engg. (Civil), AAI, Bagdogra Airport.
6. The Labour Enforcement Officer (Central) Siliguri Office of the Asst. Labour Commissioner (Central), Choudhury Complex, Near New Masjid, Burdwan Road, Siliguri-734001.
7. Agreement Copy.

SCHEDULE OF QUANTITIES

Name of work :- Minor Capital Works at Bagdogra Airport during 2020-21. SH.: - ACP Cladding for roof level chajjas and window chajjas in Terminal Building.

Item No.	Description	Unit	Qty.	Rate	Amount
1	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chajjas, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	sqm	1024.10	150.00	153615.00
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion. Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC 15).	kg	343.12	375.00	128670.00
3	Providing & fixing in position 3mm thick Aluminium composite panels in external face, column / wall cladding and canopy ceiling of approved make comprising virgin polyethylene core sandwiched between two skins of 0.25mm thick. Fixing of surface cladding to masonry / concrete faces / steel structure as called for (straight/slope and curvilinear profile and shapes), fixed on appropriate and adequate frame work of aluminium tubular sections (aluminium frame work to be paid separately) including all accessories and all incidental work. The cladding shall be done in accordance with the drawings, fixed to sides and faces of columns/ piers, to sills and soffits of window opening, returned over coping, to RCC / structural steel system, etc. to line and level. The joints shall be properly sealed with approved silicon sealant to make the joints watertight and weather proof including, fixing over aluminium frame using mechanical fasteners such as Aluminium cleats and stainless steel fasteners all complete as approved by the Engineer-in-charge. The work shall be completed as per specification and directions of Engineer-in-charge.	sqm	376.45	1770.00	666316.50
				Total Rs.	948601.50

(Rupees Nine Lacs Forty Eight Thousand Six Hundred One and Fifty Paise Only)


22/02/2021

(S. K. Podder)
AGM (E-C)

AAI, Bagdogra Airport

Signature Not Verified

Digitally signed by SUJIT KUMAR
PODDER

Date: 2021.03.17 15:29:47 IST

Location: eProcurement System for Central
PSUs