

सं.स. : भाविप्रा/म्योर/अभि/बाउण्डी वाल/डब्लू-62/2021-22/831-41
Ref. No. AAI/MUIR/ENGG/Boundary Wall/W-62/2021-22/831-41

दिनांक: 01.10.2021
Date: 01.10.2021
स्पीड पोस्ट/ई-मेल

3438-48

सेवा में,

मेसर्स एस.के. कन्स्ट्रक्शन
ग्राम-बरेमा, पोस्ट-रामेश्वर
वाराणसी-221405

M/s SK Construction,
Vill-Barema, Post-Rameshwar,
Varanasi-221405

विषय : म्योरपुर एयरपोर्ट, जिला सोनभद्र, उत्तर प्रदेश में मौजूदा पुरानी चारदीवारी को तोड़कर आरसीसी फ्रेम्ड स्ट्रक्चर बाउंड्री वाल का निर्माण।

Demolishing of existing old boundary wall & Construction of RCC framed Structure Boundary Wall at Muirpur Airport, Dist, Sonbhadra, U.P. (Tender ID : 2020_AAI_65165_1))

संदर्भ : ई-निविदा खुलने की तिथि : 17.05.2021

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपया 2,19,69,325.00 (रुपया दो करोड़ उन्नीस लाख उनहत्तर हजार तीन सौ पच्चीस मात्र) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपया 355.20 लाख से 38.15% (अठ्तीस दशमलव एक पाँच प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs 2,19,69,325.00 (Rupees Two Crore Nineteen Lakhs Sixty Nine Thousand Three Hundred Twenty Five only) which is 38.15 (Thirty Eight point One Five percent) below to the estimated cost put to tender of Rs. 355.20 lakhs.

- 2) उप महाप्रबन्धक (अभि0-विद्युत), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा वरिष्ठ प्रबन्धक (अभि0-सि0), भा. वि.प्रा., म्योरपुर एयरपोर्ट, सोनभद्र (यूपी.) उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 11.10.2021 तक उप महाप्रबन्धक (अभि0-विद्युत) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपए के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The DGM(Engg-Elect), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Senior Manager (Engg-Civil), AAI, Muirpur Airport, Sonbhadra (UP) shall be our authorised representative. You are requested to attend the office of the DGM(Engg-Elect) by 01.11.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) कृपया प्रतिभूति निक्षेप राशि रुपया 21,96,933.00 (रुपया इक्कीस लाख छियाब्बे हजार नौ सौ तैतीस मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

Please deposit Rs. 21,96,933.00 (Rupees Twenty One Lakhs Ninety Six Thousand Nine Hundred Thirty Three only), towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition referred above of the contract document.

शेष पृष्ठ 2 पर....

4
24/10/21



-2-

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनियम एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनियम एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से वरिष्ठ प्रबन्धक (अभि०-सि०), भा. वि.प्रा., म्योरपुर एयरपोर्ट, सोनभद्र (यू.पी.) से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Senior Manager (Engg-Civil), AAI, Muirpur Airport, Sonbhadra (UP) immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 04 (चार) महीने हैं जो कि दिनांक 11.10.2021 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 04 (Four) months and the same shall be reckoned from 11.10.2021
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः उप महाप्रबन्धक (अभि०-विद्युत), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the DGM (Engg-Elect), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 04 (सिविल कार्य रु. 2,19,69,325.00) संलग्न है।
Schedule 'A' (total page 04) (Civil works Rs. 2,19,69,325.00) of the work is enclosed.
- उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

संलग्नक- यथोपरि एवं फार्म-5
Encl:- As above and Form-V

भवदीय

उ.म.प्र. (अभि.-वि०), ११/१०/२०

Dy. GM (Engg-Elect)

अध्यक्ष, भा०वि०प्रा० के लिए व उनकी तरफ से

For and on behalf of the Chairman, AAI

Dy. General Manager Engg. (Elect.)

भा०वि०प्रा०ला०ब०शा० अन्तर्राष्ट्रीय हवाई अड्डा, वाराणसी
A.A.I., L.B.S.I. International Airport, Varanasi



प्रतिलिपि:


मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. महाप्रबन्धक (अभि)-उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ (फार्म-7 संलग्न)
4. वरिष्ठ प्रबन्धक (अभि-सिविल), भाविप्रा, म्योरपुर एयरपोर्ट (यूपी.) : आवश्यक कार्यवाही हेतु।

ब. आंतरिक-

- | | | |
|-----------------------|---|----------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. स.म.प्र. (सिविल) | : | -तदैव- |
| 3. स.म.प्र. (विद्युत) | : | -तदैव- |
| 4. प्रभारी (वित्त) | : | -तदैव- |
| 5. कार्यादेश फाईल | | |
| 6. अनुबन्ध | | |


उ.म.प्र.(अभि.-विद्युत), 01/10/20

Inviting Authority: Airports Authority of India

Line of Work: Demolishing of existing old boundary wall & Construction of RCC framed Structure Boundary Wall at Muirpur Airport, Dist, Sonbhadra, UP.

Contract No: 2020_AAI_65165_1

Name of the Bidder/ Bidding Firm / Company :	M/S SURENDRA KUMAR YADAV PROP S K CONSTRUCTION R/O BAREMA POST RAMESHWAR VARANASI
--	---

PRICE SCHEDULE

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
0.1	Civil Works						
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil	Item1	4542.00	Cum	105.00	476910.00	INR Four Lakh Seventy Six Thousand Nine Hundred & Ten Only
2	Filling available excavated earth (excluding rock) in treanches plinth ,sides of foundation etc.in layer not exceeding 20cm in depth .consolidating each deposited layer by ramming and watering ,lead upto 50 m and lift upto 1.5 mtr.	Item2	3972.00	Cum	105.00	417060.00	INR Four Lakh Seventeen Thousand &Sixty Only
3	Extra for every additional lift of 1.5m or part thereof in excavation/banking excavated or stacked materials. a) All kinds of soil	Item3	500.00	Cum	50.00	25000.00	INR Twenty Five Thousand Only
4	Providing and laying in position cement concrete of specified grade excluding cost of centering and shuttering All work upto plinth level. A) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Item4	202.00	Cum	3600.00	727200.00	INR Seven Lakh Twenty Seven Thousand Two Hundred Only
5	Centering and shuttering including strutting, propping etc. and removal of from for all heights. A) Foundations, footing, base of columns, etc. for mass concrete.	Item5	1830.00	Sqm	85.00	155550.00	INR One Lakh Fifty Five Thousand Five Hundred & Fifty Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights. A) Lintel, beams, plinth beams, girder, bressumers, and cantilever.	Item6	2160.00	Sqm	125.00	270000.00	INR Two Lakh Seventy Thousand Only
7	Centering and shuttering including strutting, propping etc. and removal of form for: a) Columns, Pillars, Piers, Abutments, posts and struts.	Item7	2830.00	Sqm	125.00	353750.00	INR Three Lakh Fifty Three Thousand Seven Hundred & Fifty Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	Item8	53560.00	Kg	56.00	2999360.00	INR Twenty Nine Lakh Ninety Nine Thousand Three Hundred & Sixty Only
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	Item9	21650.00	Kg	56.00	1212400.00	INR Twelve Lakh Twelve Thousand Four Hundred Only
10	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. "Excess/ less cement used as per design mix is payable/ recoverable separately). a) All work upto plinth level	Item10	775.00	Cum	5200.00	4030000.00	INR Forty Lakh Thirty Thousand Only
11	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. "Excess/ less cement used as per design mix is payable/ recoverable separately). a) All work above plinth level upto floor V level.	Item11	160.00	Cum	5200.00	832000.00	INR Eight Lakh Thirty Two Thousand Only
12	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in. a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Item12	885.00	Cum	5300.00	4690500.00	INR Forty Six Lakh Ninety Thousand Five Hundred Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
13	Brick work with common burnt clay F.P.S (non modular)bricks of class designation 7.5 in superstructure above plinth level upto floor V level in all shape and sizes in: a) Cement mortar 1:6 (1 cement : 6 coasre sand)	Item13	370.00	Cum	5300.00	1961000.00	INR Nineteen Lakh Sixty One Thousand Only
14	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 fine sand)	Item14	6465.00	Sqm	115.00	743475.00	INR Seven Lakh Forty Three Thousand Four Hundred & Seventy Five Only
15	15 mm cement plaster on the rough side of single or half brick wall of mix : a) 1:6 (1 cement: 6 fine sand)	Item15	6465.00	Sqm	120.00	775800.00	INR Seven Lakh Seventy Five Thousand Eight Hundred Only
16	6 mm cement plaster of mix : a) 1:3 (1 cement: 3 fine sand)	Item16	2564.00	Sqm	120.00	307680.00	INR Three Lakh Seven Thousand Six Hundred & Eighty Only
17	Structural Steel work Riveted bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all completed.	Item17	7400.00	Kg	76.00	562400.00	INR Five Lakh Sixty Two Thousand Four Hundred Only
18	Steel work welded in built up sections/framed work including cutting, hoisting fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. A) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Item18	2000.00	Kg	76.00	152000.00	INR One Lakh Fifty Two Thousand Only
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: a) Two or more coats on new work	Item19	50.00	Sqm	180.00	9000.00	INR Nine Thousand Only
20	Finishing wall with water proofing cement paint of required shade a) New work (two or more coats applied @ 3.84kg/10sqm)	Item20	15500.00	Sqm	60.00	930000.00	INR Nine Lakh Thirty Thousand Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
21	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	Item21	2330.00	Metre	200.00	466000.00	INR Four Lakh Sixty Six Thousand Only
22	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50m lead as per direction of Engineer-in-charge. A) In Cement Mortar	Item22	1500.00	Cum	400.00	600000.00	INR Six Lakh Only
23	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50m lead as per direction of Engineer - In-charge.	Item23	11.00	Cum	1200.00	13200.00	INR Thirteen Thousand Two Hundred Only
24	Carriage of unserviceable material by mechanical transport i/c loading/unloading within Airport premises	Item24	1136.00	Cum	140.00	159040.00	INR One Lakh Fifty Nine Thousand &Forty Only
25	Taking away the serviceable bricks on his own cost and disposal of unserviceable material/malba within AAI premises as per direction and satisfaction of Engineer-in-charge. Disposal cost of malba will be paid separately. 25% quantity will be considered for the executed Item No. 21 for measurement of this item.	Item25	375.00	Cum	2400.00	-900000.00	INR Minus Nine Lakh Only
Total in Figures						21969325.00	INR Two Crore Nineteen Lakh Sixty Nine Thousand Three Hundred & Twenty Five Only
Quoted Rate in Words		INR Two Crore Nineteen Lakh Sixty Nine Thousand Three Hundred & Twenty Five Only					

Signature Not Verified

Digitally signed by SAMIR KUMAR NASKAR
Date: ... : IST
Location: eProcurement System for Central PSUs



प.क. गर्ग
P.K. Garg
उप महाप्रबंधक अभियांत्रिकी (विद्युत)
Dy. General Manager Engg. (Elect.)
भा.वि.प्रा.ला.ब.रा. अन्तर्राष्ट्रीय हवाई अड्डा, वाराणसी