



दिल्ली मेट्रो रेल कॉर्पोरेशन लि० DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का संयुक्त उपक्रम)

(A JOINT VENTURE OF GOVERNMENT OF INDIA AND GOVT. OF DELHI)

CIN: U74899 DL 1995 GOI 068150

No.DMRC/CGM/PD/L-1/WR/

Date 28.01.2021

LOA

To,

M/s GL Contractor

2/167, Subhash Nagar,

New delhi-110027

Mobile No. 9910448774

Email:Lavinhora@gmail.com

Sub: Contract PD-23: Development of Road Pavement between Main Road and Welcome Station entry for access of fire tenders to PD area

- Ref:** (i) Your online e-tender submission on date 14.08.2020.
(ii) Post bid clarifications asked on e-portal dated 24.12.2020.
(iii) Your reply to post bid clarifications submitted online on 30.12.2020.
(iv) Online opening of the financial bids on 20.01.2021

Dear Sir,

1. With reference to above, Letter of Acceptance (LOA) is hereby issued to you for the above mentioned work at the total cost of **INR 13,06,943.29/- (Rupees Thirteen Lakhs Six thousand Nine hundred Forty Three and Twenty Nine Paise only)** inclusive of all central/ state/local taxes/ GST, duties, levies, cess and all other incidental charges required to fulfil the tender conditions including statutory deduction.
2. The total period of contract is **Two (02) Months** from the date of commencement of work as per NIT clause 1.1.2 (n).
3. The period of commencement of work is within Seven (7) days from the date of issue of "Letter of Acceptance" (LOA) or as per the instructions of Engineer-in-charge as per NIT clause 1.1.2 (m).
4. The payment shall be made on the basis of measurement of the actual work done by the contractor.
5. Necessary deductions as per statutory requirement shall be made by DMRC at the time of payment.

UNCONDITIONAL
ACCEPTANCE
FOR GL CONTRACTORS

25, ASHOKA ROAD, (NEAR PATEL CHOWK METRO STATION) New Delhi-110001

Website : www.delhimetrorail.com

6. The contractor shall adhere to guidelines of Delhi Pollution Control Committee (DPCC) to curtail pollution and follow all the statutory laws issued by Govt. of Delhi.
7. The Scope of Work (Annexure-A) and BOQ of works (Annexure-B) are enclosed.
8. You shall ensure full compliance with Tax Laws and labour laws of India with regard to this contract and shall be solely responsible for the same. You shall keep the employer fully indemnified against your liability of tax, interest, penalty etc. respect thereof, which may arise.
9. CGM/PD of this organization will be the Engineer for this contract.
10. You are requested to contact this office immediately for further necessary action in this matter and to start the work.
11. All the work shall be executed in accordance with the specifications stipulated in Tender.
12. This Letter of Acceptance is sent herewith to you in duplicate. You are requested to return one copy of it duly signed by you on all pages indicating "Unconditional Acceptance" thereof so as to reach the undersigned within one week of the receipt of this letter (As per Clause F3 of Instructions to Tenderers (ITT)).
13. It may please be noted that until a formal agreement is executed, this letter will constitute a binding Contract between you and DMRC Ltd. Please take necessary action as required vide Clause Nos. F4 and F5 of Instructions to Tenderers (ITT), regarding signing of agreement and submission of performance security respectively.

Thanking you,

Yours faithfully,

UNCONDITIONAL ACCEPTANCE
For GL CONTRACTORS

Proprietor
29/09/21

DMRC
Deptt.
28, Ashoka Road
New Delhi
(Rajesh Ranjan)

Dy. General Manager/Elect./PD

For and on the behalf of Delhi Metro Rail Corporation Ltd.

Encls: One copy of this letter in Duplicate

CC: DGM/F/PD for kind information please.

SCOPE OF WORKS

1. The contractor will execute the work i.e. "Contract: PD-23: Development of Road pavement between Main road and welcome station entry for access of fire tenders to PD Area."
2. The above mentioned work shall be carried out with contractors own material & labour as per the specifications.
3. The Brief scope of work is mentioned in DSR / BOQ and as per site requirement.
The work under this contract shall consist of, but not limited to, all materials, labour, equipment's, tools, plants and necessary machinery as required to completely execute any or/ and following works within DMRC premises/ scope:
 - Works related to repair and maintenance of drainage systems, water supply systems, etc.
 - Upkeep and routine maintenance related works of office buildings" outer/ inner faces i.e. painting works of inner walls, boundary walls, repairing etc.
 - Any work required for enhancing the outlook of the existing office building.
 - Any other new work.
 - Other miscellaneous items as per instructions of engineer in charge.
 - Additional manpower, if any deployed by contractor, for execution of any Non DSR Item, the rate for manpower to be taken as per Minimum wages.
 - The contractor shall plan & execute the work in such a way that the work proceeds smoothly to the satisfaction of engineer.
 - The Contractor shall attend regular coordination meetings convened by the employer/engineer for interface and adhere to the decisions taken in the meeting.
 - Access will be provided to the staff of the contractor appointed by employer for carrying out their works and bringing materials and Equipments at site. However, the security of materials and Equipments brought at the site will be the responsibility of the Contractor.
 - The Contractor shall take all necessary precautions to ensure safety of the staff, adjoining structures, materials & equipments and the work in progress as per the directions of engineer-in-charge.
 - In case of discrepancy among Standard codes of Practice, Technical Specifications and provision in sub-clause in this NIT, the order of precedence will be as below:
 - (i) Provision in NIT/BOQ.
 - (ii) Technical Specifications
 - (iii) CPWD Specifications
 - (iv) Standard Code of Practice.
 In case of discrepancy among Standard Codes of Practice, the order of precedence will be IRS, IRC, IS, BS, DIN.
4. **Time Schedule:**
The contract period for execution of the above mentioned work is 02 (Two) months from the date of commence of work. The work should start within 7 days of issuance of work order by the competent authority. However the emergency works arisen should be attended promptly.
5. **Specifications:**
CPWD Specifications / IS code are applicable.

For GL CONTRACTORS

Proprietor

29/07/2021

Ranghu

D. M. R. C.
PD Deptt.
25, Ashoka Road
New Delhi

BOQ

BOQ						
Contract PD-23		Development of Road pavement between Main road and welcome station entry for access of fire tenders to PD Area				
SCHEDULE "A" - DSR						
S.no.	DSR 2018 Items	Item Nomenclature	Unit	Rate (in Rs.)	Qty	Amount (in Rs.)
1	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	cum	1737.45	30	52,123.50
2	15.2.1	Nominal concrete 1:3:6 or richer mix (l/c equivalent designmix)				
3	16.82	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	mtr	28.05	8	224.40
4	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in - charge.	cum	2534.7	10	25,347.00
5	15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	kg	4.15	50	207.50
6	1.1.18	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	cum	284.6	25	7,115.00
7	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:	cum	6376.25	10.35	65,994.19
8	6.1.1	Cement mortar 1:4 (1 cement : 4 coarse sand)				
9	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	219.65	100	21,965.00
10	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	cum	181.85	100	18,185.00
11	2.6.1	All kinds of soil				
12	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	cum	6788.6	25	1,69,715.00
13	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)				
14	4.3.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	sqm	609.3	60	36,558.00
15	16.43	Providing and laying design mix cement concrete of M-30 grade, inroads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/less cement used as per design mix is payable/ recoverable separately.				

for GL CONTRACTORS

Proprietor

R. C. R. C.
PD Deptt.
20, Ashoka Road
New Delhi

16	16.43.2	Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	ccum	9153.75	73.125	6,69,367.97
17	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	kg	83.5	3000	2,50,500.00
18	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.				
19	4.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:				
20	4.2.2	1:1½:3 (1 cement : 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	cum	8976.45	30	2,69,293.50
21		Any DSR 2018				1,00,000.00
TOTAL "A"						16,86,596.06
Quoted Rate 22.51 % below						3,79,652.77
Grand Total						13,06,943.29
Rupees Thirteen Lakhs Six thousand Nine hundred Forty Three and Twenty Nine Paise only						

For GL CONTRACTORS

29/01/2021
29/01/2021



Signature Not Verified

Digitally signed by
N.Sai Vasundara
Date: 2021.01.29
15:56:15 IST
Location: eProcure-