

By Post and Email

LETTER OF ACCEPTANCE



No: NHSRCL/BRC/MA/03/Electrical Dismantling PF7/2711.2/OBRC 853

Date: 03.02.2021

M/s. Suparbha Technical Services

Bhardwaj Kutir,
Sunar Mohalla, Hanuman Road,
Raghogarh, Distt. Guna,
Madhya Pradesh-473226

Subject: Tender no.: NHSRCL/BRC/2020/44

Vadodara Division- *Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor*

- Reference:**
1. NIT No. NHSRCL/BRC/2020/44 dated 04.12.2020
 2. Tender No. NHSRCL/BRC/2020/44.
 3. Corrigendum No.01, dated 26.12.2020.
 4. Tender/ bid opened on 04.01.2021
 5. Financial bid opened on 01.02.2021.

Dear Sir,

With reference to above this is to notify you that your offer dated 18.12.2020 for execution of the "Tender no.: NHSRCL/BRC/2020/44 - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor" for the Accepted Contract Amount of the equivalent of Rs. 26,54,047.84 (inclusive of GST) (in words: Rupees Twenty-Six Lakhs Fifty-Four Thousand Forty-Seven and Paise Eighty-Four only), as corrected and modified in accordance with the Instructions to Tenderers, is hereby accepted by the Employer.



AP/ma
03/02/2021

नेशनल हाई स्पीड रेल कॉर्पोरेशन लिमिटेड
(केन्द्र सरकार एवं भाग लेने वाली राज्य सरकारों की संयुक्त क्षेत्र कंपनी)

National High Speed Rail Corporation Limited
(A Joint sector company of Govt. of India and participating State Governments)

परियोजना कार्यालय : तृतीय तल, उत्पादकता हाउस, उत्पादकता रोड, अलकापुरी, वडोदरा - 390007
Project Office: 3rd Floor, Productivity House, Productivity Road, Alkapuri, Vadodara - 390007
Phone No (Office): 265-2600000, Email id: cpmbrcl@nhsrcl.in
पंजीकृत कार्यालय : एशिया भवन, द्वितीय तल, रोड नम्बर 205, सेक्टर 9, द्वारका, नई दिल्ली - 110077
Registered Office: Asia Bhavan, 2nd Floor, Road No. 205, Section 9, Dwarka, New Delhi - 110077
+91-11-28070001/02/03/04, +91-11-28070150, Email id: psmd@nhsrcl.in
CIN No. U60200DL2016GOI291002

f / NHSRCL @nhsrcl www.nhsrcl.in

The scope of work, accepted rates and terms and conditions applicable to this Letter of Acceptance are as under:

1. Scope of Work:

- 1.1. Scope of work under this contract shall include Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor as specified in schedule of work, specification as per GCC, PCC and other documents as stipulated in the tender documents but not restricted to.
- 1.2. The supply of entire materials in accordance with specification and the whole of the work necessary for the complete installation as set down in this specification and with the accompanying schedules and drawings. Materials and components not specifically stated in the specifications and/or bill of materials or noted on the drawings or anywhere in tender document but which are necessary for satisfactory installation /commissioning and operation of the system shall be deemed to have been included in the scope of work.
- 1.3. The work will be supervised by Senior Divisional Elect. Engineer/Power, Vadodara, Western Railway or his authorized representative. However, payment will be made by NHSRCL on the basis of work certified by Senior Divisional Elect. Engineer/Power, Western Railway, Pratapnagar, Vadodara-390004.

2. Accepted rates and payment schedule are mentioned hereunder:

S. No	Schedule	Basic Value	Rate quoted in % age.	Amount
1	Schedule 'A': Supply & Erection	28,88,288	8.11% below	26,54,047.84
	Grand Total Rs.			26,54,047.84
Total Amount in words:				
Rupees Twenty-Six Lakhs Fifty-Four Thousand Forty Seven and Paisa Eighty Four only.				



APingl
03/02/2021

3. You are hereby requested to please contact **Chief Project Manager, National High-Speed Rail Corporation Limited, Vadodara** to make necessary arrangement to take the work in hand.
4. This Letter of Acceptance shall be treated as "**Notice of Commencement**" **w.e.f. 03.02.2021**, failing which National High-Speed Rail Corporation Limited administration reserve right to take action as per Condition of Contract.
5. The completion period of above work will be **180 (One Hundred and Eighty) days** from the date of commencement (**i.e. up to 02.08.2021**) which may please be noted.
6. Please advise maximum / minimum number of labour that you will engage on the above work contract and register this work with concerned labour department at Vadodara and Ahmedabad.
7. You are also requested to observe the provision of contract labour act (R&A) 1971. So please advise maximum/minimum number of labour that will be engaged by you on the above work. Any failure of the provision of the said act that will attract penal provision, which may please be noted. Necessary certificate authorizing your engagement is enclosed herewith. Information required as per form VI may be submitted to LEO/(c)/Vadodara & Ahmedabad endorsing the copy to this office immediately on commencement to the work. Unless and until formal agreement is made and got executed, this acceptance letter along with all the tender conditions will constitute a legal binding contract between NHSRCL and contractor **M/s. Suparbha Technical Services**, Bhardwaj Kutir, Sunar Mohalla, Hanuman Road, Raghogarh, Distt. Guna, Madhya Pradesh-473226.
8. The contractor would be required to furnish the name, with complete bio-data including the work experience of the project personnel to the Chief Project Manager / Engineer in charge of work, for his approval.



You are requested to furnish the Performance Security within 30 days in accordance with the Conditions of Contract, using for that purpose one of the Performance Security Forms included in Annexure to ITT.

Please acknowledge the receipt.

Thanking you,



AB/03/02/2021
Dy. Chief Project Manager,

**National High-Speed Rail Corporation Limited,
Vadodara**

Encl: Bill of Quantities (5 pages)


Copy to:

- (1) Labour Enforcement Officer, (Central), Chandrababha Flats No.2, Krishna Nagar Society, Opp. Moti Baug Palace, Vadodara. 390 001.
- (2) Regional Labour commissioner, (Central). Chandrababha Flats No.2, Krishna Nagar Society, Opp. Moti Baug Palace, Vadodara. 390 001.
- (3) G.M Contract of New Delhi for information & Necessary Action Please.
- (4) D.G.M. Finance Manager, New Delhi for information and action please.
- (5) D.G.M. Finance Manager, Vadodara for information and action please

Schedule-A

Name of work: - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor.


Sr No	Description	Unit	Unit Rate (₹)	Qty	Total Amount (₹)
	BRCP				
1	Removing of all existing LT panels of different sizes and distribution boards with clamps and handed over to SSEE/P/BRCP office depot/store.	Nos	1,680.00	11.00	18,480.00
2	Removing of existing 12 Mtrs. high mast complete with all accessories and reinstall at suitable locations as decided by railway, including construction of new foundation, new foundation bolts and templates	Nos	78,500.00	1.00	78,500.00
3	Removing of 3 phase pump set with all column pipe and all accessories with control panels and hand over to SSEE/P/BRCP office depot/store	set	7,840.00	1.00	7,840.00
4	Removing of all existing rail/round/octagonal poles with street light fitting/clamps/pipe etc and shifting of the same to the depot as per technical specification	Nos	1,787.00	70.00	1,25,090.00
5	Providing 100 mm diameter cast Iron pipe by pushing method	Mtrs	1,985.00	160.00	3,17,600.00
6	Digging of cable trench 100 mm wide & 200 mm deep on concrete/tar road/platform & refilling to its original position.	Mtrs	266.00	500.00	1,33,000.00
7	Digging of cable trench 600x900 mm in all types of soil including Hard , rocky etc.	Mtrs	51.00	1,700.00	86,700.00
8	Laying of bricks and sand for double cable	Mtrs	80.00	1,700.00	1,36,000.00
9	Laying of cable in existing trench/pipe in trench	Mtrs	15.00	3,100.00	46,500.00
10	Laying of cable on wall/cover shed/existing tray with MS clamp	Mtrs	25.00	1,500.00	37,500.00
11	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 300 sq. mm	Mtrs	1,010.00	240.00	2,42,400.00



ABN/1
03/02/2021

Name of work: - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor.


Sr No	Description	Unit	Unit Rate (₹)	Qty	Total Amount (₹)
	BRCP				
12	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 185 sq. mm	Mtrs	590.00	300.00	1,77,000.00
13	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 95 sq. mm	Mtrs	359.00	300.00	1,07,700.00
14	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 25 sq. mm	Mtrs	80.00	500.00	40,000.00
15	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 10 sq. mm	Mtrs	72.00	300.00	21,600.00
16	Supply of XLPE insulated, PVC sheathed armoured LTUG aluminium cable 4 core, 6 sq. mm	Mtrs	65.00	240.00	15,600.00
17	S/F/T/C of 5 mtr height GI street light octagonal pole, double arm complete with all accessories with foundation	Nos	13,105.00	10.00	1,31,050.00
18	Supply of LED street light luminaries of 45 watt complete with all accessories	Nos	550.00	20.00	11,000.00
19	FTC of LED flood light fittings on octagonal pole/high mast	Nos	97.00	20.00	1,940.00
20	Providing cable marker (HT/LT)	Nos	162.00	60.00	9,720.00
21	Providing LT panel board outdoor type, floor mounted with I/C MCCB, 4 pole 125 Amp, -2 Nos, and O/G MCCB, 4 pole, 40 Amp-02 nos, MCCB, 4P, 32 Amp- 2 nos with multi-functional energy meter EMFIS with communication port	Nos	70,227.00	1.00	70,227.00
22	Providing LT panel board outdoor type, floor mounted with incomer MCCB, 4P, 250 Amp - 2 nos, and O/G MCCB, 4 pole, 125 Amp-02 nos, MCCB, 4-pole, 100 Amp- 2 nos with multi-functional energy meter EMFIS with communication port	Nos	1,27,950.00	1.00	1,27,950.00



AKing
03/02/2021

Name of work: - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor.


Sr No	Description	Unit	Unit Rate (₹)	Qty	Total Amount (₹)
	BRCP				
23	Providing G. I. pipe earthing	Nos	2,429.00	14.00	34,006.00
24	Removing of all existing fitting with clamp and hand over to site office store	Nos	45.00	100.00	4,500.00
25	Removing of all existing cables of various sizes and hand over to site office store	Mtrs	9.00	2,000.00	18,000.00
26	Removing of all existing 05 wire catenary /sub mains with clamp, pipe, casing capping etc. and hand over to site office store	Mtrs	11.00	1,200.00	13,200.00
27	Removing of all existing signage's boards with clamps and hand over to site office store	Nos	112.00	20.00	2,240.00
28	Removing of all existing water coolers with accessories and hand over to site office store	Nos	560.00	4.00	2,240.00
29	Removing of all existing train examination light + rajdhani light fittings with accessories and hand over to site office store	Nos	78.00	60.00	4,680.00
30	Removing of all existing 3 phase battery charger 440/110 DC, 300 Amp with all fittings, clamps, pipe etc and hand over to site office store	Nos	2,800.00	1.00	2,800.00
31	Removing of all existing 3 phase battery charger 440/110 DC, 200 Amp with all fittings, clamps, pipe etc and hand over to site office store	Nos	2,800.00	1.00	2,800.00
32	Removing of all existing 1 phase transformers 3 KVA, 230/110 Volts with all fittings, clamps, pipe etc. and hand over to site office store	Nos	336.00	3.00	1,008.00
33	Removing of all existing cable tray of various sizes with clamps, fittings, support etc. and hand over to site office	Mtrs	11.00	400.00	4,400.00
	Total for BRCP (A)				20,33,271.00



AB/191
03/04/2021

Name of work: - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor.

Sr No	Description	Unit	Unit Rate (₹)	Qty	Total Amount (₹)
	BRCY				
34	Supply of XLPE insulated and PVC sheathed, armoured LTUG Aluminum cable, four-core, 35 mm ²	Mtrs	90.00	1,250.00	1,12,500.00
35	Digging of cable trench 450x900 mm in all types of soil including Hard , rocky etc. (500m x 0.45m x 0.9m =202.5cum)	Cum	101.00	203.00	20,503.00
36	Supply and laying of HDPE pipe, 160 mm dia, by pushing method under track	Mtrs	934.00	100.00	93,400.00
37	Supply and laying of RCC half round pipe 150 mm ID and 1 Mtrs length	Mtrs	57.00	500.00	28,500.00
38	Dismantling of existing FL mast 20 mtrs height, in pieces complete with all accessories and transportation of the same from site to PRTN scrap depot for DS8	Nos	33,600.00	1.00	33,600.00
39	Removing of existing 20 Mtrs. high mast complete with all accessories and reinstall at suitable locations as decided by railway, including construction of new foundation, new foundation bolts and templates	Nos	1,23,200.00	2.00	2,46,400.00
40	Design, supply, erection, testing and commissioning of 12 mtrs High Mast complete with Design, supply, erection, testing and commissioning of high Mast complete with accessories	Nos	1,96,298.00	1.00	1,96,298.00
41	Supply of LED flood light fittings 150 Watt as per CEE/WR specification	Nos	7,501.00	6.00	45,006.00
42	FTC of LED flood light fittings on octagonal pole/high mast	Nos	97.00	6.00	582.00
43	Providing controlling board with time switch and contactor	Nos	3,986.00	2.00	7,972.00
44	Providing double door DB with I/C MCCB 4P 63 Amp-1 No, ELCB 4P,100 mA, 40 Amp-1 no. and O/G MCB TPN 32 Amp-2 nos, & MCB DP 16/32 Amp-4 Nos.	Nos	26,960.00	1.00	26,960.00
45	Providing G. I. pipe earthing	Nos	2,429.00	6.00	14,574.00



Handwritten signature
03/02/2021

Name of work: - Vadodara Division- Electrical dismantling work Associated with PF No. 7 at Vadodara Railway station and shifting of existing Electrical utilities between KM 394 to 400 in connection with High Speed Rail Corridor.

Sr No	Description	Unit	Unit Rate (₹)	Qty	Total Amount (₹)
	BRCY				
46	Removing of all existing rail/round/octagonal poles with street light fitting/clamps/pipe etc and shifting of the same to the depot as per technical specification	Nos	1,787.00	6.00	10,722.00
47	Laying of cable in existing trench/pipe in trench/pipe in trench	Mtrs	15.00	1,200.00	18,000.00
i	Total for BRCY (B)				8,55,017.00
ii	Total Basic Cost (A+B)				28,88,288.00
iii	Quoted Rate by Contractor on Basic Cost (ii)				-8.11% below
iv	Final Value of Work in INR				26,54,047.84



Signature Not Verified

Digitally signed by Abodh Kumar
Date: 2021.02.03 19:07:30 GMT+05:30
Location: eProcurement System for Central PSUs