

By Post and Email

LETTER OF ACCEPTANCE

No: NHSRCL/BRC/MA/03/GSFC-works/244/2/OBRC 886

Date: 08.02.2021

M/s R S Enterprises,
Nilgiri Apartments, Shop No. 3A,
Sec. 6, Nerul, Navi Mumbai – 400706.
Email: rsenterprises1406@gmail.com

Subject: Tender no.: NHSRCL/BRC/2020/47

Construction of Boundary Wall inside GSFC Campus, and other miscellaneous works inside GSFC Campus in connection with Mumbai-Ahmedabad High Speed Rail Project.

- Reference:**
1. NIT no. NHSRCL/BRC/2020/47 dated 28.12.2020
 2. Tender No. **NHSRCL/BRC/2020/47.**
 3. Tender opened on 19.01.2021
 4. Financial bid opened on 03.02.2021.
 5. Negotiation held on 05.02.2021.
 6. Your letter dated 05.02.2021 regarding revised offer.

Dear Sir,

With reference to above this is to notify you that your revised offer dated 05.02.2021 for execution of the "Tender no.: NHSRCL/BRC/2020/47 - Construction of Boundary Wall inside GSFC Campus, and other miscellaneous works inside GSFC Campus in connection with Mumbai-Ahmedabad High Speed Rail Project." for the Accepted Contract Amount of the equivalent of Rs. 44,54,637.88 (inclusive of GST.) (in words: Forty-Four Lakh Fifty-Four Thousand Six Hundred Thirty-Seven Rupees and Eighty-Eight Paise only), as corrected and modified in accordance with the Instructions to Tenderers, is hereby accepted by the Employer.

नेशनल हाई स्पीड रेल कोर्पोरेशन लिमिटेड
(केन्द्र सरकार एवं भाग लेने वाली राज्य सरकारों की संयुक्त क्षेत्र कंपनी)

National High Speed Rail Corporation Limited
(A Joint sector company of Govt. of India and participating State Governments)

परियोजना कार्यालय : तृतीय तल, उत्पादकता हाउस, उत्पादकता रोड, अलकापुरी, वडोदरा - 390007
Project Office: 3rd Floor, Productivity House, Productivity Road, Alkapuri, Vadodara - 390007
Phone No (Office): 265-2600000, Email id: cpmbrc@nhsrcl.in
पंजीकृत कार्यालय : एशिया भवन, द्वितीय तल, रोड नम्बर 205, सेक्टर 9, द्वारका, नई दिल्ली - 110077
Registered Office: Asia Bhavan, 2nd Floor, Road No. 205, Section 9, Dwarka, New Delhi - 110077
+91-11-28070001/02/03/04, +91-11-28070150, Email id: psmd@nhsrcl.in
CIN No. U60200DL2016GOI291002

The scope of work, accepted rates and terms and conditions applicable to this Letter of Acceptance are as under:

1. Scope of Work:
 - 1.1. The work is being done to acquire the plot inside existing GSFC campus for the construction of High Speed Rail Corridor. The boundary wall is to be handed over to end user i.e. GSFC after completion of work by contractor. All works should be executed with good quality of construction standard and under strict supervision.
 - 1.2. Construction of Boundary wall for full height (3.5 to 5.0m) with construction joints & Concertina Wire as per existing boundary wall.
 - 1.3. Providing and fixing of Concertina Wire / Coil Fencing with punched tape concertina coil 600 mm dia. 10-meter openable length at the top of the wall & fixed to Y frame (made from MS Angle) embedded to wall and sharp glass pieces on top of wall.
 - 1.4. Supply and fixing of Y Frame made from MS Angle of size not less than 50 x 50 x 6 mm at every 2.5 m spacing for fixing of Concertina Wire.
 - 1.5. Raised and cut pointing on brick work on both faces of the wall with cement mortar 1:3 (1 cement: 3 fine sand). Supply and fixing sharp glass pieces with cement mortar 1:4 on top of the wall.
 - 1.6. All the equipment for the execution of work, materials for construction, temporary works for storing, scaffolding, curing, manpower, water, electricity etc. is in the scope of contractor.
 - 1.7. Design and execution of all temporary works necessary for the civil construction shall be carried out by the Contractor at his own cost.
 - 1.8. For excavation work suitable arrangement for breaking/ dismantling of asphalt/ concrete road, walls etc. by JCB/pneumatic breaker will be done by Contractor.


Dy. Chief Project Manager-Civil
उप मुख्य परियोजना प्रबंधक-सिविल
National High Speed Rail Corporation Ltd.
राष्ट्रीय उच्च गति रेल निगम लिमिटेड
वडोदरा / Vadodara

- 1.9. Cutting of trees, bushes and cleaning & cutting of vegetation is to be done by contractor as required.
- 1.10. Brick work shall be laid in English bond or as directed by Engineer-in-Charge. Entire Brick work shall be raised uniformly no portion shall be raised more than one meter higher than the adjoining portion with joints raked at the end of each day's work so as to receive pointing at later stage. Level of brick work shall be checked at every 0.75 meter interval and all uneven, irregular, disturbed bricks shall be pulled down and rebuilt with fresh brick work at the contractor's expense.
- 1.11. Fresh Brick masonry work shall be protected from rain if any, by suitable covering and entire work shall be cured for at least 14 days after completion.
- 1.12. Coping Concrete cube testing & material testing for construction of boundary wall, as and when required as per relevant IS code or as per instruction of Engineer in Charge shall be carried out at the cost of contractor.
- 1.13. All safety precautions for working inside GSFC campus are to be taken by the Contractor. All arrangements for same, like providing safety tape/ barriers around excavated area or construction are to be made available by the Contractor.
- 1.14. Appropriate PPE, barricade and proper scaffolding should be used at site for the safety of team members, GSFC Personal & GSFC property on site.
- 1.15. Contractor shall ensure the presence of their engineer and supervisor full time during execution of work at site.
- 1.16. All the statutory compliances for the execution of the work shall be taken care by the Contractor. Including Entry, Exit of labours and materials inside GSFC campus as per GSFC rules and regulations.
- 1.17. NHSRCL shall not be in any manner whatsoever liable for any incidence of accident, damage or injury to any person or property that may occur during


Dy. Chief Project Manager-Civil
उप मुख्य परियोजना प्रबंधक-सिविल
National High Speed Rail Corporation Ltd.
राष्ट्रीय उच्च गति रेल निगम लिमिटेड
वडोदरा / Vadodara

the execution of the work. Contractor shall also be liable to make good the loss/damage, if any caused to NHSRCL or GSFC due to the work.

- 1.18. The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor and his workers & suppliers shall abide at all times by all existing rules and regulations of GSFC and all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.
 - 1.19. The Contractor shall be responsible for the Health & Safety of staff, labour, Works, Plant, Contractor's Equipment, Temporary Works throughout the execution of the Works.
 - 1.20. The Contractor shall co-ordinate with the other agencies such as civil, security, safety of GSFC in the area and works in close liaison with them for execution of works and its requirements of electricity, water, entry, exit of labours, materials etc.
 - 1.21. The Contractor shall prepare a programme for completion of various works within 07 days of awarding the contract in consultation with the Employer and submit the same to the Employer.
 - 1.22. The work should not be hampered / affected due to non-availability of manpower, Materials or supervision.
 - 1.23. The work completed in all respect is to be handed over to full satisfaction of GSFC i.e. end user.
2. Accepted rates and payment schedule are mention hereunder:


Dy. Chief Project Manager-Civil
उप मुख्य परियोजना प्रबंधक-सिविल
National High Speed Rail Corporation Ltd.
राष्ट्रीय उच्च गति रेल निगम लिमिटेड
वडोदरा / Vadodara

S. No	Schedule	Basic Value	Rate quoted in % age.	Amount
1	Schedule 'A': Total 16 items related to civil works	29,90,624.29	43.64% above	42,95,733.20
2	Schedule 'B': Total 3 items related to civil works	1,22,677.90	29.53% Above	1,58,904.68
	Grand Total Rs.	31,13,302.19		44,54,637.88
Total Amount in words: Forty-Four Lakh Fifty-Four Thousand Six Hundred Thirty-Seven Rupees and Eighty-Eight Paise only.				

3. You are hereby requested to please contact **Chief Project Manager, National High-Speed Rail Corporation Limited, Vadodara** to make necessary arrangement to take the work in hand.
4. This Letter of Acceptance shall be treated as "**Notice of Commencement**", failing which National High-Speed Rail Corporation Limited administration reserve right to take action as per Condition of Contract.
5. The completion period of above work will be **90 (Ninety) days (i.e. 09.05.2021)** from the date of commencement which may please be noted.
6. Please advise maximum / minimum number of labour that you will engage on the above work contract and register this work with concerned labour department at Vadodara.
7. You are also requested to observe the provision of contract labour act (R&A) 1971. So please advise maximum/minimum number of labour that will be engaged by you on the above work. Any failure of the provision of the said act that will attract penal provision, which may please be noted. Necessary certificate authorizing your engagement is enclosed herewith. Information


Dy. Chief Project Manager-Civil
 उप मुख्य परियोजना प्रबंधक-सिविल
 National High Speed Rail Corporation Ltd.
 राष्ट्रीय उच्च गति रेल निगम लिमिटेड
 वडोदरा / Vadodara

required as per form VI may be submitted to LEO/(c)/Vadodara endorsing the copy to this office immediately on commencement to the work.

8. Unless and until formal agreement is made and got executed, this acceptance letter along with all the tender conditions will constitute a legal binding contract between NHSRCL and contractor M/s R S Enterprises, Nilgiri Apartments, Shop No. 3A, Sec. 6, Nerul, Navi Mumbai – 400706.
9. The contractor would be required to furnish the name, with complete bio-data including the work experience of the project personnel to the Chief Project Manager / Engineer in charge of work, for his approval.

You are requested to furnish the Performance Security within 30 days in accordance with the Conditions of Contract, as per the Performance Security Forms included in Annexure to ITT.

Please acknowledge the receipt.
Thanking you,


Dy. Chief Project Manager,
National High-Speed Rail Corporation Limited,
Vadodara

Encl: Bill of Quantities (02 pages)

Copy to:

- (1) Labour Enforcement Officer, (Central), Chandrababha Flats No.2, Krishna Nagar Society, Opp. Moti Baug Palace, Vadodara. 390 001.
- (2) Regional Labour commissioner, (Central). Chandrababha Flats No.2, Krishna Nagar Society, Opp. Moti Baug Palace, Vadodara. 390 001.
- (3) G.M Contract of New Delhi for information & Necessary Action Please.
- (4) D.G.M. Finance Manager, New Delhi for information and action please.
- (5) D.G.M. Finance Manager, Vadodara for information and action please


Dy. Chief Project Manager-Civil
उप मुख्य परियोजना प्रबंधक-सिविल
National High Speed Rail Corporation Ltd.
राष्ट्रीय उच्च गति रेल निगम लिमिटेड
वडोदरा / Vadodara

GSFC Boundary wall work					
S. No	Particulars	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Schedule-A					
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	Sqm	460.8	7.16	3,299.33
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge				
2.1	All kinds of soil	Cum	459.36	109.36	50,235.61
3	Providing and laying Brick Bat/black trap rubble soling 230mm thick at required level and grade in foundation, plinth, in ramps etc. including hand packing filling interstices with quarry spalls and sand, watering and compacting suitable earth compactor.	Cum	47.52	1444.79	68,656.42
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Cum	47.52	1369.72	65,089.09
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	133.92	2334.67	312,659.01
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and above plinth level and below plinth level.Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	385.008	2334.67	898,866.63
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	230.4	129.35	29,802.24
8	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)				
8.1	RCC Coping above Brick work at above plinth level and below plinth level.	Cum	62.9608	1645.73	103,616.48
9	Supply and using cement at worksite : OPC 53 grade	tonne	36.67	4830	177,116.10
10	Pointing on brick work or brick flooring with cement mortar 1:3 (1 cement : 3 fine sand)above plinth level and below plinth level: Raised and cut pointing	Sqm	2731.12	77.29	211,088.26
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level and below plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more for the RCC Coping	Kg	4942.423	57.94	286,363.99
12	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers for the Coping.above plinth level and below plinth level.	Sqm	264.008	253.33	66,881.15

Dy. Chief Project Manager-Civil

उप मुख्या परियोजना प्रबंधक-सिविल

GSFC, Gandhinagar, Gandhinagar, Gandhinagar, Gandhinagar

GSFC Boundary wall work					
S. No	Particulars	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
13	Fixing sharp glass pieces in cement mortar 1:4 at top of wall	Sqm	120.005	101.85	12,222.51
14	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately) at top of wall	Rm	480.02	212.34	101,927.45
15	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete MS Angle for Concertina Wire Considered 50 x 50 x 6 mm at every 2.5 m spacing L = 450 mm in side wall + 300 mm above wall + 450 mm on both side to form Y shape at top of wall.	Kg	1425.6	72.11	102,800.02
16	Misc. SOR Items	LS	1		500,000.00
Total Schedule-A					2,990,624.29
Schedule-B					
17	Hire and running charges of crane 20 tonne capacity	Day	10.00		
18	Providing road crane of different capacity with diff. jib length revolving type for material handling, assembly & erection of girders/slab/RCC Box etc. - 25 MT capacity with 60 feet jib	Day	5.00	4,187.21	20,936.05
19	Providing road crane of different capacity with diff. jib length revolving type for material handling, assembly & erection of girders/slab/RCC Box etc. - 12MT capacity with 36 feet jib	Day	5.00	3,349.77	16,748.85
20	Hire and running charges of loader	Day	10.00		
21	Hiring of JCB Machine (in good working condition) for leveling and dressing ground / dismantling structures including disposal of debris through dumpers etc. with contractor's labour, JCB machine, machine operator, fuel, etc. The contractor shall arrange road permit for vehicle for all the States of operation, as per instructions of engineer in-charge and vehicle shall not be more than three years old. Payment shall be made for actual working hours at site.	Hour	100.00	849.93	84,993.00
Total Schedule B					122,677.90
TOTAL Schedule (A+B)					3,113,302.19

Signature Not Verified

Digitally signed by Abodh Kumar
Date: 2021.02.08 17:30:57 GMT+05:30
Location: eProcurement System for
Central PSUs