



Ref. No: AAI/HUB/ENGG-E/Perimeter/WO-01/2021-22/1558-69

Date: 19.04.2021

//By Speed Post/ Email//

सेवा में/ To

मेसर्स . आरबी मल्टीटेक/M/s. R. B. Multitech,

अमरनाथ इंडा पार्क की/ 5 Amarnath IND. Park NR.,

मक्का उत्पाद मिल/ Maize product Mill,

ओधव –सिंगरवा रोड सिंगरवा/ Odhav –Singarava Road Singarva,

अहमदाबाद/Ahmedabad – 382 430.

कार्य का नाम/ Name of Work:- प्रावधान है कि हुबबल्ली हवाई अड्डे पर अलगाव के बाद नई परिधि सड़क के लिए परिधि सड़क प्रकाश।/ Provision of Perimeter road lighting for New Perimeter Road after segregation at Hubballi Airport."

संदर्भ/ Ref: 1) AAI Tender Id :- 2021_AAI_67233_1

2) Your E-Tender (Financial Bid) opened on 09.02.2021.

महोदय/ Dear Sir,

1. अध्यक्ष, भा. वि. प्रा. की ओर से उपरोक्त कार्य हेतु आपकी निविदा को कुल बातचीत की गई राशि रु.33,10,683.00 (Excluding GST) रुपए तैंतीस लाख दस हजार छह सौ और तिरासी केवल (जीएसटी छोड़कर) जो अनुमानित लागत रु.47,28,646.00 से 29.99% नीचे है, एतद्वारा स्वीकार किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs.33,10,683.00 (Thirty Three Lakhs Ten Thousand Six Hundred and Eighty Three Only)** which is **29.99% Below** the justified cost of **Rs. 47,28,646.00 (Rupees Forty Seven Lakhs Twenty Eight Thousand Six Hundred and Forty Six Only)** Excluding GST.

2. सहायक महाप्रबंधक (इंजिनियरिंग-विद्युत) एएआई, हुबबल्ली हवाई अड्डा इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने के लिए निर्धारित दिनांक:03.05.2021 तक सहायक महाप्रबंधक (इंजी-विद्युत) भा.वि.प्रा हुबबल्लि हवाई अड्डा, हुबबल्लि के कार्यालय में उपस्थित हों। संविदा करार को



रुपये 100/- (केवल एक सौ रूपए) मूल्य के एक गैर न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर के मूल्य को आपके द्वारा वहन किया जाएगा.

Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi shall be the Engineer -In-Charge of this work. You are requested to attend the office of Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi by 03.05.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees Hundred Only) and the cost of the stamp paper shall be borne by you.

3. एनएटी क्लॉज़ -2 के अनुसार, अर्नेस्ट मनी अमाउंट में छूट दी गई थी। ₹. 3,31,068.00 (रुपए तीन लाख इकतीस हजार अड़सठ केवल) की कुल जमा करें, अन्यथा अनुबंध दस्तावेज़ के पृष्ठ संख्या जी.सी.सी-19 पर अनुबंध के खंड 1-ए के अनुसार बकाया सुरक्षा राशि को चालूबिलों में से काटा जायेगा.

The Earnest Money Deposit Amount of **was exempted as per NIT clause -2.**, you are hereby advised to deposit **Rs. 3,31,068.00 (Rupees Three Lakhs Thirty One Thousand Sixty Eight Only)** towards security deposit within 10 days after the date of issue of this letter, failing which the same will be deducted as per Tender Condition Clause 1-A of page GCC-18 of contract document.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970, ठेका श्रम (विनियमन एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार और विनियमनका अधिनियम) के प्रावधानों का पालन करने का अनुरोध किया जाता है सेवा की शर्तें) अधिनियम 1996, भवन और अन्यनिर्माण श्रमिक कल्याण अधिनियम 1996, जैसा कि केंद्र और राज्य सरकारों के, जोकी निविदा खंड संख्या-19 जीसीसी के नियमों के पृष्ठ संख्या 53 से 59 में निर्दिष्ट है।

You are requested to comply with the provisions of contract labor (Regulation and abolition) act of 1970 and contract labor (Regulation and abolition) Central rules 1971, Child labor (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other construction workers welfare Cess Act 1996 as specified in Clause-19 on Page No.53 to 59 of GCC of tender and rules of Central and State Governments.



5. आपको यह भी निदेश दिए जाते हैं कि आप प्रबंधक (इंजिनियरिंग-विद्युत), हुबल्ली हवाई अड्डा, हुबल्ली से तुरंत संपर्क करें जो आपको साइट सौंपने के लिए व्यवस्था करे

You are also directed to contact Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi immediately, who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि इस कार्य को पूरा करने की अवधि **04 (चार) महीने** और इसी कार्य आदेश के 10th वें दिन से i.e. **29.04.2021** तक प्रतिपूर्ति की जाएगी।

Please note that the time allowed for carrying out the work shall be **04 (Three) Months** and same shall be reckoned from the 10th day of placement of this work order i.e. **29.04.2021**

7. अनुबंध के संबंध में किसी भी आगे के पत्राचार को आमतौर पर असिस्ट को संबोधित किया जाना चाहिए। जनरल मैनेजर (इंजी-इलेक्ट), हुबल्ली हवाई अड्डा, जो इस काम के इंजीनियरिंग-इंचार्ज होंगे।

Any further correspondence in connection with the contract should normally be addressed to the Asst. Gen. Manager (Engg- Elect), Hubballi Airport, who will be the Engineering-In-charge of this work.

8. कृपया पावती भेजें एवं इस पत्र के साथ संलग्न इसकी प्रतिलिपि पर हस्ताक्षर करते हुए उसे स्वीकृति के तौर पर अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as token of acceptance.

9. If any grammatical mistakes in Hindi version, the English version will supersede Hindi version.

भवदीय/Yours faithfully,

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg- Elect)

कृते एवं अध्यक्ष की ओर से/ For and on behalf of the Chairman,

भा.वि.प्रा/ Airports Authority of India,

हुबल्ली हवाई अड्डा/Hubballi Airport, Hubballi

संलग्न/ Encl:

1. Schedule



प्रतिलिपि / Copy To :- Internal

1. महा प्रबंधक (इंजी-वि), भाविप्रा, दक्षिणी क्षेत्र, भाविप्रा, चेन्नई हवाई अड्डा, चेन्नई/
General Manager (Engg-E), Southern Region, AAI, Chennai Airport, Chennai – 17
2. महा प्रबंधक (एफएंडए), दक्षिणी क्षेत्र, भाविप्रा, चेन्नई हवाई अड्डा, चेन्नई/ General
Manager (F&A), Southern Region, AAI, Chennai Airport, Chennai – 17
3. संयुक्त महा प्रबंधक (सतर्कता), दक्षिणी क्षेत्र, भाविप्रा, चेन्नई हवाई अड्डा, चेन्नई/ Jt.
General Manager (Vigilance), Southern Region, AAI, Chennai Airport, Chennai – 17
4. उप महा प्रबंधक (इंजी-वि.), दक्षिणी क्षेत्र, भाविप्रा, चेन्नई हवाई अड्डा, चेन्नई/ DGM
(Engg-E), Southern Region, AAI, Chennai Airport, Chennai – 17.
5. विमान पत्तन निदेशक, भाविप्रा, हुबबल्ली हवाई अड्डा, हुबबल्ली/ Airport Director, AAI,
Hubballi Airport, Hubballi-30.
6. उप महा प्रबंधक (इंजी-सी), भाविप्रा, हुबबल्ली हवाई अड्डा, हुबबल्ली/ DGM (Engg-C),
AAI, Hubballi Airport, Hubballi.
7. प्रबंधक (इंजी- वि.), भाविप्रा, हुबबल्ली हवाई अड्डा, हुबबल्ली/ Manager(Engg-E), AAI,
Hubballi Airport, Hubballi.
8. समझौते की प्रति/ Agreement copy
9. फ़ाइल/ File

External

1. कार्मिक सलगत अधिकारी, सीटीएस , HDMC पार्क के सामने , भवानी नगर लास्ट बस
स्टॉप के पास, भवानी नागर, हुबबल्ली-580023/ Labour Enforcement Officer, No.2733
/4B/ CTS. No.2733/ 4B, 1st Floor, (Opposite to HDMC Park), Near Bhavani Nagar
Last Bus Stop, Bhavani Nagar, Hubballi-580023.
2. उप क्षेत्रीय केंद्रीय भविष्य निधि आयुक्त, उप क्षेत्रीय कार्यालय, चौथी मंजिल, श्रीनाथ
कॉम्प्लेक्स, न्यू कॉटन मार्केट, पी.बी. संख्या: 620, हुबबल्ली/ Sub Regional Central
Provident Fund Commissioner, Sub Regional Office, 4th Floor, Srinath Complex,
New Cotton Market, P.B.No:620, Hubballi.


19/04/2021

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg. – Elect)
भा.वि.प्रा/ Airports Authority of India,
हुबबल्ली हवाई अड्डा/Hubballi Airport, Hubballi

Schedule of Quantity


कार्यकानाम/ Name of work : हुबबल्ली हवाई अड्डे पर अलगाव के बाद नई परिधि सड़क के लिए परिधि सड़क प्रकाश का प्रावधान।/ Provision of Perimeter road lighting for New Perimeter Road after segregation at Hubballi Airport."

Item No.	Description of Item	Unit	Qty.	Rate	Amount
1.00	SH-I SUPPLY OF LT POWER CABLES Supplying of 4C X 16 sqmm aluminium conductor armoured XLPE insulated, PVC sheathed power cable for working voltage upto & i/c 1.1 KV. as per IS : 7098 (Part-I), 1988 with latest amendments.	Mtr.	3270	112	366240.00
2.00	SH-II SITC OF POLES AND LED FIXTURES Supply of MS tubular street light pole of 1 meter length made out of 50 mm dia min B class MS pipe (3.6 mm thickness) including supply and fixing of GI flat clamp bracket of size 500mmx50mm x 5mm having provision of angle adjustment (for focusing towards perimeter boundary wall) for mounting 50W LED flood light luminaire at an angle of 70o apart horizontally as per technical specification and base plate of 200 mm x 200 mm x 12 mm thickness M.S. Sheet welded at the bottom of pole for fixing on foundation bolts complete as required for structural stability. the pole shall have provision of flood light cable termination and cable looping box fixing arrangement.The pole shall have provision of earthing bolts termination of earth electrode. Pole shall have painting with two coats of red oxide Primer and two coats of Aluminium (Silver) paint including numbering of pole with black paint on yellow circular background etc. as required, complete as per technical specifications.	Each	36	1750	63000.00

(Signature)
19/04/2021

सहायक महा प्रबंधक (अभि-विद्युत)/Asst.General Manager Engg.(E)
भारतीय विमान पत्तन प्राधिकरण, हुबबल्ली, कर्नाटक-30
AIRPORTS AUTHORITY OF INDIA
HUBLI AIRPORT, HUBLI, KARNATAKA - 580 030


Item No.	Description of Item	Unit	Qty.	Rate	Amount												
3.00	SITC of 6 mtr (5.1 mtr above ground and 0.9 mtr below the ground) swaged type MS tubular pole as mentioned below size as per IS: 2713 (part-III-1980) along with 300 mm X 300 mm X 6 mm MS base plate. <table><tr><td>DIA</td><td>THICKNESS</td><td>HEIGHT</td><td>LOCATION</td></tr><tr><td>69.3 mm</td><td>3.25 mm</td><td>(0.9+3.1 mtr)</td><td>Bottom</td></tr><tr><td>50.0mm</td><td>3.25 mm</td><td>2.00</td><td>Top</td></tr></table> The pole shall have single arm of 1.5 mtr length made up of 40 mm dia MS pipe suitable for fixing of 1x 36 w LED Street light fixture including suitable size bracket for fixing of arm on pole, providing / making 1:3:6 (1 cement : 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) cement concrete foundation 900 mm below the ground and 300 mm above the ground level , erection of pole on foundation of size 400x400x1200 mm ,along with providing and fixing 2x1.5 Mtr length 40 mm dia B class GI pipe for cable entry, having suitable bend and its fixing arrangement, including excavation and refilling etc complete as required .The pole shall have provision of cable termination and cable looping box of IP-66 categeory. Pole shall have painting with two coats of red oxide Primer and two coats of Aluminium (Silver) paint including numbering of pole with black paint on yellow circular background etc. as required, complete as per technical specifications and drawings.	DIA	THICKNESS	HEIGHT	LOCATION	69.3 mm	3.25 mm	(0.9+3.1 mtr)	Bottom	50.0mm	3.25 mm	2.00	Top	Each	142	3500	497000.00
DIA	THICKNESS	HEIGHT	LOCATION														
69.3 mm	3.25 mm	(0.9+3.1 mtr)	Bottom														
50.0mm	3.25 mm	2.00	Top														
4.00	Supply of 36W LED based roadlighting luminaire with epoxy powder coated pressure die cast Aluminium housing with weather proof gasket for LEDs & control gear compartments and having protection not less than IP 66 and having lenses specially designed for street lighting and toughened glass cover with not less than 110 lumen/watt and complete with all accessories. The luminaire should comply with the specifications mentioned in technical specifications.	Each	222	2000	444000.00												
5.00	Supply of 50W LED based Flood light fixture with epoxy powder coated pressure die cast Aluminium housing with weather proof gasket for LEDs & control gear compartments and having protection not less than IP 66 and having lenses specially designed for flood lighting and toughened glass cover with not less than 110 lumen/watt and complete with all accessories. The luminaire should comply with the specifications mentioned in technical specifications.	Each	36	3500	126000.00												


 19/04/2021
 सहायक महा प्रबंधक (अभि-विद्युत)/Asst.General Manager Enng.(E)
 भारतीय विमान पत्तन प्राधिकरण, हुबळी, कर्नाटक-580001
 AIRPORTS AUTHORITY OF INDIA
 HUBLI AIRPORT, HUBLI, KARNATAKA - 580001

Item No.	Description of Item	Unit	Qty.	Rate	Amount
6.00	Erection of steel tubular pole of length not exceeding 1.5 meters including all accessories in cement concrete 1:3:6 (1 Cement 3 Coarse sand 6 graded stone aggregate 40mm normal size) foundation of size not less than 300x300x400 mm thick including 150 mm height of foundation above ground level (level above ground may be revised to suit the site conditions especially considering the expected water level stagnation) including excavation and refilling including positioning template and foundation bolts supplied along with the pole and providing, laying and fixing of 2 x 0.80 meter long 40 mm inner dia "B" Class GI pipe having suitable bend in the foundation for loop in loop out of the cable to the pole etc as required, complete as per technical specifications and site requirements.	Job	36	2250	81000.00
7.00	Installation, Testing and Commissioning of prewired LED type flood light fitting on the existing street light tubular pole of height 1 mtr including connections with 1.5 sq.mm FRLS PVC insulated, copper conductor, three core flexible industrial cable (For phase, neutral and earth) and carriage of fitting from store to site etc. as required.	Job	36	225	8100.00
8.00	Installation, Testing and Commissioning of prewired LED type Street light fitting on the existing street light tubular pole of height 5 mtr including connections with 1.5 sq.mm FRLS PVC insulated, copper conductor, three core flexible industrial cable (For phase, neutral and earth) and carriage of fitting from store to site etc. as required.	Job	222	225	49950.00
9.00	SH-III SUPPLY & LAYING OF HDPE PIPES AND LAYING OF CABLES Excavation of the cable trenches in hard rock not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	Cum	10	312	3120.00
10.00	Supplying and laying of following size HDPE pipe of PN4, PE 63 ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required.				
10.10	40 mm dia(OD) HDPE Pipe	Mtr.	2700	67	180900.00
10.20	90 mm dia (OD) HDPE Pipe)	Mtr.	1300	262	340600.00

सहायक महा प्रबंधक (अभियंता) (सहायक प्रबंधक) Manager Enng.(E)
 भारतीय विमान पत्तन प्राधिकरण, हुबळी, कर्नाटक-30
 AIRPORTS AUTHORITY OF INDIA
 HUBLI AIRPORT, HUBLI, KARNATAKA - 580 030

Item No.	Description of Item	Unit	Qty.	Rate	Amount
11.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/HDPE pipe as required. (upto 35 sqmm)	Mtr.	2688	62	166656.00
12.00	Laying of one number PVC/XLPE insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/HDPE pipe as required. Cable size (Above 185 Sq mm and Upto 400 sq. mm)	Mtr.	1220	87	106140.00
13.00	Laying of one number PVC /XLPE insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. (Above 185 Sq mm and Upto 400 sq. mm)	Mtr.	20	62	1240.00
14.00	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5C X 300 Sqmm of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required.	Set	2	625	1250.00
15.00	Supplying and making end termination with brass single compression gland and aluminium lugs for 4C X 16 Sqmm of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required.	Set	356	60	21360.00
16	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. (for 3.5Cx300 Sq mm cable)	Set	2	1312	2624.00
17	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	Job	53	187	9911.00
18	SH-IV EARTHING Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (but with charcoal/ coke and salt) as required.	Set	18	8750	157500.00
19	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	Mtr.	108	187	20196.00


 सहायक महा प्रबंधक (अग्नि-विद्युत)/Asst. General Manager Engg.(E)
 भारतीय विमान पत्तन प्राधिकरण, हुबळी, कर्नाटक-30
 AIRPORTS AUTHORITY OF INDIA
 HUBLI AIRPORT, HUBLI, KARNATAKA - 580 030

Item No.	Description of Item	Unit	Qty.	Rate	Amount
20	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable including connection with lugs/ nut bolt etc as required.	Mtr.	3908	12	46896.00
21	SITC OF LT PANEL Design, Fabrication, Supply, Installation, Testing & Commissioning of out door Feeder Panel, cubicle type, made out of 2 mm thick CRCA sheet with 100 x 50 mm channel base frame in the bottom, totally enclosed, IP 54, free standing dust and vermin proof, compartmentalised with front lockable double doors, suitable for operation on 3 phase, 415 V, 50Hz AC system with TPN busbars and internal control wiring of minimum 2.5 sqmm copper FRLS PVC insulated wires, interconnection, duly powder coated of approved shade with angle iron stand size 50mm x 50mm x 5mm and 75cm height, i/c digging & grouting with cement concrete etc. as per specifications having following switchgears and accessories, and as approved by EIC, complete as required. the panel shall have 25% spare space. Incomers 250A, 4P 36kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection with spreader links suitable termination of 3.5Cx300 sqmm aluminium armoured cable - 2 No. RYB indication lamp, LED type - 6 Nos. (0-500)V, 3Ph voltmeter, Acc. class 1 with 90 deg defl. scale - 2 No. (0-100)A ammeter Acc. class 1 with 90 deg defl. scale - 2 Nos. 6A 3 pole voltmeter selector switch - 2No. Ammeter Selector Switch- 2 Nos ON/OFF/TRIP indication lamp, LED type - 6 Nos. Bus coupler 250A, 4P 36kA MCCB with out release - 1 Nos. 200A TPN busbar chamber with Aluminum busbar. Outgoings 200 A, 4P 36kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection -02 Nos. 40A, 4P 25kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection -04 Nos.	Mtr.	1	350000	350000.00


 सहायक महा प्रबंधक (अग्नि विभाग) Asst. General Manager Engg. (E)
 भारतीय विमानपत्तन प्राधिकरण, हुब्ली, कर्नाटक-30
 AIRPORTS AUTHORITY OF INDIA
 HUBLI AIRPORT, HUBLI, KARNATAKA - 580 030

Item No.	Description of Item	Unit	Qty.	Rate	Amount
	AC3 Rating 4P ,415V AC, power contactors alongwith 2 nos. auxiliary contact power terminals(1NO+1NC) not less than 16A capacity.- 4 nos.				
	24 Hrs analog type daily timer suitable for 230 V, 50Hz single phase AC supply.- 4 sets				
	16A, 10kA, C curve SP MCB-6 nos				
	ON/OFF/TRIP indication lamp, LED type - 3 Nos for each outgoing.				
22	Supply, Installation Testing & Commissioning of cable looping box of size 200mm x 300mm x 105 mm (LxBxH) made of Thermoplastic confirming to atleast IP 65 having provision for connection of luminaire through 3x1.5sqmm flexible cable and looping in & out of 4x16/25 sqmm 1.1 KV grade incomer and outgoing cable with suitable size of connector & seperator, groomets, glands and all accessories i/c fixing of box on existing street light pole with suitable clamps and providing 1 No. "C" series 6 A SP MCB in the box etc. complete as required.	Job	178	1500	267000.00

Total Amount (Excluding GST) Rs. 3310683.00

(Rupees Thirty Three Lakhs Ten Thousand Six Hundred and Eighty Three Only)

Note: Terms and conditions as per Work Order.

(Signature)
19/04/2021

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg – Elect.)

भा.वि.प्रा/ Airports Authority of India

हुबल्ली हवाई अड्डा/ Hubballi Airport, Hubballi

Signature Not Verified

Digitally signed by ANILDAS BEKAL
Date: 2021.06.21 14:55:35 IST
Location: eProcurement System for Central PSUs