

Ref. No. AAI/RPR/SM/ENGG (E)/CW/WO-01/2021-22/

Date: 28.05.2021

By Speed Post/E-mail

सेवा में,

मेसर्स लीशा इलेक्ट्रिकल्स,
इलेक्ट्रिकल, सिविल एण्ड एयर कंडीशनिंग,
ऑफिस / वर्क : फ्लैट नं. सी-57,
शंकराओ पाध्ये अपार्टमेंट,
वर्धा रोड, सावित्री विहार, सोमलवाड़ा,
नागपुर - 440025 (एमएच)

M/s Leesha Electricals,
Electrical, Civil & Air Conditioning
Office/Work: Falt No.C-57,
Shankarao Padhye Apartment,
Wardha Road, Savitri Vihar, Somalwada,
Nagpur - 440025 (MH)

कार्य का नाम:- एस. वी. एयरपोर्ट, रायपुर पर आरक्षित लाउंज की प्रकाश व्यवस्था में संशोधन।

Name of work:- Modification of lighting system of Reserved Lounges at S.V. Airport, Raipur.

संदर्भ/Ref:- आपकी ई-निविदा जो 07.05.2021 को खोली गई/ Your e - tender opened on 07.05.2021.

महोदय/ Sir,

1. उल्लिखित कार्य हेतु आपकी ई-निविदा के संबंध में आपके द्वारा उद्धरीत कुल रु. 6,47,000.00 (रुपये छः लाख सैंतालीस हजार मात्र) (जी. एस. टी. रहित), जो कि आंकलन लागत राशि रु. 7,41,393.00 (रुपये सात लाख इकचालीस हजार तीन सौ तिरानबे मात्र) (जी. एस. टी. रहित) से (-)12.73% कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling of Rs. 6, 47,000.00 (**Rupees Six Lakhs Forty Seven Thousand Only**) (excluding GST), which is (-) 12.73% below the estimated cost put to tender of **Rs. 7, 41,393.00 (Rupees Seven Lakhs Forty One Thousand Three Hundred Ninety Three only)** (excluding GST).

2. वरिष्ठ प्रबंधक (अभि-वि), भाविप्रा, स्वामी विवेकानंदा हवाईअड्डा, रायपुर, उपरोक्त कार्य के प्रभारी होंगे। आपसे निवेदन है कि आप वरिष्ठ प्रबंधक (अभि-वि), भाविप्रा, स्वामी विवेकानंदा हवाईअड्डा, रायपुर, के कार्यालय में दिनांक 15.06.2021 को उपस्थित रहकर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। ठेका करार का निष्पादन एक सौ रूपए मूल्य के गैर अदालती स्टैम्प पेपर पर किया जाएगा तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

SM Engg (E), AAI, Swami Vivekananda Airport, Raipur, shall be the Engineer - In-charge of the work. You are requested to attend the office of SM Engg (E) AAI, Swami Vivekananda Airport, Raipur by 15.06.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one hundred only) and the cost of the stamp paper shall be borne by you.



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

3. आपसे अनुरोध है कि आप ठेका श्रमिक (विनिमय एवं उन्मुलन) अधिनियम 1970 के उपबन्धों का अनुपालन करें। साथ ही ठेका श्रमिक (विनिमय एवं उन्मुलन) केन्द्रीय नियमावली 1971 एवं केन्द्रीय एवं राज्य सरकारों के न्यूनतम वेतन तथा उससे सम्बन्धित अन्य नियमों का पालन करें।
You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules of Central and State Governments, with its upto date amendments thereof.
 4. आपको यह भी निर्देश दिया जाता है कि आप प्रबंधक (अभि-वि), भाविप्रा, स्वामी विवेकानंदा हवाई अड्डा, रायपुर, से अविलम्ब सम्पर्क करें जो आपको कार्यस्थल सौंपेंगे।
You are also directed to contact Mgr. (Engg-E), AAI, S.V. Airport, Raipur, immediately who will arrange to hand over the site to you.
 5. कृपया यह भी नोट कर लें कि निविदा के अनुसार कार्य निष्पादन हेतु अनुगत समय 02(दो) महीने है जो कि दिनांक 15.06.2021 से माना जायेगा।
Please note that the time allowed for carrying out the work shall be 02 (Two) months and same will be reckoned from 15.06.2021.
 6. इस ठेके से संबंधित किसी भी प्रकार के पत्र व्यवहार के लिए कार्य के प्रभारी को संबंधित करेंगे।
Any further correspondence in connection with the contract should normally be addressed to the Engineer - in- charge.
 7. कृपया इस पत्र कि प्राप्ति सूचना दे तथा इसके साथ संलग्न अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
 8. कार्यआदेश के संबध में किसी प्रकार की टंकणीय त्रुटि/विसंगति होने पर अंग्रेजी संस्करण मान्य होगा।
With reference to this work order, if in case of any typographical mistake/discrepancy arise, the English version shall be applicable final.
- धन्यवाद / Thanking you,
संलग्न / Encl: Schedule

भवदीय / Yours faithfully,

वरिष्ठ प्रबंधक (अ-वि). / Senior Manager [E-E]
एएआई, स्वामी विवेकानंदा, हवाई अड्डा, रायपुर / AAI, S. V. Airport, Raipur

Airports Authority of India
S. V. Airport, Raipur
Engineering Electrical Wing

Schedule of Quantity

Name of Work : Modification of lighting system of Reserved Lounges at S.V. Airport, Raipur.


Sr. No.	Description of Item	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Supply Installation Testing and commissioning of Pendant/ Surface / recess mounted tunable white decorative light fixture with silver housing and minimum diameter 500 - 520 mm. Rated power consumption of 45 - 52W and suitable to operate with 240V, 50Hz A.C. supply having minimum 2400 Lumens system output at full intensity on 4000K CCT at CRI>80. Luminaire should be able to be controlled by a remote switch upto 15 Mtr distance. Luminaire should be tunable from minimum 2200K to 6500K CCT. Luminaire should have chrome ring within color transparent plasti part. Side ring should light up and change along with the change of light downwards. Similar to make: Philips, model no.: Semeru Pendant or equivalent.	Nos.	16.00	28350.00	453600.00
2	Supply Installation Testing and commissioning of Indoor type connective Hub, Hue Bridge and switch having 100-240 V AC/50-60HZ Outbook Volt - 5V DC 600mA, Standby Power 0.1W max Power Adapter Capacity, Frequency band 2400-2483.5 MHz and control up to 50 numbers lamps including digital dimmable tuning and competable with voice assistant Amazon Alexa, Google Assistant of all proposed range including white ambience products and it should also work under zigbee technology. Similar to make: Philips, model no.: Hue Bridge 2014-08-26 or equivalent.	Nos.	2.00	8500.00	17000.00
3	Supply Installation Testing and commissioning of Flexible LED strip with tunable white and colour changes option having IP20 rating with suitable for indoor application. Light should tune between 2200K to 6500K CCT. Also with CRI>80 in the range from 2200KBBL - 4000KBBL, >65 at 6500K BBL. Off-BBL. LED Strip should deliver minimum 800 lumens/ mtr at 4000K CCT. Beam angle: 120 degree +/-10; Wattage: 24W ; Length of each roll should be flexible available in 2Mtr and 1mtr for customized length. LED strip suitable for 50K switching cycle and also compitable for zigbee technology for wifi operation through mobile or Wifi switch. Similar to make Philips Hue strip V3 2M or equivalent.	Mtr.	36.00	3050.00	109800.00
4	Supply Installation Testing and commissioning of Deep recess pressure die cast aluminium tiltable LED COB spot light with efficacy >70 lumens/watt, SDCM<3. Beam angle of 30 degree to 40 degree for light distribution. Life class 50K burning hours @ L80B50. Power consumption of 15W with >1150 Lumens system output at 4000 K CCT with CRI>90. Supplied with Driver having operating voltage 220V-270V AC with P.F.>0.9. Cutout Diameter of 90 mm to 100mm. Similar to Make Philips Model No. RS378Z M55 D70 S-R AJ or its equivalent.	Nos.	16.00	3850.00	61600.00


28.05.21
SM (E17)

Name of Work : Modification of lighting system of Reserved Lounges at S.V. Airport, Raipur.

Sr. No.	Description of Item	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
5	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc Coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm to centre to centre, shall be fixed in a direction perpendicularity G.I intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm n centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer 's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer-in-Charge but excluding the cost of painting with: 12.5 mm thick tapered edge gypsum plain board confirming to IS: 2095-(Part 1): 2011 (Board with BIS certification marks).	Sq. Mtr.	10	500.00	5000.00
				Total (Rs.)	6,47,000.00

(Rupees in words: Six Lakhs Forty Seven Thousand only)


 28-05-21
 (Pramod Soni)

Sr. Manager(E-E)
 AAI, S. V. Airport, Raipur