



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

दिनांक / DATE22/03/2021.....

संदर्भ सं / Ref. No. AAI/BD/Engg(C)/Covered Walkway/W.O.-08/20-21/ 2172-76

सेवा में/To

M/s Chinmoyee Construction
Shubham Apartment, Flat No. GD,
Narayantala East, Baguihati,
Kolkata – 159

विषय/Sub: - Minor Capital Works at Bagdogra Airport during 2020-21. SH.: -
Construction of covered walkway along approach road at Bagdogra
Airport.

संदर्भ/Ref: - Your tender dated: - 05/03/2021.

महोदय/Dear Sir(s),

1. Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 42,10,350.00 (Rupees Forty Two Lacs Ten Thousand Three Hundred Fifty Only)** which is **40.35% below** the estimated cost put to tender of Rs. 70,58,906.25.
2. AGM (E-C), AAI, Bagdogra Airport, shall be the Engineer – in – charge of the work. You are requested to attend the office of AGM (E-C), AAI, Bagdogra Airport, Dist.: - Darjeeling, Pin: - 734421 by **01/04/2021** to sign and complete the contract agreement. The contract agreement shall be executed on a non – judicial stamp paper of value **Rs. 100 (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.
3. Please deposit **Rs. 4,21,035.00 (Rupees Four Lacs Twenty One Thousand Thirty Five Only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of clause of **1A** on page **35** of the contract document.
4. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments.
5. You are also directed to contact **Manager (E-C)**, Bagdogra Airport immediately who will arrange to hand over the site to you.

(Signature)

6. Please note that the time allowed for carrying out the work shall be **Eleven Months** and same shall be reckoned from the 10th days after issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer – in – charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance

Thanking you.

संलग्न/Enclosure: - Schedule of Rates.

भवदीय /Yours faithfully



**सहा. महा. प्रबंधक इंजी. (सिविल)/Asst. General Manager (E-C),
अध्यक्ष के लिए और उनकी तरफ से/For and on behalf of the Chairman,
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India,
बागडोगरा विमानपत्तन/Bagdogra Airport**

SCHEDULE OF QUANTITIES

Name of work :- Minor Capital Works at Bagdogra Airport during 2020-21. SH.: - Construction of covered walkway along approach road at Bagdogra Airport.

Item No.	Description	Unit	Qty.	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	cum	675.00	60.00	40500.00
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	535.00	40.00	21400.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size).	cum	17.00	3600.00	61200.00
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	cum	120.00	4800.00	576000.00
5	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	sqm	775.00	100.00	77500.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	15000.00	58.00	870000.00
7	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
	Hot finished welded type tubes.	kg	18000.00	75.00	1350000.00
8	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (± 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.				
		sqm	1790.00	625.00	1118750.00
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	sqm	1100.00	50.00	55000.00

Item No.	Description	Unit	Qty.	Rate	Amount
10	Preparation of structural design and drawings for MS covered walk-way and getting the same vetted from Jadavpur University or Sibpur university or IIT kharagpur to make "Good For Construction" drawings including submission of 02 sets of drawings, design and Technical Specifications etc., inclusive of all payment to consultants and to Jadavpur University/Sibpur university/IIT kharagpur etc. for vetting, all complete as instructed by the Engineer-in-Charge.	Job	1.00	40000.00	40000.00
Total Rs.					4210350.00

(Rupees Forty Two Lacs Ten Thousand Three Hundred Fifty Only)

 22/03/21

(S. K. Podder)

AGM (E-C)

AAI, Bagdogra Airport

Signature Not Verified

Digitally signed by SUJIT KUMAR
PODDER

Date: 2021.03.23 12:11:18 IST

Location: eProcurement System for Central
PSUs