

(पंजीकृत डाक)

संदर्भ: भा.वि.प्रा./रापु./अभि(सि)/स.म.प्र./जी.पी. हट/2021/1980-91 दिनांक:-01.07.2021

सेवा में,

To,

मेसर्स अवधेश कंस्ट्रक्शन,
220, ए.पी. कॉलोनी,
गया, बिहार-823001

M/s Awadhesh Construction,
220, A.P. Colony,
Gaya, Bihar-823001

विषय: स्वामी विवेकानन्द हवाई अड्डा, रायपुर में सी प्रकार के एयरक्राफ्ट के लिए रनवे 24 एवं एप्रन का विस्तारिकरण और अन्य संबंधित कार्य हेतु।

उपशीर्ष: ग्लाइड पाथ हट एवं संबंधित सिविल कार्य।

निविदा क्रमांक : 2021_AAI_71131_1

Sub: Extension of Runway at 24 beginning, Expansion of Apron suitable for C type of Aircraft and other associated works at Swami Vivekananda Airport Raipur.

SH : Glide Path Hut and Associated civil works.

Tender ID: - 2021_AAI_71131_1

संदर्भ: आपकी ई-निविदा जो दिनांक 13.05.2021 को खोली गयी।

Ref: Your E-tender opened on 13.05.2021

महोदय/Sir,

1. उपरोक्त कार्य के लिए आपकी मदद दर निविदा आपके द्वारा उद्धरित राशि रु. 57,90,899.00/- (रुपये सत्तावन लाख नब्बे हजार आठ सौ निन्यानबे) जो कि अनुमानित लागत रु. 81,20,000/- (जी.एस.टी. छोड़कर) से 28.68 % नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs 57,90,899.00/- (Rupees Fifty Seven Lakhs Ninety Thousand Eight Hundred Ninety Nine only) (Excluding GST) which is 28.68% Below the estimated cost put to tender of Rs. 81,20,000/- (Excluding GST).

2. आपसे अनुरोध है कि कृपया दिनांक 15.07.2021 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 15.07.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 0/- (रुपये शून्य मात्र) है। कृपया संविदा करार के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार इस कार्यादेश के जारी होने के

तिथि से 10 दिनों के भीतर जमानत जमा के रुपये 5,79,090/- (रुपये पाँच लाख उनासी हजार नब्बे मात्र) इस कार्यालय में जमा कराये अन्यथा यह निविदा दस्तावेज के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. Nil received along with your tender. Please deposit Rs. 5,79,090/- (Rupees Five Lakh Seventy Nine Thousand Ninety Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page GCC-16 of tender document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर जी.सी.सी-50 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनिमय एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही ठेका श्रमिक (विनिमय एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनिमय) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनिमय) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 तथा केन्द्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 50 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई.एस.आई. अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ई.एस.आई. पंजीकरण काम के वास्तविक समापन तक वैध रहें।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप प्रबंधक (इंजी-सि), स्वामी विवेकानंद हवाई अड्डा, रायपुर से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg. - Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 06 (छह) महीने होगा और इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 06 (Six) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

भवदीय,

संलग्न: अनुसूची-अ

(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)

भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

मूलप्रति में नही

प्रतिलिपि:

1. क्षेत्रीय कार्यापालक निदेशक, पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
2. महाप्रबंधक (अभि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
4. उपमहाप्रबंधक (अभि-सि), भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
5. सहायक महाप्रबंधक (सर्तकता), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
6. सहायक श्रम आयुक्त (सी), डी-6, आदर्श सोसाइटी, सेक्टर-1, अवंती विहार, रायपुर।
7. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक-डी, स्कीम नं.-32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.)-492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
2. उपमहाप्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
3. सहायक महाप्रबंधक (अभि-वि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
4. प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
5. कार्यालय प्रति।

(अजय सिंह भदौरिया)

सहा. महाप्रबंधक (अभि.-सि)


Schedule-A

Name of Work: Extension of Runway at 24 beginning, Expansion of Apron suitable for C type of Aircraft and other associated works at Swami Vivekananda Airport Raipur.
SH : Glide Path Hut and Associated civil works.

Sl.No	Description of Work / Item(s)	Units	No. of Qty	Rate	Amount
1	Providing and fixing of one number Prefabricated frangilble hut (deisgned as per criteria mentioned in ICAO's Aerodrome Design Manual (DOC 9157) Part-6 of size 7.0 x 3.5m and 3.00m height along the wall and 3.30 m height at the centre, made of sand witch panel of 2mm thick FRP/GRP sheet at the outer sides and middle part consists of PU Foam of density 40 kg/m ³ , which has to be installed into the operational area.The prefabricated frangilble hut shall consist of following : a) Provision of one number of partition wall with partially Glass door & locking. b) Provision of one number of main door on longer side wall with necessary locking arrangement. c) Provision of holes as per approved drawings on walls for electrical cables, split air conditioning system, communication cables, including necessary fixing arragnement for electric fittings, fixtures & NAV AIDS installation in cabin as per approved drawings. d)The exterior of the hut shall be painted with design of white and red squares (2 feet x 2 feet) as per direction of Engineer in charge. e) The cost of the hut is inclusive of design, earlier/newly vetting of design by Govt. Engineering college, of any size ,fabrication, transportation, all taxes including service tax and commisioning of hut at the proposed site as per drawing and specification over Cement Concrete Platform (Required Civil work shall be paid seperately)	Set	1.00	1350000.00	1350000.00
2	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. a) All kinds of soil	Sqm	4932.00	12.00	59184.00
3	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) All kinds of soil	Cum	31.00	78.00	2418.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	cum	395.00	3400.00	1343000.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	cum	7.00	4100.00	28700.00
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a) 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	.Cum	9.00	4500.00	40500.00
7	Centering and shuttering including strutting, propping etc. and removal of form work for : a) Foundations, footings, bases for columns.	sqm	64.00	200.00	12800.00
8	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level. A) Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	683.00	69.00	47127.00
9	Brick work with fly ash bricks (Min compressive strength 35 kg / sq cm) in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	10.00	3700.00	37000.00

A7-22/Jan
01/07/2021

10	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. a) Size of Tile 600x600 mm	sqm	25.00	800.00	20000.00
11	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	sqm	4815.00	575.00	2768625.00
12	Supplying and stacking at site. A) Moorum	Cum	218.00	305.00	66490.00
13	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	238.00	60.00	14280.00
14	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 coarse sand)	Sqm	5.00	155.00	775.00
Total					5790899.00


 01/07/2021
 A. J. Lakshmi