



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या/Ref No: AAI/RHQ/NR/ENGG(E)/RCS-LH&WS/2020-21/51

दिनांक/Date: 25.03.2021

By Speed post/ E-mail
(jccpl@ymail.com)

सेवा में,

To,

मैसर्स जेसीसी इंजीनियर्स प्राइवेट लिमिटेड,
फर्स्ट फ्लोर, रघुनाथ मार्केट,
नियर टेलीफोन एक्स्चेंज,
पठानकोट, पंजाब - 145001

M/s JCC Engineers Private Limited,
1st Floor, Raghunath Market,
Near Telephone Exchange,
Pathankot, Punjab - 145001

कार्य का नाम : उत्तर प्रदेश राज्य में आरसीएस हवाई अड्डों पर लैंडिंग टी, विंड सॉक और संबंधित विद्युत कार्यों का प्रावधान।
Name of work: Provision of Landing T, Wind Sock & allied electrical works at RCS Airports in UP State.

संदर्भ: -सीपीपी पोर्टल पर निविदा संख्या: 2021_AAI_71435_1 में आपकी वित्तीय बिड जो दिनांक 16.03.2021 को खोली गयी।

Ref:- Your Financial Bid opened on dated 16.03.2021 against Tender ID: 2021_AAI_71435_1 on CPP portal.

1. उपरोक्त उल्लेखित कार्य के लिए आपका ई-टेन्डर आपके द्वारा बताए गये मद मूल्यों पर कुल राशि रु. 50,55,000/- (रुपये पचास लाख पचपन हजार मात्र) जीएसटी रहित, जो कि न्यायोचित लागत रु 58,51,483/- से 13.61 प्रतिशत नीचे है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 50,55,000/- (Rupees Fifty Lakh Fifty Five Thousand Only)** excluding GST, which is 13.61% below the justified cost of Rs. 58,51,483/-.

2. वरिष्ठ प्रबंधक/सहायक महाप्रबंधक/उप महाप्रबंधक/संयुक्त महाप्रबंधक (अभि.-विद्युत), संबंधित एयरपोर्ट पर कार्यरत, इस कार्य के प्रभारी अभियंता होंगे, जिनका विवरण संलग्नक-1 में दिया गया है। आपसे निवेदन है आप करारनामे पर हस्ताक्षर करने के लिए दिनांक 09.04.2021 तक अधोहस्ताक्षरी के कार्यालय में उपस्थित हों तथा करारनामे को पूरा करें। ठेके का करारनामा रु 100/- (रु एक सौ मात्र) के नोन ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा जिसका खर्च आपके द्वारा उठाया जाएगा।

SM/AGM/DGM/Jt.GM (Engg.-E) of respective Airports shall be the Engineer-in-Charge of the work as per details in **Annexure-1** enclosed. You are requested to attend the office of undersigned by **09.04.2021** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of **Rs.100/-** (Rs. One Hundred only) and the cost of the stamp paper shall be borne by you.

3. इस ठेके में बयाना राशि लागू नहीं होने की वजह से आपसे कोई बयाना राशि प्राप्त नहीं हुई है। अतः ठेके के करारनामे के अनुसार सुरक्षा राशि के लिए, इस पत्र के जारी करने की तिथि से 10 दिनों के भीतर जमानत राशि रु 50,5500/- (रुपये पांच लाख पांच हजार पांच सौ मात्र) जमा कर दें, अन्यथा इतनी ही राशि जीसीसी के पृष्ठ संख्या 16 पर दिये गए क्लॉज नं 1 ए की शर्त के अनुसार काट ली जाएगी।

The earnest money amount has not been received from you as EMD is not applicable in this contract. Therefore, please deposit **Rs. 50,5500/- (Rupees Five Lakh Five Thousand Five Hundred Only)** towards security deposit within 10 days of issue of this letter, failing which, same shall be deducted as per condition of Clause no. 1A at page no. 16 of GCC.

4. आपसे निवेदन है कि आप अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियमों 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिकों (सेवा का नियमन और शर्त) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, जो कि निविदा के जीसीसी पृष्ठ संख्या 49 से 56 तक क्लॉज़ 19, 19A से 19M, 20 एवम 20A में निर्दिष्ट है तथा केंद्र और राज्य सरकार के नियमों के प्रावधानों का अनुपालन करें।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition and Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19, 19A to M, Clause 20 and 20A on page no.49 to 56 of GCC of Tender and rules of Central and State Government.

5. आपको निर्देशित किया जाता है कि तुरंत वरिष्ठ प्रबंधक/सहायक महाप्रबंधक/उप महाप्रबंधक/संयुक्त महाप्रबंधक (अभि.विद्युत), संबन्धित एयरपोर्ट पर कार्यरत प्रभारी अभियंता, से मिलें, वह आप को साइट सौंपने की व्यवस्था करेंगे।

You are directed to contact SM/AGM/DGM/Jt.GM (Engg.-E), EIC of controlling Airports immediately who will arrange to hand over the site to you.

6. कृपया नोट कर ले कि काम करने का निर्धारित समय 03 (तीन) महीना है जोकि दिनांक 05.04.2021 से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be **03 (Three) months** and same shall be reckoned from 05.04.2021.

7. ठेके के त्रुटि दायित्व अवधि 12 (बारह) महीने है, जो कि कार्य समाप्ती की वास्तविक तिथि जो कि माप पुस्तिका में दर्ज है, से गिना जाएगा।

The defect liability period shall be **12 (Twelve) months** after actual completion date as recorded in measurement book.

8. इस अनुबंध के संबंध में कोई और पत्राचार सामान्य रूप से प्रभारी अभियंता, संबन्धित एयरपोर्ट के पते पर किया जाएगा।

Any further correspondence in connection with this contract should normally be addressed to the Engineer-in-Charge of respective Airports.

9. कृपया पावती भेजें और इस पत्र की डुप्लिकेट कॉपी हस्ताक्षर करने के बाद स्वीकृति के टोकन के रूप में अधोहस्ताक्षरी को लौटाएं।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned either via email or post as a token of acceptance.

10. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall form part of contract.

नोट : हिंदी अथवा अंग्रेजी संस्करण में अंतर पाये जाने पर अंग्रेजी संस्करण मान्य होगा।

NOTE: If there any discrepancy is observed in Hindi and English version, the English version will be considered.


संलग्नक / Enclosed :-

1. Annexure – 1.
2. Schedule of Quantities (Pg. 1 to 2)

उप .महाप्रबंधक (अभि.-विद्युत), उ.क्षे. /Dy. Gen. Manager (Engg. - E), NR,
भाविप्रा, प्रचालन कार्यालय /AAI, Operational Offices,
गुरुग्राम रोड, नई दिल्ली /Gurugram Road, New Delhi-37
कृते अध्यक्ष, भाविप्रा /For and on behalf of Chairman, AAI

Annexure - 1

Sr. No.	Name of Airport / Station	Controlling Engineer-in-charge (SM / AGM / DGM / Jt.GM(Engg.-E)
1	Aligarh	Safdarjung Airport, New Delhi
2	Azamgarh	Varanasi Airport, Varanasi
3	Moradabad	Bareilly Airport, Bareilly
4	Muirpur	Varanasi Airport, Varanasi
5	Shrawasti	Ayodhya Airport, Ayodhya


25/03/2021

उप. महाप्रबंधक (अभि.-विद्युत), उ.क्ष. /Dy Gen. Manager (Engg. - E), NR,
भाविप्रा, प्रचालन कार्यालय /AAI, Operational Offices,
गुरुग्राम रोड, नई दिल्ली-37 /Gurugram Road, New Delhi-37

Schedule of Quantity

Name of Work : Provision of Landing T, Wind Sock & allied electrical works at RCS Airports in UP State.

S. No.	Description of Item	Unit	Qty.	Rate (Ex. GST)	Amount
1	Supply, Installation, Testing & Commissioning of Landing 'H' direction indicator complying with ICAO & CAR standards consisting of three rectangular Aluminium limbs having length of 4000 mm each supported with 50mm dia Aluminium pipe of 1350mm length & frangible coupling with flanges, 9/10 watt LED lamp fixtures with glass dome(minimum IP 65) and lamps for each limb, each circuits to operate on 230 V, 50 Hz AC supply, providing control unit with suitable control transformer, Relay, Contactor, copper wiring upto Junction Box etc. as required for remote operation of landing 'T' from CCR Hall as well as from control tower, connections/ interconnections, civil foundations for each legs along with MS anchor base plate, casting pedestal up to 1mtr outside all around the landing 'H' with 1:2:4 cement concrete of 100mm thick and neat finish top etc. complete as required at following station: Aligarh / Azamgarh / Moradabad / Muirpur / Shrawasti Airport	Each	5	180000	900000
2	Supply, Installation, Testing & Commissioning of frangible & externally illuminated Wind Direction Indicator conforming to ICAO & CAR standards and suitable for operation on 230 V, 50 Hz single phase supply and consist of following as required at the given stations: (a) 4.5 mtr high FRP frangible pole/mast of red/white colour. The frangibility shall conforming to ICAO Annex 14 & Aerodrome design manual part-VI/FAA guidelines. (b) Wind sock cone should have a length of not less than 3.60 m and diameter, at larger end, of not less than 0.90 m as per technical specifications. (c) Illuminating indicator with Four nos. 20 watt LED lamps with lamps mounting arrangement for outdoor conditions. (d) One no. LED aviation obstruction light having aluminium cast body and red polycarbonate dome, internal wiring, provision for remote control operation. (e) Providing and laying 1:2:4 Cement Concrete foundation for installation of WDI and casting pedestal all around upto 7.5 m radius with 100mm thick 1:2:4 cement concrete & neat finish top surface as per OEM recommendations & as per direction of EIC for the following stations: Aligarh / Azamgarh / Moradabad / Muirpur / Shrawasti Airport	Each	5	200000	1000000
3	SITC of portable type Digital Electronic weighing scale of 200 Kgs capacity with double display and having 600mm X 600mm MS Platform, load cells, Digital Indications, division of 20gms minimum alongwith platform base structures and other accessories etc. suitable to operate on 230V, 50Hz AC power supply or battery of 6V, 4.5 Ah for Check in counters including calibration & stamping by state authority, complete as required at following station: Aligarh / Azamgarh / Moradabad / Shrawasti Airport	Each	8	10000	80000
4	Supply of 4 core x 16 sq.mm. XLPE insulated, PVC inner sheathed, armoured aluminium cable, 1100 V as per IS 7098 (Part 1) 1988 with upto date amendments complete, as required.	Mtr	8400	150.00	1260000



S. No.	Description of Item	Unit	Qty.	Rate (Ex. GST)	Amount
5	Supplying and laying of PN 6, 63 mm outer dia HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 4984:2016, complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	Mtr	300	250.00	75000
6	Supplying and laying of 100 mm dia GI pipe, Class 'B' for crossing of roads & pathways i/c cutting, jointing with coupler etc. as required direct in ground including excavation and refilling the trench and making good the same, complete as required.	Mtr	200	790.00	158000
7	Laying of one number PVC insulated and PVC sheathed / XLPE, 1.1 KV grade aluminium armoured upto 35 sq.mm power cable in the existing HDPE/MS /Hume pipe as required.	Mtr	500	20.00	10000
8	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of Upto 35 sq. mm (clamped with 1mm thick saddle) on wall surface as required.	Mtr	200	50.00	10000
9	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size upto 35 sq.mm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	Mtr	7700	200.00	1540000
10	Supplying and making end termination with brass compression gland and aluminium lugs for 4x16 sqmm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	Set	20	500.00	10000
11	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 4 x 16 sq.mm. size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	Set	12	1000.00	12000

Total (exc. GST) 5055000.00

Say (Rs.) 5055000.00

(Rs. Fifty Lakh Fifty Five Thousand Only)


25/03/2021

उप. महाप्रबंधक (अभि.-विद्युत), उ.क्षे. /Dy Gen. Manager (Engg. - E), NR,
भाविप्रा, प्रचालन कार्यालय /AAI, Operational Offices
गुरुग्राम रोड, नई दिल्ली-37 /Gurugram Road, New Delhi-37