

Government eProcurement System Created By: A.V Rama Krishna Created Date/Time: 01-Apr-2021 02:02 PM Tender Title: Consultancy services for Survey and Volume calculations for grading of Operational area Tender ID: 2021_AAI_73355_1
--

Tender Inviting Authority: Asst. General Manager Engg(civil)-I, Begumpet airport Hyderabad

Name of Work: Consultancy services for Survey and Volume calculations for grading of Operational area.

Contract No: 2021_AAI_73355_1

SCHEDULE OF WORK / ITEM(S)					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	N K Engine 07AAXPY1

					Rate
1.00	Providing Contour map by conducting Topographical survey inside the operational area including taking reduced levels at 5M x 5M intervals and preparation of contour map. The levels shall also be submitted on excel spread sheet and in any other form as decided by the Engineer in Charge. The Counter map is prepared to carry out the wall to wall grading inside the operational area. The quoted rate shall include the following. 1. Carrying out site survey and taking reduced levels at 5M x 5M grid. 2. Marking of the existing structure, payment, drains & converts, roads & buildings, electricals and CNS installations, etc in the contour map. 3. Finalizations of the best profile for the wall to wall grading of the operational area as per the ICAO regulations wherever applicable and sound Engineering practices in keeping with the ground profile and prevailing drainage system. 4. Study of the existing drainage system including suggestion of improvement and agumentation plan for the smooth drainage system in operational area duly considering hydrological data. 5. Submission of 4 sets of contour map in scale (1:5000) with marking structures (3 hard copies and 1 soft copy) Note: The survey work shall be carried out inside operational area in restricted working hours. All men and vehicles shall be permitted to enter the operational area only on possession of security passes. Existing level of runway, taxiways, main Apron and remote apron will be provided by AAI and the same needs to be incorporated in contour map. Payment will be restricted to the area of operational area excluding above said pavements.	540.00	Acre		1125.00
2.00	Preparation ad submission of quantity calculating of earth work in Excavation/ Excavation of Ordinary rock & Hard rock and filling needed to achieve proper wall to wall grading of required slope and gradient of operational area based on the data obtained from Topographical survey & contour map and as per the above finalized profile including submission of 6 sets of contour maps and quantity calculation sheets in hard copys and also in soft copy.	440.00	Acre		190.00

Total in Figures

Lowest Amount Quoted BY: VEERAAIAH ASSOCIATES(279600.00)

ers(GSTN-124A1ZN)	IDAX CONSULTING AND RESEARCH PVT. LTD.(GSTN-		TECHNOLAND ENGINEERS AND SURVEYORS(GSTN-		Growever Infra Private Limited(GSTN-07AAGCG8710.117G)		U.C.CONSULTANCY(GST N-NA)	
Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
607500.00	850.00	459000.00	600.00	324000.00	1260.00	680400.00	966.52	521920.80

