

Government eProcurement System
Created By: PRASAD RAMJEE
Created Date/Time: 14-May-2021 11:36 AM
Tender Title: Construction of perimeter road around operational wall at Visakhapatnam Airport
Tender ID: 2021_AAI_75896_1

Tender Inviting Authority: <Asst General manager Engg(C) - I>

Name of Work: "Construction of perimeter road around operational wall at Visakhapatnam Airport"

Contract No: AAI/VZ/Engg (C) / Perimeter road/21-22

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate	ARP ENTERPRISES(GSTN-37ABKFAB6849Q1ZV)		RECHI CONSTRUCTION PVT LTD(GSTN-19AAGCB6641K1Z30)		ARUDHI PROJECTS(GSTN-37ABKFA7284C1Z81)		JAYRAM INDUSTRIES INDIA PRIVATE LIMITED(GSTN-19AAGCB6641K1Z30)		Ruchira Associates(GSTN-37AAQFR2340N1ZC)		M/s.JG Construction(GSTN-NA)		D.SRINIVAS(GSTN-NA)		VADAY CONSTRUCTION PRIVATE LIMITED(GSTN-NA)	
					Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver/finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	240.00	Cum	100.00	1800.00	432000.00	2000.00	480000.00	2250.00	540000.00	1850.00	444000.00	2550.00	612000.00	2200.00	528000.00	2425.00	582000.00	1700.00	408000.00
2.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	240.00	Cum	100.00	1600.00	384000.00	2000.00	480000.00	2000.00	480000.00	1500.00	360000.00	1970.00	472800.00	1700.00	408000.00	2600.00	624000.00	1700.00	408000.00
3.00	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator, vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. The panel shuttering work shall be paid for separately. (Note:- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/ recoverable separately).	320.00	Cum	100.00	6000.00	1920000.00	5900.00	1888000.00	6875.00	2200000.00	6200.00	1984000.00	5900.00	1888000.00	5200.00	1664000.00	7800.00	2496000.00	6200.00	1984000.00
4.00	Providing and laying non-pressure NP2 class (light duty) R C C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :450 mm dia. R.C.C. pipe	50.00	Mtr	100.00	2000.00	100000.00	1400.00	70000.00	1875.00	93750.00	800.00	30000.00	2000.00	100000.00	3140.00	157000.00	2500.00	125000.00	950.00	47500.00
5.00	Supplying and filling moorum with Plasticity Index not more than 6 and liquid limit not more than 25 obtained from approved quarry / embankment or depressions in layers not exceeding 20cm (loose) in depth (or any thickness as approved by the Engineer- in - Charge in case vibratory roller is used) including breaking clods, watering, consolidating each layer with power road roller 8-10 tonners weight or vibratory roller of adequate capacity under optimum moisture content condition to give density not less than 98 % of the maximum modified standard proctor density complete including leveling fine dressing to the required grade. Camber and slope completed as per specifications and as directed by the Engineer-In-Charge with all leads and lifts (The item includes cost of work, payment if necessary royalty, carriage of moorum up to work site for all leads and lifts involved from all sources acquired or arranged by the Contractor. Payment to be made for compacted quantity only).	1200.00	Cum	100.00	688.96	826752.00	538.00	645600.00	687.00	824400.00	1100.00	1320000.00	700.00	840000.00	405.00	486000.00	800.00	960000.00	425.00	510000.00

L1 Amount	L1 Vendor
408000.00	VADAY CONSTRUCTION PRIVATE LIMITED
360000.00	JAYRAM INDUSTRIES INDIA PRIVATE LIMITED
1664000.00	M/s.JG Construction
30000.00	JAYRAM INDUSTRIES INDIA PRIVATE LIMITED
486000.00	M/s.JG Construction

Total in Figures

3662752.00

3563600.00

4138150.00

4138000.00

3912800.00

3243000.00

4787000.00

3357600.00

Lowest Amount Quoted BY: M/s.JG Construction(3243000.00)

BOQ Summary Details
Tender Title: Construction of perimeter road around operational wall at Visakhapatnam Airport
Tender ID: 2021_AAI_75896_1

Sheet Name	Sl.No	Bidder Name	Amount		Bid Rank
BoQ1	1	M/s. IG Construction	3243000.00	L1	
	2	VADAY CONSTRUCTION PRIVATE LIMITED	3357500.00	L2	
	3	RECHI CONSTRUCTION PVT LTD	3563600.00	L3	
	4	ARP ENTERPRISES	3662752.00	L4	
	5	Ruchira Associates	3912800.00	L5	
	6	JAYRAM INDUSTRIES INDIA PRIVATE LIMITED	4138000.00	L6	
	7	ARUDHI PROJECTS	4138150.00	L7	
	8	D.SRINIVAS	4787000.00	L8	