



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
देहरादून हवाई अड्डा, देहरादून।
Dehradun Airport, Dehradun

स्पीड पोस्ट

सं. संख्या :: भाविप्रा/डीडीएन/अभि-सि/ग्रेड सुधार /2021 / 998

दिनांक: 06.09.2021

सेवा में,

मेसर्स एचआर कंस्ट्रक्शन प्राइवेट लिमिटेड

फ्लैट नंबर 803, ए ब्लॉक सरस्वती अपार्टमेंट,

गोमती नगर एक्सटेंशन सेक्टर-4,

लखनऊ - 226010.

विषय: देहरादून हवाई अड्डे पर मौजूदा रनवे के लिए ग्रेड सुधार।

Subject: Grade Correction for existing runway at Dehradun Airport

सन्दर्भ : विषय कार्य की Tender ID-2021_AAI_76958_1 के अनुरूप में आपकी ई.-निविदा सं. 279254 |

Ref: Your bid No. 279254 corresponding to Tender ID-2021_AAI_76958_1 for subject work.

प्रिय महोदय

Dear sir,

- 1) आपके द्वारा उपरोक्त कार्य की ₹ 5,43,75,250.00 (GST के बिना) (रु पांच करोड़ तैंतालीस लाख पचहत्तर हजार दो सौ पचास मात्र) की मद दर ई-निविदा जो कि उक्त कार्य की अनुमानित लागत ₹ 6,09,60,000.00 (GST के बिना) से 10.80% कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your e- tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling Rs. 5,43,75,250.00 (excluding GST) (Rupees Five crore Forty Three Lakhs Seventy Five Thousand Two Hundred and Fifty Only) which is 10.80% below the estimated cost put to tender of Rs. 6,09,60,000.00 Only (excluding GST).

- 2) उप महाप्रबंधक इंजी (सिविल), भाविप्रा, देहरादून हवाईअड्डा, देहरादून कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि इस पत्र के जारी होने की तारीख से 15 दिनों के भीतर उप महाप्रबंधक इंजी (सिविल), भाविप्रा, देहरादून हवाईअड्डा, देहरादून के कार्यालय में उपस्थित होकर ठेका संविदा को हस्ताक्षरित कर पूर्ण करें। ठेका ₹ 100 / (रूपये एक सौ मात्र) के गैर-न्यायिक मोहर पत्र पर सम्पादित किया जाएगा एवं मुद्रांक पत्र की कीमत आपके द्वारा वहन की जाएगी।

DGM (Engg.Civil), AAI, Dehradun Airport, Dehradun shall be the Engineer-in charge of the work. You are requested to attend the office of DGM (Engg.Civil), AAI, Dehradun Airport, Dehradun within 15 days from the date of issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-Judicial stamp paper of value Rs. 100/- (Rs One hundred only) and the cost of the stamp paper shall be borne by you.

06/09/21
इंजी. जसबीर सिंह / Er. Jasbir Singh
उप महाप्रबंधक (इंजी. - सिविल)
Dy. GEN. MANAGER (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण / AAI
देहरादून एयरपोर्ट, देहरादून
DEHRADUN AIRPORT, DEHRADUN

- 3) निविदा के साथ प्राप्त अग्रिम धरोहर राशि **रु निल** को ठेका संविदा की धारा 1A के अनुसार धरोहर राशि का हिस्सा मानकर उसमें बदल दिया जावेगा। तत्पश्चात सुरक्षा जमा राशि की कटौती प्रत्येक चल लेखा बिल से संविदा शर्तों के अनुसार की जाएगी ।

The Earnest money amount of **Rs. NIL** received along with your tender will be treated and converted as part of Security deposit as per condition of clause no 1A of contract document. Thereafter Security Deposit shall be recovered from each running bill as per condition of contract.

- 4) आपसे अनुरोध है कि इस पत्र के जारी होने की तारीख से 30 दिनों के भीतर अनुबंधों में उल्लिखित अन्य जमाओं के अलावा, निविदा राशि के 3% (तीन प्रतिशत) की अपरिवर्तनीय प्रदर्शन गारंटी अर्थात् **रु 16,31,258.00 (सोलह लाख इकतीस हजार दो सौ अट्ठावन रुपये मात्र)** अनुबंध समझौते के उचित प्रदर्शन के लिए, किसी राष्ट्रीयकृत बैंक या किसी अनुसूचित बैंक से लेकिन किसी सहकारी या ग्रामीण बैंक से नहीं, निविदा दस्तावेज के पृष्ठ संख्या 15 पर खंड 1 (ii), पृष्ठ संख्या 137 पर परिशिष्ट 3 और पृष्ठ संख्या 131 पर अनुसूची "ई" के अनुसार प्रस्तुत करें।

You are requested to submit an irrevocable performance guarantee of 3% (Three Percent) of the tender amount i.e. **Rs. 16,31,258.00- (Rupees Sixteen lakhs Thirty One Thousand Two Hundred and Fifty Eight Only)** in addition to other deposits mentioned in the contracts towards proper performance of the contract agreement from a Nationalized Bank or any Scheduled Bank but not from any Co-operative or Gramin Bank within 30 days from the date of issue of this letter as per clause 1 (ii) on page no. 15, Addendum 3 on page no. 137 of tender document and Schedule "E" on P.g no. 131 of the general rules and conditions of the contract agreement.

- 5) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) 1970 श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम, ई0एस0आई0 अधिनियम-1948, ई0पी0एफ0 अधिनियम-1952 तथा इस संबंध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।

You are requested to comply with provision of contract Labour (Regulation Abolition) Act 1970 and contract Labour (Regulation and Abolition) Central rules 1971, minimum wages, ESI act-1948, EPF Act-1952 and other rules there of Central and State Government.


- 6) आपको निर्देशित किया जाता है कि तुरन्त प्रभाव से सहायक महाप्रबंधक (इंजी-सि), भाविप्रा, देहरादून हवाईअड्डा, को संपर्क करें जो कि आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asstt. General Manager (Engg- Civil) AAI, Dehradun Airport, immediately, who will arrange to hand over the site to you.

- 7) कृपया ध्यान रहे कि कार्य करने का निर्धारित समय 06 माह है जो कि इस पत्र के जारी होने की तिथि के दसवें दिन से गिना जाएगा।

Please note that time allowed for carrying out the work shall be **06 Month** and same shall be reckoned from the 10th day of the date of issue of this letter.

- 8) संविदा के संदर्भ में सामान्यतः कोई भी पत्राचार कार्य प्रभारी अभियन्ता को सम्बोधित करते हुए किया जाना चाहिए। Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.



इंजी. जसबीर सिंह / Er. Jasbir Singh
उप महाप्रबंधक (इंजी.-सिविल)
Dy. GEN. MANAGER (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण / AAI
देहरादून एयरपोर्ट, देहरादून
DEHRADUN AIRPORT, DEHRADUN

- 9) कृपया प्राप्ति की पावती भेजें एवं पत्र कि अनुलिपि (जो कि संलग्न है) को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

नोट:- हिंदी तथा अंग्रेजी संस्करण में अंतर पाए जाने पर अंग्रेजी संस्करण मान्य होगा।

Note :- If any discrepancy is observed in Hindi and English version, then English version will be followed.



(जसबीर सिंह)

(Jasbir Singh),

उप महाप्रबन्धक (इंजी-सि),

DGM (E-C),

भाविप्रा, देहरादून हवाईअड्डा

AAI, Dehradun Airport

वास्ते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For & on behalf of the Chairman,


Airports Authority of India

संलग्नक: अनुसूची-अ

Encl: Schdule-A


SCHEDULE A**NAME OF WORK: Grade correction for existing runway work at Dehradun Airport.**

Item No.	Item Description	Qty.	Unit	Rate	Amount
1)	CIVIL WORK & ELECTRICAL ITEMS				
1	Providing and laying of Hot Mix Dense Asphaltic Concrete(DAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade VG-30 Bitumen (supplied in Bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8 to 10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade (VG-30) content shall be taken as 135 kg/m ³ of mix supplied in Bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material]	450.00	Cum	9900.00	4455000.00
2	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete(SDAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade VG-30 Bitumen (supplied in Bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade (VG-30) content shall be taken as 120 kg/m ³ of mix supplied in Bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material]	700.00	Cum	9200.00	6440000.00
3	Providing and laying of Hot Mix Dense Bituminous Macadam(DBM) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade VG-30 Bitumen (supplied in Bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8 to 10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade (VG-30) shall be taken as 110 kg/m ³ of mix supplied in Bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material]	4800.00	Cum	8100.00	38880000.00
4	Providing and applying tack coat using hot straight run bitumen of Viscosity grade VG-30 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications: On bituminous @ 0.5Kg/sqm.	72500.00	Sqm	30.00	2175000.00
5	White washing with lime to give an even shade : New work (three or more coats)	18750.00	Sqm	20.00	375000.00
6	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of oil dirt, scales, oil, grease and other foreign material etc. and lining out complete. New work (Two or more coats)	4000.00	Sqm	125.00	500000.00
7	Supply of C.I. isolating transformer housing box ,water tight round type , metal container of outside size 330 mm height 450 mm made of 10 mm thick cast iron moulding all round ,except the top surface , which is 15 mm thick ,cast iron moulding suitable to receive a light fitting base plate on the top and underground housing associated with transformer power cable and having a clear hole center at one side surface centre 75 mm above bottom surface suitable to receive one no of 50 mm dia "B" CLASS G.I.pipe including check nuts as required.The box should have two SS earth bolts and 4 nuts with washers of M10 X 30 MM tapped inside near the hole (4" away from the hole centre) and having a drain hole at the bottom suitably tapped to receive 15 mm dia "B" class G.I. pipe and having clear opening of 220 mm at the top surface and 6 nos M10 tapped hole at the hole centre 260 mm to receive fitting base plate and bolts as required as per AAI drawing & specifications.	97.00	Each	5000.00	485000.00
8	Supply of elevated type Runway edge light fitting suitable for following complete with bottom box and all accessories i/c halogen lamp, lens / filter / prism etc. as required and as per specifications.				0.00
	a) bi -directional edge light fitting	26.00	Each	9000.00	234000.00
	b) Uni directional STOP BAR light with lamp	12.00	Each	11000.00	132000.00


 Page 1
 इंजी. जसबीर सिंह / Er. Jasbir Singh
 उप महाप्रबंधक (इंजी. - सिविल)
 Dy. GEN. MANAGER (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण /AAI
 देहरादून एयरपोर्ट, देहरादून
 DEHRADUN AIRPORT, DEHRADUN

Schedule A

9	Supply of elevated type high intensity uni-directional simple approach light fittings complete with lens holder, lens, clamping mechanism, prefocus lamp holder, halogen lamp central column assembly, breakable coupling, gaskets, two pin secondary lead base plate with 6 nos. of stainless steel bolts, spring & plain washers & other accessories with lens, filters etc. complete in all respect and confirming to specifications.	10.00	Each	7000.00	70000.00
10	Supply of breakable coupling for approach light fittings complete as required.	17.00	Each	550.00	9350.00
11	Installation of transformer housing box with a base concrete of 1:3:6 of size 630 x 630 x 100 mm thick all round concrete of 1:2:4 1, 150 mm thick, the top sloped with 1:2:4 cement concrete including providing and fixing 250 mm long 15 mm dia "B" class G.I. pipe with check nuts for drainage of water including excavation of side shoulder and refilling (Wherever the transformers boxes are not in a line the same has to be aligned in such a way that the centre fall in a straight line) etc complete as required.	97.00	Each	1500.00	145500.00
12	Dismantling of existing SAPL light fittings complete units from the existing location and re-installation of the same, testing & Commissioning including making connections with the existing isolating transformer etc. (this work required be carried out during Changes in RWY Profile of runway 08). (A set of 17 SAPL fittings)	17.00	Each	3000.00	51000.00
13	Dismantling of existing RUNWAY EDGE /TURNING PAD/STOP BAR units from the existing location and re-installation of the same, testing & Commissioning including making connections with the existing isolating transformer etc. (this work required be carried out during Changes in RWY Profile). (RUNWAY EDGE /TURNING PAD fittings)	80.00	Each	1000.00	80000.00
14	Supply of 5KV grade plug & receptacle of type-1 class B connector & suitable field attachment . 5KV grade PVC insulated PVC sheathed single core standard copper conductor cable confirming to IS:1554 (Part-1) etc. as reqd.				
	a) 16 Sqmm	70.00	Set	1000.00	70000.00
	b) 6 Sqmm	18.00	Set	800.00	14400.00
15	Providing / laying and fixing of following size "B" class G.I. pipe with threading and alignment of pipe with transformer housing box , providing check nuts etc as required.				
	a) 50 mm	150.00	Meter	1000.00	150000.00
16	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed copper conductor airfield lightning cable of exceeding 1.1 KV grade but not exceeding 11 KV grade as required. :-				
	a) Single core 16 sq. mm.	10.00	Set	1500.00	15000.00
	b) Single core 6 sq. mm.	5.00	Set	800.00	4000.00
17	Supply of two pin secondary plug assembly for approach light fitting (Length 3.50 mtr) complete as required.	20.00	Each	4500.00	90000.00
Total in Figures					54375250.00
Quoted Rate in words		Rupees Five Crore Forty Three lacs Seventy Five Thousand Two Hundred Fifty Only			


 06/9/24
 इंजी. जसबीर सिंह / Er. Jasbir Singh
 उप महाप्रबंधक (इंजी. - सिविल)
 Dy. GEN. MANAGER (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण /AAI
 देहरादून एयरपोर्ट, देहरादून
 DEHRADUN AIRPORT, DEHRADUN