



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

No. AAM/ENGG (E)/AMED-IX/UPS/2021-22/ **A-12**

Date: 24.08.2021

To

M/s. Lakshmi Electrical Enterprises
No. 1C, CLC Works Road,
New Colony, Chromepet,
Chennai – 600 044.

Sub: SITC of UPS and allied Electrical Works in Ceremony Lounge at Chennai International Airport.

Ref: Tender ID: 2021_AAI_80543_1

Tender Ref. No. AAM/ENGG (E)/AMED-IX/UPS/2021-22/1


Dear Sir (s),

1. Your E-tender for the above mentioned work is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 4,48,305.00 (Rupees Four Lakhs Forty Eight Thousand Three Hundred and Five Only) which is 15.15% below the Justified Cost of Rs. 5,28,356.00 (Rupees Five Lakhs Twenty Eight Thousand Three Hundred and Fifty Six Only) which is inclusive of all the taxes, duties, levies and octroi etc., Except GST which will be paid extra as applicable.
2. Joint General Manager (Engg-Elect)-II, AMED, Operational Office, Airports Authority of India, Chennai Airport, Chennai – 600027 shall be the Engineer-In-Charge of the work. You are requested to attend to the Office of Joint General Manager (Engg-Elect)-II, AMED AAI, Chennai Airport by 07.09.2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
3. Please deposit the amount of Rs. 44,831.00 (Rupees Forty Four Thousand Eight Hundred and Thirty One Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per Clause 1A of General Conditions of Contract.
4. You are also directed to contact the Joint General Manager (Engg-Elect)-II, Airport Maintenance Electrical Division, Operational Office, Airports Authority of India, Chennai Airport or his Authorized representative immediately for the execution of the above work.

Contd... 2

फैक्स: 044 - 2256 0008 ई पी ए बी एक्स: 2256 0551, चेन्नई हवाई अड्डे, चेन्नई – 600 016.

Fax: 044 - 2256 0008 EPABX: 2256 0551, Chennai Airport, Chennai – 600 016.



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

-2-

5. You are requested to comply with the provision of Contract Labour Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act and Rules thereof Central and State Governments.
6. Please note that the time allowed for carrying out the work shall be 2 (Two) Months which shall be reckoned from **01.09.2021**.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule of Quantity (Page no. 1 of 3).

W. Xavier
24/8/21

(W. Francis Xavier)
Joint General Manager (Engg - Elect)-II,
For and on behalf of the Chairman,
Airports Authority of India.

AIRPORTS AUTHORITY OF INDIA
CHENNAI AIRPORT, CHENNAI 600 016.
SCHEDULE OF QUANTITY

Name of Work: SITC of UPS and allied Electrical Works at Ceremonial Lounge in Chennai International Airport.

Sl.No	Description of Items	Quantity	Unit	Rate/ Unit (Excluding GST)	Amount (Excluding GST)
SH: I	SITC of Ups and Allied Electrical Works				
1	SITC of 10KVA, 3Ph-3Ph IGBT based double conversion online UPS system with 12V 65Ah - 20 Nos SMF batteries for backup and with battery rack, etc compatible with DG Set & confirming to tender technical Specification. UPS OEM must have authorised service center at chennai.	1	set	352,000.00	352,000.00
2	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted,inclusive of 100 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.) (TPN 4 (8+12) Way MCB DB double door)	1	Nos	6,700.00	6,700.00
3	Supplying of following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, complete with tinned copper bus bar,neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) (SPN 8 Way MCB DB double door)	3	Nos	1,400.00	4,200.00

4	Supplying and fixing following rating, 415 volts, MCB, C curve, 10KA in the existing MCB DB complete with connections, testing and commissioning etc., as required				
4.01	20A FP MCB	1	Nos	1,100.00	1,100.00
4.02	16A TP MCB	5	Nos	840.00	4,200.00
5	Supplying and fixing of 5 amps to 32 amps rating, 240/415 volts, "C" curve, 10KA miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	30	Nos	130.00	3,900.00
6	Supplying and fixing of 5 amps to 32 amps rating, 240/415 volts, "C" curve, 10KA miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole	3	Nos	460.00	1,380.00
7	Supply of Copper Conductor, XLPE insulated, PVC sheathed, armoured power cable of 1.1 KV grade of following Sizes conforming to IS 7098 (Part-1) as amended upto date as required. 4core 4 sqmm	185	Mtr	235.00	43,475.00
8	Supply and Installation of 63A 4P ON Load Change Over switch operating on 3-PHASE, 415volt, 50HZ, with enclosure etc. as required.	1	set	4500.00	4,500.00
9	Laying of 4 core 4 sqmm Copper armoured cable over existing false ceiling in ceremony lounge with ceiling supports where ever possible; Including cutting of the false ceiling for entry and exit of the cable; carrying false ceiling work for the cut portion and any other portion damaged during laying of the cable, including applying putty and colour for the damaged false ceiling.	185	Mtr	50.00	9,250.00

10	Laying of 4 core 4 sqmm Copper armoured cable in suitable dia 2mm thick PVC pipe and concealing the pipe in wall; including chipping the wall, plastering, applying putty and painting it matching with existing wall colour.	25	Mtr	260.00	6,500.00
11	Installation of SPN double door 8way DB by concealing it(flush mounting) in wall;including chipping the wall, plastering, applying putty and painting it matching with existing wall colour.	3	Job	200.00	600.00
12	Removing the existing light point wiring from the existing DB and terminating the same in the newly installed SPN DB's adjacent to the existing DB'S. Routing of all the wires shall be through 2mm thick PVC PIPE of suitable dia concealed in wall;including chipping the wall, plastering, applying putty and painting it matching with existing wall colour.	3	Job	2500.00	7,500.00
13	Supplying and making end termination with brass compression gland and aluminium lugs for 4x4 sqmm of PVC insulated and PVC sheathed / XLPE Copper conductor cable of 1.1 KV grade as required.	10	Nos	300.00	3,000.00
Total Excluding GST				448,305.00	

(Rupees Four Lakhs Forty Eight Thousand Three Hundred and Five Only)

6/8/2020
Jt. GM (E-E)-II

AAI, Chennai Airport.