

भाविप्रा/कोल्हापुर/संयुक्त.म.प्र.(अभि-सि)/डब्ल्यू-03/2021-22/ 367
AAI/Kolhapur/Jt.GM (Engg-C)/W-03/2021-22/ 367

दिनांक: 07/12/2021
Date: 07/12/2021

सेवा मे,
मेसर्स सुरेश कन्स्ट्रक्शन कंपनी,
11, बाबागंज, प्रतापगढ़,
प्रतापगढ़,
उत्तर प्रदेश - 230001

To,
M/s. Suresh Construction Company,
11, Babaganj, Pratapgarh
Pratapgarh,
Uttar Pradesh - 230001

कार्य का नाम : कोल्हापुर हवाई अड्डे पर बैलेंस ऑपरेशनल बाउंडरी वाल, फायर पिट, कूलिंग पिट,
ओवरहैड टैंक तथा अंडरग्राउंड स्टैटिक टैंक का निर्माण कार्य।

Name of Work: Construction of Balance Operational Boundary wall, fire pit, cooling pit,
overhead tank & underground static tank at Kolhapur Airport.

संदर्भ:- दिनांक 08/10/2021 को खोला गया आपका ई-टेंडर (वित्तीय लिफाफा)
Ref: Your e -tender (Financial bid) opened on 08/10/2021

महोदय/Sir,

1. उपरोक्त कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दर पर कुल रु. 6,49,93,005/- (रु. छः करोड़ उन्नचास लाख तिरानबे हजार पाँच, मात्र) (GST के बगैर) पर स्वीकृत की जाती है जो की निविदा मे रखी गयी अनुमानित लागत रु. 9,86,06,000/- (रु. नौ करोड़ छियास्सी लाख छः हजार, मात्र) से 34.09 % नीचे है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 6,49,93,005/- (Rs. Six Crores Forty-Nine Lakhs Ninety-Three Thousand and Five, only) (Excluding GST) which is 34.09% below the estimated cost put to tender of Rs. 9,86,06,000/- (Rs. Nine Crores Eighty-Six Lakhs Six Thousand, only)

2. संयुक्त महाप्रबंधक (इंजी-सिविल), भारतीय विमानपत्तन प्राधिकरण, कोल्हापुर विमानक्षेत्र, कोल्हापुर कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 12/12/2021 तक संयुक्त महाप्रबंधक (इंजी-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र के कार्यालय मे उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु. 300/- (रु. तीन सौ मात्र) के गैर न्यायिक स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Joint General Manager (Engg- Civil), Airports Authority of India, Kolhapur Airport, Kolhapur shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Jt. General Manager (Engg- Civil), AAI, Kolhapur Airport by 12/12/2021 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

3. इस निविदा के साथ कोई भी अग्रिम धन राशि नहीं मांगी गयी थी जिसके एवज़ मे अग्रिम धन राशि का घोषणा पत्र मांगा गया था। कृपया, प्रतिभूति निक्षेप राशि रु. 32,49,651/- (रु. बत्तीस लाख उन्नचास हजार छः सौ इकावन) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त 1A पृष्ठ क्रमांक GCC-16 के अनुसार की जाएगी।

The earnest money deposit was not applicable for this tender instead of that declaration of earnest money deposit was sought. Please deposit Rs. 32,49,651/- (Rupees Thirty-Two Lakh Forty-Nine Thousand Six Hundred Fifty-One, only), towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted the same will be deducted as per condition of GCC Clause no. 1A at page 16 of GCC of tender document.

4. कार्यादेश जारी होने के 30 दिन के भीतर, आप भा.वि.प्रा. को रु. 19,49,790/- (रु. उन्नीस लाख उन्नचास हजार सात सौ नब्बे, मात्र) की बैंक गारंटी जो आपके कार्य के निविदा खंड की शर्त 1(i) के अनुसार निष्पादन गारंटी होगी, प्रस्तुत करेंगे। बैंक गारंटी निविदा कागजात के GCC के पृष्ठ क्र. 108 तथा 110 मे दिये गए प्रारूप के अनुसार होनी चाहिए।


07/12/2021

Within 30 days of issue of work order, you shall submit to AAI, a Performance Guarantee as per condition of Clause 1(i) on page no. GCC 15 for an amount of **Rs. 19,49,790.00/- (Rs. Nineteen Lakh Forty-Nine Thousand Seven Hundred Ninety, only)** in the form of Bank Guarantee on the proforma appended at page no. GCC-108 & 110 of tender document.

5. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 के प्रावधान का पालन करे जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971, Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

6. आपको निर्देश दिया जाता है कि आप तुरंत **वरिष्ठ प्रबंधक (इंजी-सिविल)**, भाविप्रा, कोल्हापुर विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **12 (बारह) महीना** है जोकि इस पत्र के जारी करने के 10 वे दिन से गिना जायेगा।

You are also directed to contact **Senior Manager (Engg-Civil)**, AAI, Kolhapur Airport immediately who will arrange to hand over site to you. Please note that, the time allowed for carrying out the work is **12 (Twelve) Months** which shall be reckoned from 10th day of issue of this letter.

7. इस ठेके के संबंध में आगे की कोई भी पत्राचार **संयुक्त महाप्रबंधक (इंजी-सिविल)**, भाविप्रा, कोल्हापुर विमानक्षेत्र,, कोल्हापुर 416004 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the **Joint General Manager (Engg-Civil)**, AAI, Kolhapur Airport, Kolhapur -416004.

8. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall from part of contract.

9. उपरोक्त कार्य के लिए त्रुटि दायित्व की अवधि 12 (बारह) महीने होगी।

The defects liability period for the above-mentioned work is 12 (Twelve) months.

10. यदि ठेकेदार को किसी भी सुरक्षा नियम का उल्लंघन करते हुए पाया जाता है, तो वह ब्लैक लिस्टेड हो जाएगा और अन्य कानूनी कार्यवाही के लिए जिम्मेदार होगा।

If Contractor is found violate any of Security Regulations, he shall be Black listed and will be responsible subjected to other Legal Proceedings.


11. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

12. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।

In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully



07/12/2021.

संयुक्त महाप्रबंधक (अभि-सिविल),

भाविप्रा, कोल्हापुर हवाईअड्डा, कोल्हापुर

कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

Joint General Manager (Engg.-Civil),

AAI, Kolhapur Airport, Kolhapur

For & on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Assistant General Manager (E-C), AAI, Kolhapur Airport.

Name of Work: Construction of Balance Operational Boundary wall, fire pit, cooling pit, overhead tank & under ground static tank at Kolhapur Airport.

Contract No: 2021_AAI_81807_1

Name of the Bidder/ Bidding Firm / Company :	M/s Suresh Construction Co
--	----------------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Schedule of Quantity					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	2538.00	Cum	70.00	177660.00	INR One Lakh Seventy Seven Thousand Six Hundred & Sixty Only
2.01	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	2024.00	Cum	120.00	242880.00	INR Two Lakh Forty Two Thousand Eight Hundred & Eighty Only

7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3.01	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Hard rock (blasting prohibited)	3574.00	Cum	800.00	2859200.00	INR Twenty Eight Lakh Fifty Nine Thousand Two Hundred Only
4.01	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	6303.00	Cum	20.00	126060.00	INR One Lakh Twenty Six Thousand & Sixty Only
5.01	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. Ordinary or hard rock	458.00	Cum	30.00	13740.00	INR Thirteen Thousand Seven Hundred & Forty Only
6.01	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	137.00	Cum	4700.00	643900.00	INR Six Lakh Forty Three Thousand Nine Hundred Only
7.01	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	590.00	Cum	3600.00	2124000.00	INR Twenty One Lakh Twenty Four Thousand Only
8.01	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	4599.00	Sqm	165.00	758835.00	INR Seven Lakh Fifty Eight Thousand Eight Hundred & Thirty Five Only
9.01	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	312.00	Sqm	170.00	53040.00	INR Fifty Three Thousand & Forty Only

7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
10.01	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	117.00	Sqm	200.00	23400.00	INR Twenty Three Thousand Four Hundred Only
11.01	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Strut	7663.00	Sqm	160.00	1226080.00	INR Twelve Lakh Twenty Six Thousand & Eighty Only
12.01	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	5397.00	Sqm	160.00	863520.00	INR Eight Lakh Sixty Three Thousand Five Hundred & Twenty Only
13.01	Centering and shuttering including strutting, propping etc. and removal of form for Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like.	2018.00	Sqm	160.00	322880.00	INR Three Lakh Twenty Two Thousand Eight Hundred & Eighty Only
14.01	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm wide	68.00	Meter	200.00	13600.00	INR Thirteen Thousand Six Hundred Only
15.01	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars-Fe 500D	142158.00	Kg	67.00	9524586.00	INR Ninety Five Lakh Twenty Four Thousand Five Hundred & Eighty Six Only
16.01	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars -Fe 500D	33652.00	Kg	67.50	2271510.00	INR Twenty Two Lakh Seventy One Thousand Five Hundred & Ten Only


 7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
17.01	Providing and laying in position machine batched and machine mixed design mix M 25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note:- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately). a) All works upto plinth level	1905.00	Cum	4600.00	8763000.00	INR Eighty Seven Lakh Sixty Three Thousand Only
18.01	Providing and laying in position machine batched and machine mixed design mix M 25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note:- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately). a) All works above plinth level upto floor V	478.00	Cum	4700.00	2246600.00	INR Twenty Two Lakh Forty Six Thousand Six Hundred Only
19.01	Extra for providing richer mixes at all floor levels. Note:- Excess/less cement over the specified cement content used is payable /recoverable separately. Providing M-30 grade concrete instead of M-25 grade BMC/RMC. (Note:- Cement content considered in M-30 is @ 340 kg/cum)	132.00	Cum	50.00	6600.00	INR Six Thousand Six Hundred Only

7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
20.01	Add for using extra cement in the items of design mix over and above the specified cement content therein.	40.00	Tonne	6000.00	240000.00	INR Two Lakh Forty Thousand Only
21.01	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in foundation and plinth in : Cement Mortar 1:6 (1 cement : 6 coarse sand).	2601.00	Cum	3850.00	10013850.00	INR One Crore Thirteen Thousand Eight Hundred & Fifty Only
22.01	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 above plinth upto floor V level in : Cement Mortar 1:6 (1 cement : 6 coarse sand).	1533.00	Cum	4000.00	6132000.00	INR Sixty One Lakh Thirty Two Thousand Only
23.01	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	45.00	Cum	3000.00	135000.00	INR One Lakh Thirty Five Thousand Only
24.01	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	18462.00	Kg	75.00	1384650.00	INR Thirteen Lakh Eighty Four Thousand Six Hundred & Fifty Only
25.01	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	4755.00	Kg	74.00	351870.00	INR Three Lakh Fifty One Thousand Eight Hundred & Seventy Only

901
7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
26.01	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	30.00	Sqm	700.00	21000.00	INR Twenty One Thousand Only
27.01	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	13560.00	Sqm	220.00	2983200.00	INR Twenty Nine Lakh Eighty Three Thousand Two Hundred Only
28.01	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	13540.00	Sqm	235.00	3181900.00	INR Thirty One Lakh Eighty One Thousand Nine Hundred Only
29.01	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand)	51.00	Sqm	235.00	11985.00	INR Eleven Thousand Nine Hundred & Eighty Five Only
30.01	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	8428.00	Sqm	295.00	2486260.00	INR Twenty Four Lakh Eighty Six Thousand Two Hundred & Sixty Only

SAS
7/12/21


NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
31.01	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	116.00	Sqm	225.00	26100.00	INR Twenty Six Thousand One Hundred Only
32.01	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	41.00	Sqm	60.00	2460.00	INR Two Thousand Four Hundred & Sixty Only
33.01	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	34919.00	Sqm	80.00	2793520.00	INR Twenty Seven Lakh Ninety Three Thousand Five Hundred & Twenty Only
34.01	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	906.00	Sqm	80.00	72480.00	INR Seventy Two Thousand Four Hundred & Eighty Only
35.01	Lettering with Synthetic enamel paint of approved brand and manufacture	36750.00	Per Letter per cm height	1.00	36750.00	INR Thirty Six Thousand Seven Hundred & Fifty Only
36.01	Supplying and laying at site. 53 mm to 22.4 mm size stone aggregate.	27.00	Cum	1100.00.	29700.00	INR Twenty Nine Thousand Seven Hundred Only

S
ydr
7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
37.01	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/sqmm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	6305.00	Meter	240.00	1513200.00	INR Fifteen Lakh Thirteen Thousand Two Hundred Only
38.01	Pointing/ Embossing AAI logo with cement mortar 1:3 (1 cement: 3 fine sand) Projecting out by 12mm raised on cement plastered wall as per drawing and directions of Engineer-in-Charge.	105.00	Each	225.00	23625.00	INR Twenty Three Thousand Six Hundred & Twenty Five Only
39.01	Dismantling expanded metal or I.R.C. fabrics or GI chain link fencing with necessary battens, beading & flats including stacking the serviceable material within 50 metres lead.	7680.00	Sqm	100.00	768000.00	INR Seven Lakh Sixty Eight Thousand Only
40.01	Dismantling and stacking within 50 metres lead, fencing posts or struts including all earth work and dismantling of concrete etc. in base of: T' or 'L' iron or pipe	1068.00	Each	80.00	85440.00	INR Eighty Five Thousand Four Hundred & Forty Only
41.01	Refixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	6252.00	Sqm	140.00	875280.00	INR Eight Lakh Seventy Five Thousand Two Hundred & Eighty Only

7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
42.01	Deduct for taking away of steel work in frames, shutters, trusses, channels, beams, Tee, angles, bolts, washers, GI Fencing, etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (Note:- This is a credit item and amount will be deducted from the bill.)	40498.00	Kg	22.00	-890956.00	INR Minus Eight Lakh Ninety Thousand Nine Hundred & Fifty Six Only
43.01	Supplying and filling in plinth with machined sand under floors, including watering, ramming, consolidating and dressing complete.	78.00	Cum	2500.00	195000.00	INR One Lakh Ninety Five Thousand Only
44.01	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	4.00	per bag of 50 kg cement used in the mix	1000.00	4000.00	INR Four Thousand Only
45.01	Providing and Placing in position suitable PVC water stops conforming to IS:12200 for construction/ expansion joints between two RCC members and fixed to the reinforcement with binding wire before pouring concrete etc. complete : Serrated with central bulb (225 mm wide, 8-11 mm thick)	75.00	Meter	325.00	24375.00	INR Twenty Four Thousand Three Hundred & Seventy Five Only
46.01	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	156.00	Per 50 kg cement	800.00	124800.00	INR One Lakh Twenty Four Thousand Eight Hundred Only



7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
47.01	Providing and mixing integral crystalline admixture for water proofing treatment to RCC structures like basement raft, retaining walls, reservoir, sewage & water treatment plant, tunnels / subway and bridge deck etc. at the time of transporting of concrete into the drum of the ready-mix truck, using integral crystalline admixture @ 0.80% (minimum) to the weight of cement content per cubic meter of concrete) or higher as recommended by the manufacturer's specification in reinforced cement concrete at site of work. The material shall meet the requirements as specified in ACI-212-3R-2010 i.e. by reducing permeability of concrete by more than 90%, compared with control concrete as per DIN 1048 and resistant to 16 bar hydrostatic pressure. The crystalline admixture shall be capable of self-healing of cracks up to a width of 0.50mm. The work shall be carried out all complete as per specification and the direction of the Engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage.	385.00	Kg	120.00	46200.00	INR Forty Six Thousand Two Hundred Only
48.01	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 50 mm dia nominal bore	50.00	Meter	425.00	21250.00	INR Twenty One Thousand Two Hundred & Fifty Only
49.01	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 50 mm dia nominal bore	15.00	Meter	475.00	7125.00	INR Seven Thousand One Hundred & Twenty Five Only
50.01	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 50 mm nominal bore	2.00	Each	900.00	1800.00	INR One Thousand Eight Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
51.01	Providing and fixing gun metal non- return valve of approved quality (screwed end) : 50 mm nominal bore Horizontal	1.00	Each	1000.00	1000.00	INR One Thousand Only
52.01	Providing and filling sand of grading zone V or coarser grade, allround the G.I. pipes in external work : 50 mm diameter pipe	50.00	Meter	20.00	1000.00	INR One Thousand Only
53.01	Providing orange colour safety foot rest of minimum 6 mm thick plastic encapsulated as per IS : 10910, on 12 mm dia steel bar conforming to IS: 1786, having minimum cross section as 23 mmx25 mm and over all minimum length 263 mm and width as 165 mm with minimum 112 mm space between protruded legs having 2 mm tread on top surface by ribbing or chequering besides necessary and adequate anchoring projections on tail length on 138 mm as per standard drawing and suitable to with stand the bend test and chemical resistance test as per specifications and having manufacture's permanent identification mark to be visible even after fixing, including fixing in manholes with 30x20x15 cm cement concrete block 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) complete as per design.	29.00	Each	600.00	17400.00	INR Seventeen Thousand Four Hundred Only
54.01	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality L D- 2.5 Rectangular shape 600x450 mm internal dimensions	2.00	Each	1800.00	3600.00	INR Three Thousand Six Hundred Only

7/12/21

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
55.01	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 50 mm nominal bore	2.00	Each	300.00	600.00	INR Six Hundred Only
56.01	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 80 mm dia nominal bore	6.00	Meter	600.00	3600.00	INR Three Thousand Six Hundred Only
57.01	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 80 mm nominal bore	1.00	Each	650.00	650.00	INR Six Hundred & Fifty Only
58.01	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 80 mm nominal bore	1.00	Each	2200.00	2200.00	INR Two Thousand Two Hundred Only
Total in Figures					64993005.00	INR Six Crore Forty Nine Lakh Ninety Three Thousand & Five Only
Quoted Rate in Words		INR Six Crore Forty Nine Lakh Ninety Three Thousand & Five Only				


 7/12/21