



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

No. AAI/CL/AGM/ENGG[C]/COMPOUND WALL/2021-22/155

DATE: 19/01/2022

To

M/s Garg Associates
B-34, Mohan Garden, Pipal Wali
Road, Uttam Nagar,
New Delhi-110059

By Hand/Regd. Post with A/D
/By Speed Post/By E-mail

Name of work : Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II

Ref : 1) E-Tender ID No: 2021_AAI_84573

2) Your e-tender dated: 21/12/2021 (Financial Bid)

Dear Sir (S),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rate quoted by you totaling to **₹2,61,20,250.00 [Excluding GST]** (Rupees Two Crore Sixty One Lakhs Twenty Thousand Two Hundred and Fifty Only) as per the Bill of Quantities attached, which is 25% below the estimated cost put to tender of ₹348.27 Lakhs
2. Dy. Gen. Manager (Engg-Civil)/Jt. Gen. Manager (Engg-Civil), Engineering Wing, AAI, Calicut Intl. Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Dy. Gen. Manager (Engg-Civil)/Jt. Gen. Manager (Engg-Civil), Engineering Wing, AAI, Calicut Intl. Airport by **02/02/2022** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value ₹200.00 (Rupees Two Hundred only) and the cost of the stamp paper shall be borne by you.
3. Please deposit **₹26,12,025.00** (Rupees Twenty Six Lakhs Twelve Thousand and Twenty Five Only) towards Security Deposit within 10 days from the date of issue of this letter; failing which, the same will be deducted from your running bill as per the Clause 1A of Clauses of Contract on page 16 of the tender document.
4. You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of Services) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no 49-50 of GCC of tender and rules thereof Central and State Governments.
5. You are also directed to contact Manger-(Engg-Civil), AAI, Calicut Intl. Airport immediately who will arrange to hand over the site to you.

Bombardier
19/01/2022
General Manager (Engg-Civil)
AAI, Calicut International Airport

(Contd... on page 2)

कालीकट अंतर्राष्ट्रीय हवाईअड्डा
Calicut International Airport

कालीकट हवाईअड्डा (डॉ. ए)
Calicut Airport (P.O.)

केरल-673647
Kerala-673647

दूरभाष/Phone : 0483-2711 325
फैक्स/Fax : 0483-2711 406




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

6. Please note that the time allowed for carrying out the work shall be **7 [Seven] months [including 2 (Two) month(s) considered for rain]** and same shall be reckoned from the 15th day after issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance

Yours faithfully,

Encl: BOQ (8 pages)


19/09/2022
Asst. Gen. Manager (Engg-C)
Engineering Wing,
AAI, Calicut Intl. Airport
For and on behalf of the Chairman



Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/ Bidding Firm / Company :	Garg Associates							
<u>PRICE SCHEDULE</u> (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
1	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. 3km Earth		1000.00	cum		150.00	150000.00	INR One Lakh Fifty Thousand Only
2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge; All kinds of soil		160.00	sqm		40.00	6400.00	INR Six Thousand Four Hundred Only
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. All kinds of soil		2500.00	cum		150.00	375000.00	INR Three Lakh Seventy Five Thousand Only
4	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. Ordinary rock		2500.00	cum		325.00	812500.00	INR Eight Lakh Twelve Thousand Five Hundred Only
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.		280.00	cum		200.00	56000.00	INR Fifty Six Thousand Only
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.		1860.00	cum		100.00	186000.00	INR One Lakh Eighty Six Thousand Only
7	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 60 cm girth up to and including 120 cm girth		20.00	each		1150.00	23000.00	INR Twenty Three Thousand Only


 19/08/2023
 Asst. General Manager (Engg-Civil)
 सहायक महा प्रबन्धक (इंजी-सिविल)
 ए.ए.आर. कालिकट अंतर्राष्ट्रीय विमानतट
 Calicut International Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/ Bidding Firm / Company :	Garg Associates							
PRICE SCHEDULE (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
8	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 120 cm girth up to and including 240 cm girth		10.00	each		2300.00	23000.00	INR Twenty Three Thousand Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)		400.00	cum		5000.00	2000000.00	INR Twenty Lakh Only
10	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).		100.00	cum		6191.00	619100.00	INR Six Lakh Nineteen Thousand One Hundred Only
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).		700.00	cum		6100.00	4270000.00	INR Forty Two Lakh Seventy Thousand Only
12	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).		100.00	cum		6300.00	630000.00	INR Six Lakh Thirty Thousand Only
13	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete		910.00	sqm		300.00	273000.00	INR Two Lakh Seventy Three Thousand Only
14	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.		80.00	sqm		300.00	24000.00	INR Twenty Four Thousand Only
15	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Suspended floors, roofs, landings, balconies and access platform		30.00	sqm		400.00	12000.00	INR Twelve Thousand Only

Bombadiah
19/04/2022
Asst. General Manager (Engg-Civil)
AAI, Calicut International Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/
Bidding Firm
/ Company :

Garg Associates

PRICE SCHEDULE

(This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
16	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Lintels, beams, plinth beams, girders, bressumers and cantilevers		980.00	sqm		400.00	392000.00	INR Three Lakh Ninety Two Thousand Only
17	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Columns, Pillars, Piers, Abutments, Posts and Struts		1320.00	sqm		400.00	528000.00	INR Five Lakh Twenty Eight Thousand Only
18	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like		200.00	sqm		450.00	90000.00	INR Ninety Thousand Only
19	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Edges of slabs and breaks in floors and walls Above 20 cm wide		10.00	sqm		500.00	5000.00	INR Five Thousand Only
20	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.		43700.00	kg		82.00	3583400.00	INR Thirty Five Lakh Eighty Three Thousand Four Hundred Only
21	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.		8400.00	kg		84.00	705600.00	INR Seven Lakh Five Thousand Six Hundred Only
22	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.		900.00	kg		95.00	85500.00	INR Eighty Five Thousand Five Hundred Only

Bombardier
 07/01/2022
 Asst. General Manager (Engg-Civil)
 AAI, Calicut International Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/

Bidding Firm

/ Company :

PRICE SCHEDULE

(This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
23	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works		3000.00	kg		100.00	300000.00	INR Three Lakh Only
24	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)		6530.00	sqm		300.00	1959000.00	INR Nineteen Lakh Fifty Nine Thousand Only
25	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)		390.00	sqm		300.00	117000.00	INR One Lakh Seventeen Thousand Only
26	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm)		13380.00	sqm		100.00	1338000.00	INR Thirteen Lakh Thirty Eight Thousand Only
27	Lettering with black Japan/Synthetic enamel paint paint of approved brand and manufacture		42500.00	per letter per cm height		3.00	127500.00	INR One Lakh Twenty Seven Thousand Five Hundred Only
28	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)		40.00	cum		750.00	30000.00	INR Thirty Thousand Only
29	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)		10.00	cum		750.00	7500.00	INR Seven Thousand Five Hundred Only
30	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in - charge.		5.00	cum		1500.00	7500.00	INR Seven Thousand Five Hundred Only
31	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.		4900.00	kg		7.00	34300.00	INR Thirty Four Thousand Three Hundred Only

Bombardier
 19/01/2022
 Asst. General Manager (Engg-Civil)
 भा.वि.प्र.क. अंतर्राष्ट्रीय विमानतट
 AAI, Calicut International Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/
Bidding Firm
/ Company :

Garg Associates

PRICE SCHEDULE

(This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
32	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead upto a lead of 10 km, including all lifts involved.		360.00	cum		150.00	54000.00	INR Fifty Four Thousand Only
33	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 no's rounds per 6 metre length, up to 5 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)		300.00	m		425.00	127500.00	INR One Lakh Twenty Seven Thousand Five Hundred Only
34	Removing and stacking the existing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), up to 5m height of wall, along with 9 horizontal R.B.T. reinforced barbed wire, including unfastening of G.I. staples and G.I. clips, bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge. The item should be stacked properly in bundles so as to enable reuse of the same after construction of the compound wall in that area.		1300.00	m		60.00	78000.00	INR Seventy Eight Thousand Only
35	Dismantling laterite masonry work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. : In cement mortar		690.00	cum		500.00	345000.00	INR Three Lakh Forty Five Thousand Only
36	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material (rubble/ stone) within the operational area in location/s at any lead and/ or lift, as directed by the Engineer-in-charge; and disposal of Moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved stacking location for all leads including all lifts involved as per directions of Engineer-in-charge In cement mortar		470.00	cum		400.00	188000.00	INR One Lakh Eighty Eight Thousand Only

Bom Badias
 19/04/2023
 बॉम्बे ब्याडियास
 सहायक महा प्रबन्धक (इंजी-सिविल)
 Asst. General Manager (Engg-Civil)
 भा.वि.प्र., कलिकट अंतर्राष्ट्रीय विमानचतन
 A.A.I., Calicut International Airport

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/ Bidding Firm / Company :	Garg Associates							
PRICE SCHEDULE (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
37	Laterite Stone Masonry Work in foundation and plinth by laying in position dressed laterite stone supplied by department in laterite stone masonry with cement mortar 1:6 (1 cement :6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer-in-charge. Note: All work up to 1.20m above plinth beam will be measured under this item.		660.00	cum		3000.00	1980000.00	INR Nineteen Lakh Eighty Thousand Only
38	Laterite Stone Masonry Work above plinth level up to floor V level by laying in position dressed laterite stone supplied by department in laterite stone masonry with cement mortar 1:6 (1 cement :6 coarse sand) including dressing of sides etc. complete as per the direction of Engineer-in-charge.		270.00	cum		3200.00	864000.00	INR Eight Lakh Sixty Four Thousand Only
39	Providing & fixing weep holes/ air holes in all kinds of masonry work at all levels using 110 mm (4") PVC pipe (4kgft) of approved quality as per the directions of Engineer-in-charge		720.00	m		350.00	252000.00	INR Two Lakh Fifty Two Thousand Only
40	Fixing available concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 no's rounds per 6 metre length, up to 5 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)		1300.00	m		125.00	162500.00	INR One Lakh Sixty Two Thousand Five Hundred Only
41	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. Laterite blocks for a lead of 1 km		39800.00	each		5.50	218900.00	INR Two Lakh Eighteen Thousand Nine Hundred Only
42	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. Laterite blocks for a lead of 2 km		15700.00	each		6.50	102050.00	INR One Lakh Two Thousand & Fifty Only


 19/01/2022
 Asst. General Manager (Engg-Civil)
 न.वि.प्र. कलिकट अंतराष्ट्रीय विमानतळ
 AAI, Calicut International Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/ Bidding Firm / Company :	Garg Associates							
PRICE SCHEDULE (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT In Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
43	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. Laterite blocks for a lead of 3 km		15700.00	each		7.50	117750.00	INR One Lakh Seventeen Thousand Seven Hundred & Fifty Only
44	Carriage of materials by mechanical transport including loading, unloading, stacking etc. Complete as per the direction of Engineer-in-charge. Laterite blocks for a lead of 4 km		15700.00	each		8.50	133450.00	INR One Lakh Thirty Three Thousand Four Hundred & Fifty Only
45	Providing and fixing temporary sheet fencing, repeating the procedure till the material becomes unserviceable, with ISA 65 x 65 x 6mm as vertical members, ISA 50 x 50 x 6mm as horizontal members, connected with nut and bolt arrangement. Vertical members to be fixed at 3m centre to centre and embedded in concrete block of size 60 x 60 x 60 cm. 0.4mm thick colour coated sheet to be fixed with J hook to the horizontal member to form sheet fencing. The temporary fencing should be provided at locations where compound wall is broken for reconstruction as per the security standards and for prevention of animal entry. Once the work is completed, the sheet fencing should be dismantled, taken out and re-fixed at new locations. After completion of the whole work, the material will be returned to the agency. The rate shall include materials for the work, excavation of pit for embedding concrete block for fencing post, concreting, loading, unloading, transportation to new location, erection and repetition of process etc. complete as per the direction of Engineer-in-Charge		3900.00	Sqm		420.00	1638000.00	INR Sixteen Lakh Thirty Eight Thousand Only
46	Providing and operating the hydraulic excavator cum back hoe loader on pneumatic tyre like J.C.B 2DX max or equivalent for cutting, levelling etc. in the operational area including transportation to and from the site of operation, fuel and driver charges and other incidental expenses on this account etc. as directed by the Engineer-in-Charge. (The payment will be based on the number of hours worked at the site for items that are not quantified otherwise.)		200.00	hours		1400.00	280000.00	INR Two Lakh Eighty Thousand Only
47	Dry laterite stone pitching with laterite stone blocks issued by department free of cost at various stacked locations in the operational area and preparing surface etc. complete.		1880.00	sqm		300.00	564000.00	INR Five Lakh Sixty Four Thousand Only

Bombabla
 19/07/2023
 Asst. General Manager (Engg-Civil)
 भा.वि.प्र., कलिकट अंतर्राष्ट्रीय विमानचरन
 AAI, Calicut International Airport

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: <Asst. Gen. Manager [Engg-C], O/o HOD [Civil], Engineering Wing, AAI, Calicut Intl. Airport-673647>

Name of Work: <Reconstruction of weaker sections of security compound wall and associated works at Calicut International Airport- Phase II>

Contract No: <2021_AAI_84573>

Name of the Bidder/ Bidding Firm / Company :		Garg Associates						
<u>PRICE SCHEDULE</u> (This SOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P Excluding GST	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
48	Random rubble masonry with available hard stone, issued by department free of cost at various stacked locations in operational area in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement: 6 coarse sand). The hard stone boulders made available need to be broken to required size using mechanical breaker/ jack hammer, loaded, transported by mechanical transport, and unloaded at the work site to cover any lead and lift etc as directed by EIC. The rate is inclusive of all items mentioned above and nothing extra shall be paid in this regard.		204.75	cum		800.00	163800.00	INR One Lakh Sixty Three Thousand Eight Hundred Only
49	Random rubble masonry with available hard stone, issued by department free of cost at various stacked locations in operational area, in superstructure above plinth level and up to floor five level including leveling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) above plinth level with Cement mortar 1:6 (1 cement: 6 coarse sand). The hard stone boulders made available need to be broken to required size using mechanical breaker/ jack hammer, loaded, transported by mechanical transport, and unloaded at the work site to cover any lead and lift etc as directed by EIC. The rate is inclusive of all items mentioned above and nothing extra shall be paid in this regard.		60.00	cum		850.00	51000.00	INR Fifty One Thousand Only
50	Dismantling G.I. pipes manually/ by mechanical means including stacking of pipes at the designated stacking locations/stores, for any/all lead and lift as per direction of Engineer-in-charge : Above 40 mm nominal bore		300.00	m		100.00	30000.00	INR Thirty Thousand Only
Total in Figures							26120250.00	INR Two Crore Sixty One Lakh Twenty Thousand Two Hundred & Fifty Only
Quoted Rate in Words		INR Two Crore Sixty One Lakh Twenty Thousand Two Hundred & Fifty Only						


 19/01/2022
 Asst. General Manager (Engg-Civil)
 न.वि.प्र., कलिकट अंतर्राष्ट्रीय विमानतट
 A.A.I., Calicut International Airport