



भारतीय विमानपत्तन प्राधिकरण
पश्चिमी क्षेत्र मुख्यालय
AIRPORTS AUTHORITY OF INDIA
WESTERN REGION, HQRS.

संदर्भ सं.: भाविप्रा/प.क्षे./स.म.प्र (इंजी-विद्युत)/भुज/सीडब्लू-01/2021-22/ 663
Ref. No: AAI/WR/AGM(E-E)/BHUUJ/CW-01/2021-22/

दिनांक: 17.11.2021
Date: 17.11.2021

सेवा में/ To,

मेसर्स रुद्राक्ष इंटरप्राइज/ M/s. Rudraksha Enterprise,

शाप संख्या 6 / Shop No. 6,

रामेश्वर कोम्प्लेक्स, साधू वशवाणी रोड / Rameshwar Complex, Sadhu Vasvani Road,

राजकोट 360 005/ Rajkot-360 005.

विषय/ Sub: भुज हवाई अड्डे पर फीडर पिलर का एसआईटीसी और दोषपूर्ण केबलों को बदलना ।
SITC of Feeder Pillar and Replacement of faulty cables at Bhuj Airport.

संदर्भ: आपकी ई-निविदा नं. 2021_AAI_89672_1 दिनांक 08.11.2021 को खोला गया ।

Your e-tender id. 2021_AAI_89672_1 opened on Dated 08.11.2021.

महोदय,/ Dear Sir(s),

- उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है, आपके द्वारा बताए गये मद मूल्यों पर आपकी ई-निविदा राशि कुल रु. 5,32,230.00 (रुपए पाँच लाख बत्तीस हजार दो सौ तीस मात्र) + जीएसटी है, जो कि ई-निविदा की उचित लागत राशि रु. 6,63,311/- से 19.76 % नीचे है। एजन्सी द्वारा वैध टैक्स इन्वाइस प्रस्तुत करने पर जीएसटी अदा किया जाएगा। गुजरात राज्य के लिए जीएसटी क्र. GSTIN:-24AAACA6412D1ZE है।
Your e-tender for the work mentioned above is hereby accepted on behalf of The Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 5,32,230 (Rupees Five Lakh Thirty Two Thousand Two Hundred Thirty only) + GST** which is **19.76 % Below** the Justified cost of Rs. **6,63,311/-**. GST will be paid against valid Tax invoice from the agency. For Gujarat state AAI GST no. is GSTIN:24AAACA6412D1ZE
- सहा.महाप्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, विलेपार्ले (पूर्व), मुंबई-400099, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आपकी ओर से एक विश्वसनीय प्रतिनिधी प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 26.11.2021 तक सहा.महाप्रबंधक (इंजी-विद्युत), भाविप्रा, परिचालन कार्यालय भवन, न्यू एअरपोर्ट कालोनी, विलेपार्ले (पूर्व), मुंबई-400099 के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करें। ठेके का करारनामा रु. 100/- के नॉनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।

Asstt.GM (ENGG. - ELECT.), RHQ (WR), Vile Parle (E), Mumbai - 400 099 shall be the Engineer-In-Charge of this work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office to the Asstt.GM (ENGG- ELECT.), RHQ (WR), Operational office building, New Airport Colony, Vile Parle (E), Mumbai-400 099 by 26.11.2021 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/-** and the cost of the stamp paper shall be borne by you.

P.T.O



3. कृपया **रु.53,223.00(रुपये तिरपन हजार दो सौ तेईस मात्र)** प्रतिभूति जमा के रूप में यह पत्र जारी करने के तारीख के 10 दिन के अंदर जमा किजिये। जमा करने की असफलता में वह राशि बिल से ठेके की शर्तों के अनुसार काट दी जायेगी।
Please deposit **Rs.53,223.00 (Rupees Fifty Three Thousand Two Hundred Twenty Three only)** towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your bill as per contract conditions.
4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम (नियम तथा उन्मुलन) 1971 के केन्द्रीय नियम श्रम नियम (नियमन तथा उन्मुलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।
You are requested to comply with provision of contract labour (Regulation and Abolition Act 1970 and contract labour Regulation & Abolition) Central rule 1971 and minimum wages Act & rules thereof central and safe Govt.
5. आपको यह निर्देश दिया जाता है कि आप प्रबंधक(इंजी-विद्युत), भुज हवाईअड्डा से संपर्क करें जो आपको साइट सौपने की व्यवस्था करेंगे।
You are directed to contact Mgr. (E-E), Bhuj Airport immediately who will arrange to handover the site.
6. कृपया आप से अनुरोध है की दिनांक **26.11.2021** से काम शुरू करें। कृपया ध्यान दें की काम को पूरा करने के लिए दिनांक **25.02.2022** तक का समय दिया गया है।
You are requested to start the work from **26.11.2021**. Please note that time allowed for completion of the work is up to **25.02.2022**
7. इस ठेके के संबंध में आगे का कोईभी पत्राचार सहा.महाप्रबंधक (इंजी-विद्युत), भाविप्रा, प.क्षे., क्षेत्रीय मुख्यालय, एकीकृत प्रचालन कार्यालय भवन, विलेपार्ले (पुर्व), मुंबई-400099 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to Asstt.GM(E-E), RHQ (WR), Integrated Operational office building, Vile Parle (E), Mumbai - 400099.
8. कृपया पावती भेजें तथा इस आदेश की दोहरी प्रति आपके हस्ताक्षर के पश्चात इस कार्यालय में भेजें जो कि स्वीकृती टोकन समझा जाएगा।
Please acknowledge the receipt and return the duplicate copy of this order enclosed herewith after signing to the undersigned as a token of acceptance.
9. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जायेगा।
If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.
धन्यवाद/ Thanking You,

Encl: 1. SOQ

भवदीय / Yours faithfully,
मो. सदरुल हुदा
17/11/2021
(मो. सदरुल हुदा)/(Md. Sadrul Huda)
सहा.महाप्रबंधक (इंजी-विद्युत),
Asstt.GM (Engg.-Elect.)

कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,
For and on behalf of Chairman, Airports Authority of India

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst.General Manager (E-E)

Name of Work: "SITC of Feeder Pillar and Replacement of faulty cables at Bhuj Airport."


Contract No: 2021_AAI_89672_1

Name of the Bidder/ Bidding Firm / Company : M/s. Rudraksha Enterprise

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of XLPE insulated and PVC sheathed Aluminum armoured LT cable of 1.1 KV grade confirming to IS 7098, Part-I 1988 with up to date amendments of following size and confirming to technical specifications.					
1.01	3½ X 50 sq.mm	415.00	Mtr	303.00	125745.00	INR One Lakh Twenty Five Thousand Seven Hundred & Forty Five Only
1.02	4 X 25 sq.mm	460.00	Mtr	203.00	93380.00	INR Ninety Three Thousand Three Hundred & Eighty Only
2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
2.01	4 X 25 sq. mm (28mm)	4.00	Each	450.00	1800.00	INR One Thousand Eight Hundred Only
2.02	3½ X 50 sq. mm (35mm)	4.00	Each	450.00	1800.00	INR One Thousand Eight Hundred Only
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering. and refilling the trench etc as required.					



NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3.01	Upto 35 sq. mm	119.50	Mtr	130.00	15535.00	INR Fifteen Thousand Five Hundred & Thirty Five Only
3.02	Above 35 sq mm and upto 95 sqmm	51.00	Mtr	130.00	6630.00	INR Six Thousand Six Hundred & Thirty Only
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground , sand cushioning, protective covering and refilling the trench etc but excluding excavation as required.					
4.01	Upto 35 sq. mm	130.50	Mtr	130.00	16965.00	INR Sixteen Thousand Nine Hundred & Sixty Five Only
4.02	Above 35 sq mm and upto 95 sqmm	80.00	Mtr	130.00	10400.00	INR Ten Thousand Four Hundred Only
5	Excavation of the cable trenches in hard rock not exceeding 1.5 meters in width and lift up to 1.5 meters , including getting out the excavated soil and disposal of excavated soil as directed.	50.00	Cum	600.00	30000.00	INR Thirty Thousand Only
6	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.					
6.01	Upto 35 sq. mm	183.00	Mtr	20.00	3660.00	INR Three Thousand Six Hundred & Sixty Only
6.02	Above 35 sq mm and upto 95 sqmm	75.00	Mtr	20.00	1500.00	INR One Thousand Five Hundred Only
7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.					
7.01	Above 35 sq mm and upto 95 sqmm	157.00	Mtr	20.00	3140.00	INR Three Thousand One Hundred & Forty Only
8	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.					
8.01	Above 35 sqmm and upto 95 sq mm (clamped with 25 X 3 mm MS flat clamp	30.00	Mtr	30.00	900.00	INR Nine Hundred Only
9	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.					

Atg/nd

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
9.01	Upto 35 sq. mm (clamped with 1mm thick saddle)	5.00	Mtr	35.00	175.00	INR One Hundred & Seventy Five Only
10	Providing and laying non pressure NP2 Class (light duty) 250 mm R.C.C Pipes with collers jointed with stiff mixture of cement mortar in proportion of 1:2 (1 Cement : 2 Sand) including cutting / breaking PCC/Bituminous area upto suitable depth and 400 mm width and remaking the same as good as previous etc. complete as required.	129.00	Mtr	400.00	51600.00	INR Fifty One Thousand Six Hundred Only
11	Constructing masonry Chamber 900 mm x 900 mm x 1000 mm inside, with 50 class designation brick work in cement mortar 1:4 (1 cement : 4 coarse sand) , RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate) 20 mm nominal size with RCC Cover i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate) 40 mm nominal size and inside plastering with cement mortar 1:4 (1 cement : 4 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :With common burnt clay F.P.S.(non modular) bricks of class designation 7.5.	2.00	Each	10000.00	20000.00	INR Twenty Thousand Only
12	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	50.00	Each	360.00	18000.00	INR Eighteen Thousand Only
13	SITC of Feeder Pillar					

21644

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
13.01	Supplying, installation, testing & commissioning of cubical, outdoor type, dust and vermin proof and having IP 54 protection Feeder Pillar suitable for 415V, 3 phase, 4 wire 50 Hz AC supply system fabricated in totally enclosed and compartmentalized design from CRCA sheet steel of 2 mm thick for load bearing members & 1.6 mm thick for doors i/c cleaning & finishing complete with powder coating in approved shade, TPN Aluminium Alloy bus bars of high conductivity, DMC/ SMC bus bar supports, suitable angle /channels frame in the bottom i/c civil masonry foundation works as per site requirement etc. complete as required as per technical specifications i/c providing following switch gears and accessories: <u>Incomer</u> 63 Amp 4 pole (36 KA, lcs = 100% lcu) MCCB - 1No. <u>Bus Bars</u> 100 Amp. TPN bus bars of aluminium alloy of suitable size as per technical specifications. <u>Outgoings</u> A) 63 Amp. 4 Pole, 10 KA, (lcs=100%lcu) MCCBs- 2 no. B) Spare Compartment - 1 no. with DIN Rail Channel and wiring provision. <u>Instruments</u> RYB indication lamps for incomer MCCB- 1 Set with protection fuses for control wiring, 15 A industrial socket -1 no.	2.00	Each	55000.00	110000.00	INR One Lakh Ten Thousand Only
14	Supply of Recessed mounting 2' x 2' LED panel Luminaire, 36W, IP 20, CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling complete as per technical specifications. Make : Bajaj (BZRSQ 36L LED GX D CW SD) or Equivalent.	14.00	Each	1500.00	21000.00	INR Twenty One Thousand Only
Total in Figures					532230.00	INR Five Lakh Thirty Two Thousand Two Hundred & Thirty Only
Quoted Rate in Words		INR Five Lakh Thirty Two Thousand Two Hundred & Thirty Only				

Signature Not Verified


Digitally signed by MD SADRUL HUDA

Date: 2021.11.22 16:26:10 IST

Location: eProcurement System for Central PSUs

मो. सदरुल हुदा

मार्च २०२१



MD. Sadrul Huda
Asst. General Manager (Engg-Elect.)
Airports Authority of India
प. क्षेत्र, मुख्यालय, मुंबई - 400 099.