



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

भा.भा.वि.प्रा./मदुरै/इ(वि)/MDU-311/21-22

Ref: AAI/MDU/E-E/MDU-311/21-22

दि:/Date: 27.10.2021

सेवा में /To

M/s. Sun Motor Rewinding Contractor,
No .151 , Nelamandi street,
Sivagangai -630531
E-mail: natarsansaran@gmail.com

विषय/Sub : ARMO Works of E&M Installations at Madurai Airport during 2021-2022. SH: Minor Electrical Repairs in operational area , Madurai Airport – reg.
संदर्भ/Ref: Your e-tender Financial bid number - 2021 AAI 90888 1 Opened on
20.10.2021

महोदय/Dear sir(s),

- 1) Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 3,40,980.00** (Rupees Three Lakh Forty Thousand Nine Hundred and Eighty Only) plus applicable GST which is 15.32% below the estimated cost put to tender of Rs. 4,02,687 plus applicable GST.
- 2) Jt. General Manager (Engg-Elect.), Airports Authority of India, Madurai Airport, Madurai- 625 022, shall be the Engineer-in-charge of the work. You are requested to attend the office of the Asst. General Manager (Engg-Elect.), AAI, Madurai Airport by **05.11.2021** to sign and complete the contract agreement. The contract Agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only). The tender document shall be downloaded and signed in each page which shall form part of the agreement. The entire cost towards stamp paper, downloading and printing tender document shall be borne by the contractor.
- 3) As per relevant clause of GCC-2017, which is a part of the contract agreement, security deposit @ 10% (Ten Percent) of gross amount of First & Final bill will be deducted, which shall be released after successful completion of Defects Liability Period.

Contd....2

विमानपत्तन निदेशक का कार्यालय, मदुरै हवाई अड्डा, मदुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.


(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

-2-

- 4) You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no.50 of GCC of tender and rules of Central and State Governments.
- 5) You are also directed to contact Manager (Engg-Elect)-II, AAI, Madurai Airport immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be **2 months** and the same shall be reckoned from the same date of the award of this work order.
- 6) Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
- 7) Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 8) All other terms & Conditions shall be as per tender document.
- 9) This work order is allotted the number MDU-311 which shall be quoted by you for all future correspondence in connection with this Supply order.

Encl: Schedule of Work

Yours faithfully,


Asst. General Manager (E-E)
For and on behalf of the Chairman
Airports Authority of India

विमानपत्तन निदेशक का कार्यालय, मदुरै हवाई अड्डा, मदुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AIRPORTS AUTHORITY OF INDIA


Name of Work: : ARMO Works of E&M Installations at Madurai Airport during 2021-22. SH: Minor Electrical repairs in operational area, Madurai Airport.

Contract No: AAI/MDU/E-E/MDU-311/NIT-05/2021-22

Name of the Bidder/ Bidding Firm / Company :	M/S. SUN MOTOR REWINDING CONTRACTOR, SIVAGANGAI					
PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY) (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) Please Note: 1) Tenderer should quote the rates Excluding of GST. 2) GST shall be paid to bidder for taxable services/supply against a valid tax invoice.						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply & Fixing of 6mm thick M.S. powder coated cover plate suitable for 330mm dia CI transformer housing box having 6 nos of M10 tapped holes.	16	Nos	650.00	10400.00	INR Ten Thousand Four Hundred Only
2	Supply & Fixing of rubber Gaskets suitable for 330mm dia CI transformer housing box.	16	Nos	250.00	4000.00	INR Four Thousand Only
3	Supply of M10 size stainless steel bolts of 25mm length with spring & plain washers.	300	Nos	10.00	3000.00	INR Three Thousand Only
4	Earthing with GI earth pipe 4.5m long , 40 mm dia "B" class including accessories, and providing masonry enclosure of opening 400mmx 400mm with heavy duty cover plate including locking arrangement and watering pipe etc with charcoal/coke and salt complete as required.	6	Set	4700.00	28200.00	INR Twenty Eight Thousand Two Hundred Only
5	Providing and laying earth connections from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode as required.	50	Mtr	170.00	8500.00	INR Eight Thousand Five Hundred Only

6	Dismantling of existing damaged CI transformer boxes embedded in cement concrete with suitable machine tool including removing the series isolating transformers & its cables and making the site clean etc as required.	9	job	900.00	8100.00	INR Eight Thousand One Hundred Only
7	Installation of CI transformer housing box of height 450mm with a base concrete of 1:3:6 of size 630X630X100 mm thick, all round concrete of 1:2:4 150mm thick, top sloped with 1:2:4 cement concrete including excavation, disposal of material within 20 mtrs lead ,providing and fixing 300mm long 15mm dia "B" class GI pipe with checknut for drainage of water etc complete as required.	11	job	2400.00	26400.00	INR Twenty Six Thousand Four Hundred Only
8	Providing and laying in position cement concrete 1:3:6 (1cement : 2 coarse sand : 6 graded stone aggregate 20 mm nominal size) of size 1ft x 1ft with an average thickness of 100mm around the Transformer housing Boxes /Earth pit chambers including top sloping the protruded portion of CI box/Earth pits with graded surface. This job also include Surface dressing, leveling ,watering, ramming, and finishing the surface as required.	24	Job	700.00	16800.00	INR Sixteen Thousand Eight Hundred Only
9	Providing & laying in position cement concrete of 1:2:4 with 20mm stone aggregate at required places in operational area.	10	cum	5200.00	52000.00	INR Fifty Two Thousand Only
10	Retrieving of existing 5 KV grade Airfield cables upto 16Sqmm from the underground trench which includes excavation of earth, removing of brick protection & cable , refilling the trench and restoring the surface etc as required.	200	mtr	130.00	26000.00	INR Twenty Six Thousand Only
11	Retrieving of existing 1.1KV grade power cables upto 240 Sqmm from the underground trench which includes excavation of earth, removing of brick protection & cable , refilling the trench and restoring the surface etc as required.	200	Mtr	165.00	33000.00	INR Thirty Three Thousand Only
12	Laying of 50mm dia HDPE pipe / DWC HDPE pipe direct in ground below 75cm in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc complete as required.	300	Mtr	98.00	29400.00	INR Twenty Nine Thousand Four Hundred Only
13	Laying of 110mm dia HDPE pipe / DWC HDPE pipe direct in ground below 75cm in all types of soil including excavation and refilling the trench but excluding sand cushioning and protective covering etc complete as required.	30	Mtr	100.00	3000.00	INR Three Thousand Only
14	Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 5 KV grade of size not exceeding 25 sqmm in the existing RCC/HUME/STONEWARE/METAL/HDPE/DWC pipe as required.	200	Mtr	24.00	4800.00	INR Four Thousand Eight Hundred Only
15	Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of size not exceeding 35 sqmm in the existing RCC/HUME/STONEWARE/METAL/HDPE/DWC pipe as required.	200	Mtr	25.00	5000.00	INR Five Thousand Only

16	Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of size 185 sqmm to 400 sqmm in the existing RCC/HUME/STONEWARE/METAL/HDPE/DWC pipe as required.	150	Mtr	100.00	15000.00	INR Fifteen Thousand Only
17	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVCsheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 2Cx25 Sqmm.	2	Set	2300.00	4600.00	INR Four Thousand Six Hundred Only
18	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVCsheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5C x35 Sqmm.	2	Set	2750.00	5500.00	INR Five Thousand Five Hundred Only
19	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVCsheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5C x185 Sqmm.	4	Set	5260.00	21040.00	INR Twenty One Thousand &Forty Only
20	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVCsheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5C x240 Sqmm.	2	Set	6200.00	12400.00	INR Twelve Thousand Four Hundred Only
21	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4C X 16sqmm.	2	Set	2200.00	4400.00	INR Four Thousand Four Hundred Only
22	Providing 1:2 cement mortar all around the protruding portion of CI box, upto 15cm with proper sloping with average thickness upto 5cms	108	Job	180.00	19440.00	INR Nineteen Thousand Four Hundred & Forty Only
Total in Figures					340980.00	INR Three Lakh Forty Thousand Nine Hundred & Eighty Only
Quoted Rate in Words		INR Three Lakh Forty Thousand Nine Hundred & Eighty Only				


 सहायक महा प्रबंधक (अभि.वि.)
 Asst. General Manager (E.E)
 भा.वि.प्रा. मदुरै हवाई अड्डा
 AAI, Madurai Airport