



**AIRPORTS AUTHORITY OF INDIA
BEGUMPET AIRPORT, HYDERABAD 500 016**

**By Speed Post.
DT: 08.11.2021**

Ref. No: AAI/HYD/Engg(C)/M/CAP/W-02/21-22/

To,
M/s. S.K.Construction,
Village-Barema,
Post-Rameshwar Babatpur,
Varanasi (UP) - 221 405.

Name of Work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad.
SH : Civil Works (Balance Work at the Risk & Cost of Main Work).


Ref : Tender Id No. 2021_AAI_90143_1 Opened on: 22.10.2021

Dear Sir,

1. Your e-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs.1,14,03,711/- (Rupees One Crore Fourteen Lakhs Three Thousand Seven Hundred and Eleven Only)** which is (-) 20.13% (Minus Twenty Point One Three Percent) (Excluding GST) below the estimated cost put to tender of **Rs.1,42,77,300/- (Excluding GST) - (Rupees One Crore Forty Two Lakhs Seventy Seven Thousand Three Hundred only).**
2. **Joint. General Manager Engg.-(C), AAI, Begumpet Airport, Hyderabad** shall be the Engineer-In-Charge of the work. You are requested to attend the office of **J.G.M Engg.-(C), Airports Authority of India, Begumpet Airport, Hyderabad** by **23.11.2021** to sign and complete the Contract Agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/- (Rupees Hundred only)** and the cost of the stamp paper shall be borne by you.
3. The Earnest money amount undertaking submitted in Annexure-L for an amount of **Rs.2,85,546/- (Rupees Two Lakh Eighty Five Thousand Five Hundred and Forty Six only).** As per the clauses of contract clause No. 1A on page 16 of GCC of the contract document, you are requested to deposit **Rs.11,40,371/- (Rupees Eleven Lakhs Forty Thousand Three Hundred and Seventy One Only)** towards Security Deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your running bills as per General rules and Directions on Clause 14(iv) on page 10 of GCC under head "Security Deposit" of the contract document.

4. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and contract labour (Regulation and Abolition) central rules 1971 Child labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and conditions of services) Act 1996, Building and other construction workers welfare cess Act 1996 as specified in clause 19 on GCC-49 of GCC of Tender and rules of Central and State Govt.
5. You are also directed to contact **Joint. General Manager Engg.-(C)** in the office of the **JGM Engg(C)**, immediately who will arrange to hand over the site to you.
6. Please note that the time allowed for carrying out the work is **05 (Five) Months** as entered in the Tender and shall be reckoned from the 10th day after issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. Please acknowledge the receipt and return the duplicate copy of the letter enclosed here with after signing to the undersigned as a token of acceptance.

Yours faithfully,



J.G.M. Engg (C)
Begumpet Airport, Hyderabad
For and on behalf of Chairman
Airports Authority of India.

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate ⁱⁿ Rupees	Amount ⁱⁿ Rupees
1	Supplying chemical emulsion in sealed containers including delivery as specified. Chlorpyrifos/ Lindane emulsifiable concentrate of 20%	Liter	384.00	280.00	107520.00
2	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) : Treatment of existing masonry using chemical emulsion @ one litre per hole at 300 mm interval including drilling holes at 45 degree and plugging them with cement mortar 1:2 (1 cement : 2 coarse sand) to the full depth of the hole With Chlorpyrifos/Lindane E.C. 20% with 1% concentration	mts	925.00	35.00	32375.00
3	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) : Treatment at points of contact of wood work by chemical emulsion Chlorpyrifos/ Lindane (in oil or kerosene based solution) @ 0.5 litres per hole by drilling 6 mm dia holes at downward angle of 45 degree at 150 mm centre to centre and sealing the same.	mts	245.00	25.00	6125.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	Cum	16.00	5400.00	86400.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size).	Cum	16.00	4290.00	68640.00
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	6.00	7850.00	47100.00
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	kgs	565.00	90.00	50850.00
8	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5.0 in superstructure above plinth level up to floor five level in :Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	33.00	6150.00	202950.00
9	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300mm thick AAC blocks in super structure above plinth up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer in Charge.(The payment of RCC band and reinforcement shall be made for saperately	Cum	20.00	6250.00	125000.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
10	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels . Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble Area of slab over 0.50 sqm	sqm	40.00	2400.00	96000.00
11	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm	Sqm	62.00	2300.00	142600.00
12	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Marble work	Mtr	72.00	210.00	15120.00
13	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work	mts	44.00	215.00	9460.00
14	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	sqm	589.00	50.00	29450.00
15	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	Cum	1.20	95800.00	114960.00
16	Providing and fixing ISI marked flush door shutters conforming to IS .2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	sqm	165.00	1680.00	277200.00
17	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	sqm	165.00	240.00	39600.00
18	Extra for providing vision panel not exceeding 0.1 sqm in all type of flush doors (cost of glass excluded) (overall area of door shutter to be measured): Rectangular or square	sqm	165.00	155.00	25575.00
19	Extra if louvers (not exceeding 0.2 sqm) are provided in flush door shutters (overall area of door shutters to be measured). Decorative type door	sqm	20.00	580.00	11600.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
20	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories 3and screws etc. complete	each	66.00	1050.00	69300.00
21	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.	Sqm	330.00	860.00	283800.00
22	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge:Fixing with adjustable lugs with split end tail to each jamb	mts	110.00	400.00	44000.00
23	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kgs	406.00	78.00	31668.00
24	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	kgs	2753.00	405.00	1114965.00
25	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	456.00	730.00	332880.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
26	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I.wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum moisture resistant board	Sqm	332.00	750.00	249000.00
27	Providing and fixing tiled false ceiling of approved materials of size 595x595mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge GI Metal Ceiling Lay in perforated Tegular edge global white color tiles of size 595x595 mm and 0.5 mm thick with 8 mm drop, made of GI sheet having galvanizing of 100 ms/sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC (Noise Reduction Coefficient) of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation, and backed with a black Glass fiber acoustical fleece.	Sqm	1095.00	1665.00	1823175.00
28	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanising @ 120 grams per sqm including both side) consisting of main "T" runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main "T" at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size 24x24x3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main "T" runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main "T", bottom exposed with 24mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge. Note :- Only calcium silicate false ceiling area will be measured from wall to wall. No deduction shall be made for exposed frames/ opening (cut outs) having area less than 0.30 sqm. The calcium silicate ceiling tile shall have NRC value of 0.50 (Minimum), light reflection > 85%, non- combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity <0.043 w/mK.	sqm	295.00	900.00	265500.00
29	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	Sqm	359.00	210.00	75390.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
30	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer	sqm	2704.00	40.00	108160.00
31	Applying priming coat : With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	Sqm	108.00	65.00	7020.00
32	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work	sqm	3388.00	95.00	321860.00
33	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	sqm	27.00	110.00	2970.00
34	Providing and applying white cement based <u>putty</u> of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	2704.00	75.00	202800.00
35	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	2.00	500.00	1000.00
36	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground.	sqm	1.00	850.00	850.00
37	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	2704.00	15.00	40560.00
38	Finishing walls with textured exterior paint of required shade :Old work (One or more coats) applied @ 1.82 ltr/10 sqm.	sqm	3858.00	100.00	385800.00
39	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	each	13.00	150.00	1950.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
40	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50metres lead as per direction of Engineer-in-charge.	Cum	1.00	950.00	950.00
41	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area beyond 3 sq. metres	each	39.00	250.00	9750.00
42	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	each	48.00	250.00	12000.00
43	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	kgs	1077.00	3.00	3231.00
44	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm	590.00	38.00	22420.00
45	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead : Up to 10 mm thick.	sqm	547.00	28.00	15316.00
46	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : 15 mm to 40 mm nominal bore	mts	120.00	110.00	13200.00
47	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	each	13.00	250.00	3250.00
48	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	22.00	35.00	770.00
49	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	sqm	347.00	25.00	8675.00
50	Providing and laying matt finished vitrified tile of size 300x300x9.8mm having water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	sqm	40.00	1315.00	52600.00
51	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.	each	10.00	2850.00	28500.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
52	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia	each	10.00	250.00	2500.00 ✓
53	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal outer dia Pipes	mts	69.00	315.00	21735.00 ✓
54	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 25 mm nominal outer dia Pipes	mts	94.00	345.00	32430.00 ✓
55	Providing and fixing unplasticised PVC connection pipe with brass unions : 45 cm length 15 mm nominal bore	each	34.00	105.00	3570.00 ✓
56	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm nominal bore	each	32.00	625.00	20000.00 ✓
57	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with waterproofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	sqm	63.00	415.00	26145.00 ✓
58	Providing and fixing white vitreous china flat back sensor urinal of make CERA Model No: 5005A or equivalent of approx. size 740X360 x 330mm with integrated EFS having water inlet from back side, including fixing to wall with suitable brackets all as per manufacturers specification and direction of Engineer-in-charge.	each	19.00	8650.00	164350.00 ✓
59	Providing and fixing on wall face unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.(i) Single socketed pipes 110mm diameter	mts	45.00	280.00	12600.00 ✓
60	Providing and fixing on wall face unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.(i) Single socketed pipes 75mm diameter	mts	45.00	200.00	9000.00 ✓

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
61	Providing and fixing PVC moulded fittings/ accessories: Plain Floor Trap with out jali 75mm.	each	24.00	250.00	6000.00
62	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.Plain Bend - 110mm	each	12.00	150.00	1800.00
63	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Plain Bend - 75mm	each	12.00	125.00	1500.00
64	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.Plain -Y 110x110x110 mm	each	12.00	180.00	2160.00
65	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Plain -Y 75x75x75 mm	each	12.00	150.00	1800.00
66	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Plain tee - 110x110x110 mm	each	12.00	280.00	3360.00
67	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC pipes conforming to IS : 13592 Type B including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Plain tee 75x75x75 mm	each	12.00	250.00	3000.00
68	Providing and fixing white vitreous china single piece EWC cum flushing cistern with seat cover of Model : Prince and code No: C0849N/O/P of make Parryware with S trap 280/210/110mm as required with seat cover and in built fittings complete including making necessary connections cutting and making good the floors where ever required	each	14.00	5680.00	79520.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
69	Providing and fixing windows (ECO 5000 SERIES of NCL Allteck Seccolar or Equivalent) made of pre-painted steel (Base steel as per IS 513 of 0.58mm thick galvanized as per IS 277 with Zinc of 120 GSM) primer coated with epoxy primer of 5-7 microns thick, finish painted with a polyester paint of 12-16 micron thick and back coated with 5-7 micron thick alkyd backer. Section for outer frame should be of 98X52mm, center mullion should be of 46X70mm, section for shutter frame should be of 46mmx46mm and section for glass beading should be of 18 mmX25 mm. Outer frame & mullion section to have rebate for glazed shutters, fly mesh and a 20mm provision for guard bars/grills. The sections are to be cut to length metre jointed with corner bracket made of polypropylene. Glass shutter should be mitre jointed with frame / mullion using nylon mullion cap EPDM gasket should be securely fixed around the glass in shutter between the frame and glazed shutter and both side of fixed glass. Each glazed shutter should be provided with MS powder coated friction hinges -1set, high grade aluminium powder coated handle with nylon receiver -1 no. Glass shutter and fixed glass portions should be provided with glass of 5 mm plain float glass of make saint gobain/AIS. Windows should be provided with grill made of 10mm powder coated MS square guard bars welded to 6mmx12mm powdercoated MS flat at a spacing of 100mm c/c. Grills to be fixed to window frame with 19 mm long GI self drilling screws. Corner brackets to be made of CRCA with zinc phosphating. Mullion caps be made of glass filled nylon. The frame should be fixed to the concrete/masonry wall by means of self-expanded screws driving MS electro plated 80mm long screws into the sleeves through the frame, etc complete for finished item of work.	sqm	22.00	3175.00	69850.00
70	Providing and fixing windows (Ajantha Series of NCL Allteck Seccolar or Equivalent) made of pre-painted steel (Base steel as per IS 513 of 0.58mm thick galvanized as per IS 277 with Zinc of 120 GSM) primer coated with epoxy primer of 5-7 microns thick, finish painted with a polyester paint of 12-16 micron thick and back coated with 5-7 micron thick alkyd backer. Section for outer frame should be of 46mmX52mm, center mullion should be of 46X70mm, section for shutter frame should be of 46mmx46mm and section for glass beading should be of 18 mmX25 mm. Outer frame & mullion section to have rebate for glazed shutters. The sections are to be cut to length metre jointed with corner bracket made of polypropylene. Glass shutter should be mitre jointed with frame / mullion using nylon mullion cap EPDM gasket should be securely fixed around the glass in shutter between the frame and glazed shutter and both side of fixed glass. Each glazed shutter should be provided with MS powder coated friction hinges -1set, high grade aluminium powder coated handle with nylon receiver -1 no. Glass shutter and fixed glass portions should be provided with 5 mm plain float glass of make saint	sqm	141.00	2850.00	401850.00
71	Providing and fixing C.P. brass two way bib cock Model No: CON-CHR-041KNF of Jaquar make or Equivalent 15 mm nominal bore	each	20.00	3590.00	71800.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
72	Providing and laying Glazed Vitrified floor tiles of double charged variant (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid With cement based High polymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 3mm thickness, including grouting the joints with white cement and matching pigments etc., complete. Size of tile 600mm x 600mm	sqm	1285.00	1050.00	1349250.00
73	Providing and fixing Health Faucet ABS with double lock 1.20 metre long stainless steel flexible hose and wall hook catalogue No: 573 of Jaquar or equivalent	each	20.00	1280.00	25600.00
74	Providing and fixing bright finished Contractor pro series - OCXP Door lock with key of ozone make(Product Code No: OCXP.001.K60 8" CP/SN) or equivalent with necessary screws etc. complete for flush door shutters.	each	64.00	2560.00	163840.00
75	Providing and fixing SS 202-SSS grade standard type tower bolts, of approved make of Ozone(Product code No:OZ-TB-SE 8"), with necessary screws etc. complete	each	64.00	1250.00	80000.00
76	Providing and fixing SS door stopper with rubber cushion, model no OZ-DST-55E stdSN of make OZONE or equivalent necessary screws etc. to suit shutter thickness complete	each	64.00	250.00	16000.00
77	Providing and fixing plain mirror of 5mm thick of required size (of approved quality, Modi Guard/Saint gobain or equivalent) fixed to wall with 20 x 25mm Stainless steel studs including making necessary holes to glass and the wall and including wooden plugs etc complete as per the direction of E I C	sqm	18.00	1150.00	20700.00
78	Providing and fixing Roller Blinds of of approved size of make MAC (SLM - 3724 London Mist) or equivalent with openness factor approximately 5% and the material composition should be of 12% polyester and 88% PVC, Thickness 0.68mm, Breaking strength- Warp>100 daN/5 Cm & Weft>100daN/5 Cm with necessary accessories complete, as per the site condition and as directed by EIC	sqm	150.00	2040.00	306000.00
79	Providing & fixing CP Brass Soap Dispenser. Jaquar make(product Code ACN-1135N) or equivalent.	each	15.00	1050.00	15750.00
80	Providing and fixing 32mm CP Brass Waste Coupling for wash basin/Urinal Model No: ALD-CHR-705/709 of Jaquar or equivalent.	each	43.00	1050.00	45150.00
81	Providing and fixing homogeneous polyvinyl chloride sheet/tile in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality and manufacturer like Dunlop S-758, Fevicol SR 998 or equivalent including rolling with light wooden roller weighing about 5 kg. all complete as directed by Engineer-in-charge, in approved colour and shade. 1.5 mm thick(rate per sqm with sheet)	sqm	20.00	2150.00	43000.00
82	Spray Painting of existing aluminium work with Poly-ur-ethylene paint of make MRF or equivalent to give an even shade with required PU thinner and Two coats of Metal coat as per manufacturers recommendations.:Old Work	sqm	43.00	205.00	8815.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
83	Providing and fixing 12 mm thick compact laminate Urinal partition of height 1195 mm to 1200 mm and width 450mm to 500mm with SS 304 grade accessories of make Greenlam Model A or Merino UMP SS series or equivalent as approved by Engg-in-charge.	each	14.00	1650.00	23100.00
84	Providing and laying Matt Finished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of tile 600mm x 600mm	sqm	147.00	1000.00	147000.00
85	Providing and fixing C.P. brass pillar Cock 15mm nominal bore with auto closing system 65 mm extension body Jaquar make (product Code PRS-CHR-031L65) or equivalent as approved by Engg-in-charge.	each	23.00	2150.00	49450.00
86	Providing and fixing white vitreous china wash basin of oval shape below counter type 550x400mm or nearest size. Parryware make (product code No : C0407) or equivalent	each	8.00	5560.00	44480.00
87	Providing and fixing CP brass bottle trap (with internal partition) 32mm dia size with long wall connection pipe and with flange of Jaquar make Category No: ALE-ESS 773NL 250x250 or equivalent.	each	8.00	1250.00	10000.00
88	Providing and fixing CP brass Drain Square Hinged hole for waste pipe of Viking make Category No: 41719 or equivalent. 100 mm dia	each	10.00	250.00	2500.00
89	Providing and fixing CP brass Drain Square Hinged without hole for waste pipe of Viking make Category No: 41726 or equivalent. 100 mm dia	each	29.00	190.00	5510.00
90	Providing & fixing Greenlam Sturdo Classique Evergreen model or Equivalent Cubicles (of following standard dimension which includes 600mm door size width) made of heat, bacteria, water, chemical, scratch and impact resistant 12mm thick solid compact laminate panels including doors, pilasters & intermediate panels finished with approved texture/shade as per the detail drawings & as per IS 2046 (Indian Standard) and as per fire retardant BS-476/97 standard. The product should have Green Guard Certificate. This also includes providing and fixing in position necessary hardware made out of Stainless steel (Grade 304) as per manufacturer's specifications & Architects instructions like (1) Door Knob, (2) Gravity Hinges, (3) Lockset with indicators, (4) Coat hooks with door stopper (5) U- Channels, (6) Adjustable leg, (7) Top rail hollow circular pipe (8) Corner connector (9) Rubber noise deafening tape for grooves in door & pilasters (10) Wall Bracket (11) Screws & wall Plugs. The top fitting should consist of SS round top rail which will get fixed with pilasters, with SS panel tube holder, SS corner bend (connected with top rail) will be used on the corner of cubicle in absence of brick wall, SS wall fixing is used only on the wall which will hold the ss top rail. All screws will be of 304 Grade in stainless steel with satin finish. All pilasters are supported by stainless steel bottom cladding. The base of the stainless steel bottom cladding will be anchored to the floor with a clearance height upto 150mm. as per direction of Engineer-In-charge. The contractor has to submit necessary detailed shop drawing before execution of the work. a) "L" Partition W-1.24m, D-1.60m; H-2.025m a) "L" shape Cubicle	each	5.00	42560.00	212800.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
91	Providing & fixing Greenlam Sturdo Classique Evergreen model or Equivalent Cubicles (of following standard dimension which includes 600mm door size width) made of heat, bacteria, water, chemical, scratch and impact resistant 12mm thick solid compact laminate panels including doors, pilasters & intermediate panels finished with approved texture/shade as per the detail drawings & as per IS 2046 (Indian Standard) and as per fire retardant BS-476/97 standard. The product should have Green Guard Certificate. This also includes providing and fixing in position necessary hardware made out of Stainless steel (Grade 304) as per manufacturer's specifications & Architects instructions like (1) Door Knob, (2) Gravity Hinges, (3) Lockset with indicators, (4) Coat hooks with door stopper (5) U- Channels, (6) Adjustable leg, (7) Top rail hollow circular pipe (8) Corner connector (9) Rubber noise deafening tape for grooves in door & pilasters (10) Wall Bracket (11) Screws & wall Plugs. The top fitting should consist of SS round top rail which will get fixed with pilasters, with SS panel tube holder, SS corner bend (connected with top rail) will be used on the corner of cubicle in absence of brick wall, SS wall fixing is used only on the wall which will hold the ss top rail. All screws will be of 304 Grade in stainless steel with satin finish. All pilasters are supported by stainless steel bottom cladding. The base of the stainless steel bottom cladding will be anchored to the floor with a clearance height upto 150mm. as per direction of Engineer-In-Charge. The contractor has to submit necessary detailed shop drawing before execution of the work. a) "L" Partition W-1.24m; D-1.60m; H-2.025m b) "I" shape (Front) Cubicle	each	1.00	41555.00	41555.00
92	Shifting & replacing back to position of Big Tables by Assembling & Disassembling process for the purpose of renovation of Offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	48.00	560.00	26880.00
93	Shifting & replacing back to position Chairs for the purpose of renovation of offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	96.00	110.00	10560.00
94	Shifting & replacing back to position File Racks by Assembling & Disassembling process for the purpose of renovation of offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	1.00	1200.00	1200.00
95	Shifting & replacing back to position Computer Tables for the purpose of renovation of offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	14.00	1200.00	16800.00
96	Shifting & replacing back to position Sofas for the purpose of renovation of offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	17.00	555.00	9435.00
97	Shifting & replacing back to position Almarah's for the purpose of renovation of offices from Ground floor to Third floor including files at a distance of 300m to 400m as directed by Engineer-In-Charge.	each	17.00	1000.00	17000.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
98	Providing and fixing 3.00 m high fixed frameless glass internal partitions to form Cubicles and plain wall at all floors with 12 mm thick clear toughened glass of saint gobain/AIS or approved equivalent as per elevation drawings with aluminium wedge profile with SSS finish/PSS finish OGL-PR-22 of make Ozone or equivalent in Hafele/Dorma with EPDM gasket OZ-EPDM-44 and OZ-EPDM-33 of make Ozone or equivalent in Hafele/Dorma fixed at floor and false ceiling level profile fixed with SS screws of size 8x50 mm at spacing of 300mm including necessary filling up gaps at junction and sides of glass with required weather silicon sealant edge buffing of the glass providing edge cap wherever required etc. complete .(Necessary supporting MS frame work for fixing of wedge section at false ceiling level will be done separately.Only glass area will be measured for payment. All the handling, transportation and insurance charges for glass if required will be borne by the agency.)	sqm	84.00	4300.00	361200.00
99	Providing and fixing 1800mm wide frameless double leaf swing glass door with over head panel using 12 mm thick toughened glass of Saint Gobain /AIS or approved equivalent fixed with die cast fittings with stainless steel cover of grade 304 in SSS finish including fixing of patch fittings, floor springs, locks, handles etc. using the hardware items which includes standard Bottom Patch code no.OPF-3 of Ozone or equivalent in Hafele/Dorma, standard top Patch code no.OPF-2 of Ozone or equivalent in Hafele/Dorma standard Over panel side panel connecting patch with pivot code no. OPF-1 Corner Lock OPL-1 Super Floor Spring code no.FS-8400-S of Ozone in Hafele/Dorma , SS Pull Handle SSS finish 25x450 mm code no OGH -55 of make ozone or equivalent in Hafele/Dorma and other accessories for self closing feature complete in all respects including edge buffing of all sides of glass , mirror polishing and 2mm champferring of exposed edge of door glass as per detailed drawings, manufacturers specifications and direction of Engineer in charge. (Only door area including over head panel will be measured for payment. All the handling, transportation and insurance charges if required will be borne by the agency.)	sqm	16.00	5000.00	80000.00
100	Providing and fixing 1000mm wide frameless single leaf swing glass door with over head panel using 12 mm thick toughened glass of Saint Gobain /AIS or approved equivalent with fixed with die cast fittings with stainless steel cover of grade 304 including fixing of patch fittings, floor springs, locks, handles etc. using the hardware items which includes standard Bottom Patch code no.OPF-3 of make Ozone or equivalent in Hafele/Dorma , standard top Patch code no.OPF-2 of Ozone or equivalent in Hafele/Dorma standard Over panel side panel connecting patch with pivot code no. OPF-1, f Corner Lock OPL-1 Super Floor Spring code no.FS-8400-S of Ozone or equivalent in Hafele/Dorma , SS Pull Handle SSS finish 25x450 mm code no OGH -55 of make ozone or equivalent in Hafele/Dorma and other accessories for self closing feature complete in all respects including edge buffing of all sides of glass , mirror polishing and 2mm champferring of exposed edge of door glass as per detailed drawings, manufacturers specifications and direction of Engineer in charge. (Only door area including over head panel will be measured for payment. All the handling, transportation and insurance charges if required will be borne by the agency.)	sqm	38.00	4500.00	171000.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
101	Providing and Fixing 1200 mm frameless free standing toughened glass (Saint Gobain/Asahi or approved equivalent) partition forming cubicles of 1200 mm height and of required length with mirror polished exposed edges ,fixed as per specified lay out with 150mm high spigot with base SS 304 of Taiton or equivalent make code no. TBF-SG-B-6 fixed with SS anchor fasteners of size 8x100 mm as legs glass to glass connectors 180 degree (code no.OGC-5 of Ozone or equivalent) glass to glass connectors 90 degree (code no.OGC-3 of Ozone or equivalent in Hafele/Dorma) glass to wall connectors 90degree (code no.OGC - 4 of Ozone or equivalent in Hafele/Dorma) including necessary accessories as required ts with nuts etc used as and where required as per layout plan. glass to be of required length with proper support with all gaps filled with silicon sealent ,Glass to have holes/cut outs to accommodate patch fittings. all complete. (Net Area of Glass to be measured for payment purpose. All the handling, transportation and insurance charges if required will be borne by the agency.)	sqm	24.00	4100.00	98400.00
102	Providing and fixing interior designer film of approved pattern of McCal make over the designated locations with wet applications at all floors in any design and pattern complete as per the direction and satisfaction of Engineer-in-charge. (No deductions shall be made for the blank areas in the pattern. only film area will be measured)	sqm	97.00	860.00	83420.00
103	Credit for taking away of existing Flush door with sliding blot, tower bolt etc under itme no : 42 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	each	48.00	-100.00	-4800.00
104	Credit for taking away of existing MS Windows and Ventilator including Glass as per direction of EIC under itme no : 41.43 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	kgs	4026.00	-5.00	-20130.00
105	Credit for taking away of existing Aluminium Door , Windows and Ventilator including Glass as per direction of EIC under itme no : 49 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	kgs	67.00	-50.00	-3350.00
106	Credit for taking away of existing False ceiling GI section as per direction of EIC under itme no : 49 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	kgs	204.00	-4.00	-816.00

Schedule-A

Name of work: Providing work station to accommodate HR and other departments at Begumpet Airport Hyderabad SH : Civil Works (Balance Work at the Risk & Cost of Main Work).

Sno	Description	Unit	Qty	Rate in Rupees	Amount in Rupees
107	Credit for taking away of existing plywood particle boards as per direction of EIC under itme no : 45 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	kgs ✓	2735.00 ✓	-3.00 ✓	-8205.00 ✓
108	Credit for taking away of existing dismantled wood work in scantlings as per direction of EIC under itme no : 45 (Note : This item will be operated as a credit item and the agency must quoted their rate accordingly. This amount quoted against this item will be treated as negative and overall total amount shall be adjusted accordingly to arrive at the final amount to establish lowest bidder)	kgs ✓	1094.00 ✓	-2.00 ✓	-2188.00 ✓
				Total	11403711.00 ✓
				Say	1,14,03,711.00 ✓

(Rupees One Crore Fourteen Lakhs Three Thousand Seven Hundred and Eleven Only)

J.GM(Engg.-C)
AAI,Begumpet Airport,
Hyderabad.