



भारतीय विमानपत्तनप्राधिकरण
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर
JABALPUR AIRPORT, JABALPUR-482005

संदर्भ सं.: AAI/JBP/ARMO/AMC-OPS/07/2021-22/1202/2

दिनांक : 17-12-2021

सेवा में,
To,

मेसर्स श्री शिव शक्ति इंटरप्राइजेज,
फ्लैट नंबर, F4/अंजनी अभिनन्दन अपार्टमेंट,
प्रगति नगर तिलहरी जबलपुर,
ई मेल : shrishivshakti14@gmail.com

M/s. Shri Shiv Shakti Enterprises,
Flat No/F4, Anjani Abhinandan Apartment,
Pragati Nagar Tilhari, Jabalpur (M. P.)
Mo. No. : 91-8109385344
E-mail : shrishivshakti14@gmail.com

Name of work - "Annual Maintenance Contract for Operational area i/c fire station & Tech. Block at Jabalpur Airport Jabalpur for the year of 2021-22".

संदर्भ - आपकी टेंडर दिनांक : 06/12/2021.

Ref. - Your Tender Dated : 06/12/2021.

महोदय / Sir,

- 1) ऊपर उल्लेखित कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा आमंत्रण प्रतिशत दर (-)30.00% (तीस प्रतिशत) शेड्यूल-अ {पार्ट-I (DSR 2018 Vol. - I & Vol. - II) एवं पार्ट-II} तथा कार्य के जस्टीफाइड प्रतिशत (107.53%) (एक सौ सात दशमलव पाँच तीन प्रतिशत) से (-)37.79% (सैंतीस दशमलव सात नौ प्रतिशत) नीचे स्वीकृत की जाती है। इस कार्य के लिए रु. 20,56,936.00 (रुपये बीस लाख छप्पन हजार नौ सौ छत्तीस मात्र) (जीएसटी रहित) का प्रावधान है।
➤ Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the percentage rates quoted by you at (-)30.00% (Thrifty Percent) Below on Schedule-A {Part-I (DSR 2018 Vol. - I & Vol. - II), & Part-II} & (-)37.79% (Thirty Seven Point Seven Nine Percent) Below on Justified percentage of 107.53% (One Hundred & Seven Point Five Three Percent). The Fund allocated against this work is Rs. 20,56,936.00 (Rupees Twenty Lacs Fifty Six Thousand Nine Hundred & Thirty Six Only) (Excluding GST).
- 2) वरि. प्रबंधक (अभि.-सि.), भाविप्रा, जबलपुर एयरपोर्ट, जबलपुर कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 01/01/2022 वरि. प्रबंधक (अभि.-सि.), जबलपुर एयरपोर्ट, जबलपुर के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100/- (रुपये सौ मात्र) के नोनज्युडिशियल स्टैम्पपेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा।



भारतीय विमानपत्तनप्राधिकरण
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर
JABALPUR AIRPORT, JABALPUR-482005

- **Sr. Manager, (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur shall be Engineer-in-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the **Sr. Manager (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur by **01/01/2022** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 100/- (Rupees One Hundred, Only)** and the cost of the stamp paper shall be borne by you.
- 3) कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि **रु. 2,05,694.00 (रु. दो लाख पांच हजार छः सौ चौरानवे एवं साठ पैसे मात्र)** जमा करवायें, अन्यथा निविदा के दस्तावेज की शर्त संख्या GCC Clause - 1(A) के पृष्ठ-17 के अनुसार इसे आपके रनिंग बिलों में से वसूल किया जायेगा।
- Please deposit amount of **Rs. 2,05,694.00 (Rupees Two Lacs Five Thousand Six Hundred Ninety Four & Sixty Paise Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same shall be deducted from your running bill as per Clause-1(A) of GCC page-17 of the contract document.
- 4) आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।
- You are requested to comply with the provision of Contract Labour (regulation and Abolition) Act of 1970 and Contract Labour (regulation and Abolition) Central Rules 1971 and minimum wages act and rules thereof of Central and State Governments.
- 5) आपको निर्देश दिया जाता है कि आप तुरंत कनिष्ठ कार्यपालक (अभि.-सि.), भाविप्रा, जबलपुर एयरपोर्ट, जबलपुर से मिलें वही आपको साइट सौंपने की व्यवस्था करेंगे।
- You are also directed to contact **Jr. Exe. (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur immediately who will arrange to hand over the site to you.
- 6) कृपया नोट कर लें कि काम करने का अनुमत समय **12 (बारह) महीने** हैं जो कि दिनांक **01/01/2022** से गिना जाएगा।
- Please note that the time allowed for carrying out the work shall be **12 (Twelve) months** and same shall be reckoned from **01/01/2022**.
- 7) उपरोक्त संदर्भित सभी पत्र इस डेके का भाग होंगे।
- The letters under reference shall form part of Agreement.

Asal
व.प. (सि.)



भारतीय विमानपत्तनप्राधिकरण
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर
JABALPUR AIRPORT, JABALPUR-482005

- 8) इस ठेके के संबंध में आगे कोई भी पत्राचार वरि. प्रबंधक (अभि.-सि.), भाविप्रा., जबलपुर एयरपोर्ट, जबलपुर के पते पर किया जाएगा।
- Any further correspondence in connection with this contract should normally be addressed to the Engineer-in-Charge, **Sr. Manager (Engg-Civil)**, AAI, Jabalpur Airport, Jabalpur.
- 9) यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।
- In case any discrepancy is found then English version will be taken as correct.
- 10) कृपया इसे स्वीकार करें एवं इसकी डुप्लिकेट प्रति स्विकृति के रूप में हस्ताक्षर कर वापस भेजे।
- Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

धन्यवाद / Thanking you

Encl. : Schedule -A

भवदीय / Yours Faithfully,

Asal
17/12/2021

वरि. प्रबंधक (अभि.-सि.)
Sr. Manager (Engg-Civil)
जबलपुर एयरपोर्ट, जबलपुर
Jabalpur Airport, Jabalpur

N.O.O.

1. The RED, WR, AAI Office, New Airport Colony, Vile Parle East, Mumbai - 99
2. The G.M. (Fin.), WR, AAI Office, New Airport Colony, Mumbai - 99
3. Jt. General Manager (Vigilance), AAI, WR, Porta Cabin, New Airport Colony, Mumbai - 99.
(Along with copy of Schedule of Quantity of tender document)
4. Commissioner of Income Tax, Kendriya Rajashva Bhavan, Naiper Town, Jabalpur, Madhya Pradesh 482001
5. The Assistant Labor Commissioner (Central), Block-10 Civic Centre, Marhatal, Jabalpur.
6. The Commercial Tax Officer, Ghanta Ghar Road, Jabalpur.

INTERNAL

1. The G.M. (Engg.-Pro.), AAI, Jabalpur Airport, Jabalpur.
2. The Airport Director, AAI, Jabalpur Airport, Jabalpur
3. The Jt. General Manager (Engg.-Civil), AAI, Jabalpur Airport, Jabalpur.
4. The Jt. General Manager (Engg.-Elect), AAI, Jabalpur Airport, Jabalpur.
5. The Manager (Fin.), AAI, Jabalpur Airport, Jabalpur.
6. The Jr. Exe. (E-C), AAI, Jabalpur Airport, Jabalpur (With instruction to hand over the site)

SCHEDULE - "A"

Name of work : "Annual Maintenance Contract for Operational area i/c fire station & Tech. Block at Jabalpur Airport Jabalpur for the year of 2021-22"

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
(I)	Schedule "A" (Part-I) (As per DSR - 2018 with upto date correction slip) All the sub head of DSR 2018 from Sl. No 1 to 26 (DSR - Page no. 01 to 428) (Vol- I & II)	Ref DSR 2018	
(II)	Schedule "A" (Part-II) Additional Miscellaneous Items (Rate derived at par with DSR - 2018)		
	<u>ADDITIONAL MISCELLANEOUS ITEMS</u>		
1	Supplying unskilled labour for day to day maintenance jobs / shifting of office from one location to another location etc. i/c T&P as and when required as per satisfaction of Engineer-in-charge. (Rate mentioned shall be fixed. Above/below % age Quoted by contractor shall not be applicable on this item).	Per Person per day	641.00
2	Supply of Mali for day to day maintenance work i/c T&P as and when required as per satisfaction of Engineer-in-charge (Rate mentioned shall be fixed. Above/below % age quoted by contractor shall not be applicable on this item).	Per Person per day	724.00
3	Providing of High skilled worker for day to day maintenance work i/c T&P as and when required as per satisfaction of Engineer-in-charge. (Rate mentioned shall be fixed. Above/below % age Quoted by contractor shall not be applicable on this item)	Per Person per day	933.00

Asal

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
4	Providing of skilled worker for day to day maintenance work i/c T&P as and when required as per satisfaction of Engineer-in-charge. (Rate mentioned shall be fixed. Above/below % age Quoted by contractor shall not be applicable on this item)	Per Person per day	849.00
5	Providing steno cum typist/computer operator for assisting Maintenance Engineers/Managers in preparation of payment bills, maintenance of office records & files etc. preparations of progress report, all types of computer/clerical works attend other related works/duties or vehicle driver as directed by E.I.C. (Rate mentioned shall be fixed. Above/below % age quoted by contractor shall not be applicable on this item).	Per Person per day	849.00
6	Cleaning of choked/blocked rain water pipe, soil waste pipe vent pipe, manhole, sewerage pipe, gully trap, EWC, wash basin kitchen sink, bottle trap, house drain storm water chain i/c of any diameter and size i/c removal of mulba all complete as directed by Engineer-In-Charge.		
6 (a)	Rain water pipe/soil waste and vent pipes	meter	15.80
6 (b)	Manhole i/c connected sewerage pipes upto the next manhole.	each	622.93
6 (c)	Storm water Drain (Road side)	meter	26.80
6 (d)	Storm water Drain (Runway side)	meter	27.02
6 (e)	Septic Tank Surface area upto 7.5 Sqm.	each	4021.23
6 (f)	Septic Tank Surface area 7.5 Sqm to 15.00 sqm	Each	6303.49

Asah

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
7	Cleaning of GI/Msonry/Sintex PVC over head water tank i/c removal of mulba as directed by engineer in charge and disinfecting the tank with bleaching powder.		
7 (a)	For 5000 LITRE Tank	Each	786.57
7 (b)	For 10,000 LITRE Tank	Each	1496.78
8	Supplying and placing in position to sand jute bags (with fine sand) in all respect as per direction of Engineer-in-charge.		
8 a)	Jute bags and sand supplied by agency	Each	103.58
8 b)	New Jute bags supplied by agency & used existing sand after dry & seived.	Each	37.09
8 c)	Replacing of exting Jute bages with new jute bag.	Each	25.09
9	Carriage of malba from inside AAI premises to out side AAI person by mechanical means including loading up and unloading etc. as desired by the Engineer-In-Charge complete in trucks loads. (Measuring Upto 3 Cum.)	Per Trip	1121.06
10	Replacement of rubber beading in existing aluminium door and windows complete upto the satisfaction of Engineer-in-charge.	Metre	117.82
11	Providing and fixing acrylic sheet of white or any other colour on existing board,doors & windows etc. as per satisfaction of Engineer-in-Charge with necessary screws.		
11 (a)	3 mm thick acrylic sheet	Sqm	1187.50
11 (b)	4 mm thick acrylic sheet	Sqm	1491.87
12	Supplying and fixing in position vertical/horizontal blifds as per approved make & design by the Engineer-in-Charge.		
12 (a)	Vertical venation blinds 100 mm wide	Mtr	1052.33
12 (b)	Roller blinds	Mtr	1602.38

Asals

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
13	Testing of portability of drinking water as per the IS standard and as per water supply authority i/c depositing sealed water sample to the laboratory and providing the test report of sample to Engineer in Charge.	Each	3218.29
14	Providing JCB for day to day maintenance work on hourly basis as and when required i/c the cost of driver, diesel and other maintenance for leveling dressing etc. as per direction of Engineer-in-charge.(Note:- Payment shall be done only for actual working on site.No payment for to and fro movement.)	Per Hrs	1363.68
15	Providing Road Rollar -8 to 10 tonne for day to day maintenance work on daily basis minimum eight working hours per day i/c the cost of driver, diesel and other maintenance for compaction of undulated/loose all type of soil of playground/any ground surface at AAI premises etc. as per direction of Engineer-in-charge.	Per Hrs	1500.05
16	Half brick masonry with local available size bricks of class designation 35 in foundations and plinth in: Cement mortar 1:4 (1 Cement : 4 coarse sand)	Sqm	652.95
17	Half brick masonry with local available size brick of class designation 35 in superstructure above plinth level upto floor V level Cement mortar 1:4 (1 Cement : 4 coarse sand)	Sqm	726.45
18	Brick work with local available size bricks of class designation 35 in foundation and plinth in ;	Cum	4878.63
19	Brick work with local available size bricks of class designation 35 in superstructure above plinth level upto floor V level in all shapes and sizes in ;	cum	5304.00
20	Providing and fixing 15mm nominal bore C.P. Pressmatic Pillar cock of approved quality as per satisfaction of Engineer-in-charge. (Parryware make Code no. G2013A1). 15mm nominal bore	Each	2236.44

Amal

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
21	Providing and fixing stainless steel grating for Nahani trap with white cement and matching colour of approved quality, all complete as per direction of Engineer-in-Charge.		
21 (a)	125 mm nominal size square, 100 mm dia of inner round grating.	Each	191.31
21 (b)	100 mm nominal size square, 100mm dia inner round grating.	Each	109.09
21 (c)	100mm dia hinge round grating.	Each	130.91
22	Removing and re-fixing of 60/80mm thick factory made cement concrete interlocking paver block of any grade and shap material as available at site within AAI premises laid over removed and relaid sand/churi bed as per direction & satisfaction of Engineer-In-Charge. in all respects.	sqm	2534.18
23	Providing & fixing fibre glass reinforced plastic sheet (FRP Sheet) in shed, or Morcha 1mm thick of required colour as per satisfaction of Engineer-in-charge.	Sqm	921.85
24	Tightening of barbed wire on G.I. Wire fencing including fencing of broken hooks complete.	Metre	4.62
25	Providing and fixing liquid soap container of approved make of S.S. container complete.		
25 (a)	S.S. Container (simple 100 ml capacity)	Each	676.39
25 (b)	PVC Container	Each	294.56
26	Providing and fixing toughened glass sheet paneling/glazing with U shaped neoprene moulded rubber packing including silicon sealant filling with matching colour all along the glass edges (area of opening will be measured for payment). 12mm thick glass plain (toughened)	sqm	2703.63

Asal

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
27	Providing and fixing aluminium composite panel (ACP) sheet of 4mm thick (as per approved make). The rate shall include necessary provision for making opening / cutting wherever required.(Item includes all accessories, hardware, scaffolding, provision for making opening, standard size and make all complete as per direction of Engineer-in-charge.	Sqm	2954.46
28	Providing and fixing 8mm table glass with edge moulding and polishing as per satisfaction of Engineer-in-charge. 8mm thick float glass	Sqm	1546.21
29	Providing and fixing health faucet ISI mark (Hand shower) with 1.5mtr long flexible tube with wall hook of approved quality as per satisfaction of Engineer-in-charge. (Parryware make Code no. T9875A1).	Each	1909.70
30	Providing and fixing C.P. brass ISI mark urinal spreader inner or outer as per direction and satisfaction of Engineer-in-charge.	Each	349.10
31	Providing & fixing clear polycarbonate sheet on existing aluminium/steel/wooden frame work with necessary screws i/c removal of broken glass at the height of approximate 22 mtr. Complet as per Engineer-in-Charge		
31 (a)	2mm thick sheet	Sqm	2023.75
31 (b)	6mm thick sheet	Sqm	1113.65
32	Supply & Installation of optically clear, transparent, high impact resistant Polyester Sun Control Film (Reflective Shades Film) of approved colour & shade with minimum thickness of 50 micron of 3M or equivalent approved make. Applied material shall be installed bubble-free with self-adhesive film on a smooth, dust free glass panes at all levels including cleaning of glass, necessary cutting at joints, fittings, scaffolding etc. all complete as per instruction and direction of Engineering In Charge.The rate inclusive removal of existing sun control film where ever required.	Sqm	2457.36

Asah

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
33	Providing and fixing commercial ply of ISI mark in partition etc. as well as making office racks of various size & shape having arrangement for sliding drawers and openable shutters (Lamination & hinges, sliding channels, handles shall be paid for seperately):		
33 (a)	6 mm thick ply wood.	sqm	516.05
33 (b)	12mm thick ply wood	sqm	1032.68
33 (c)	18mm thick ply wood	Sqm	1278.69
34	Providing and fixing of PVC cover of over head tank any capacity as per direction of Engineer-in-charge.		
34 (a)	45 cm dia	Each	344.96
34 (b)	60 cm dia	Each	432.23
35	Providing and pasting of 3M rectro reflective sheet with computerized letter cutting and pasting in position over the another sheet and fixing on the existing sign board / Aluminium for making sign boards/instructions board/operational signes boards etc. with approved colour and patterns with any No. and size of letters complete as per direction of Engineer-In-Charge.	Per sqm	4553.18
36	Providing and pasting of 3M rectro reflective sheet with computerized letter cutting and pasting in position over the another sheet with 2mm thick aluminium sheet and fixing on the existing frame for making sign boards/instructions board/operational signes boards etc. with approved colour and patterns with any No. and size of letters complete as per direction of Engineer-In-Charge.	Per sqm	5718.75

Ash

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
37	Providing and pasting of 3M rectro reflective sheet with computerized Printing and pasting in position over the another sheet with 2mm thick aluminium sheet and fixing on the existing frame for making sign boards/instructions board/operational signes boards etc. with approved colour and patterns with any No. and size of letters complete as per direction of Engineer-In-Charge.	Per sqm	3194.95
38	Providing & fixing 10 mm thick clear toughened glass shutter for automatic bi-parting sliding doors of sizes as per site requirement complete as per direction of Engineer-in-charge. (Maximum size of the lenght and width of the pannel shall be measured for payment).	sqm	1803.01
39	Providing & filling silicon sealant of grade 789 in gap of glazing work wherever required complete as per direction of Engineer-in-charge. (a) Avrage group size 10 x 15	Rmt.	212.73
40	Deduct for taking away of C.P. brass/Brass bib cock, stop cock, long body bib cock, long nose bib cock, angle valve, ball valve, close hole basin mixer, C.P. waste in basin/sink and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (This item rate will be fixed, above or below percentage quoted by the agency will not be applicable.)	Kg	232.49

Asah

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
41	Deduct for taking away of SCI pipe fitting, centrifugal cast (spun)/sand cast iron pipes and fittings, C.I. flushing cistern, G.I. pipes and fittings, steel doors, window, ventilators, grill, round or square bars etc. and the like item received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (This item rate will be fixed, above or below percentage quoted by the agency will not be applicable.)	Kg	22.32
42	Deduct for taking away of PVC connections, PVC flushing cistern with fittings, PVC over head tank, PVC bib cock, stop cock, ball valve, loft tank etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (This item rate will be fixed, above or below percentage quoted by the agency will not be applicable.)	kg	15.81
43	Deduct for taking away of aluminium butt hinges, sliding door bolts, tower bolts, pull boly lock, handle, door stopper, casement stay, tee chanals, plates, frames, shutters, partition, tubular sections etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. (This item rate will be fixed, above or below percentage quoted by the agency will not be applicable.)	kg	81.84

Asal

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
44	Deduct for taking away of steel work in frames, shutters, trusses, channels, beams, Tee, angles, bolts, washers etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.(This item rate will be fixed, above or below percentage quoted by the agency will not be applicable.)	kg	18.60
45	Supply & Installation of optically clear, transparent, high impact resistant Polyester Safety Film of approved colour & shade with minimum thickness of 175 micron of 3M or equivalent approved make. Applied material shall be installed bubble-free with self-adhesive film on a smooth, dust free glass panes at all levels including cleaning of glass, necessary cutting at joints, fittings, scaffolding etc. all complete as per instruction and direction of Engineering In Charge. The rate inclusive removal of existing sun control film where ever required.	Per sqm	388.65
46	Providing and fixing Frosted film (3M or equivalent approved make), on glass panes after thoroughly cleaning of existing surface, the rate inclusive removal of existing film where ever required.	Per sqm	226.51
47	Providing of Highly skilled licensed surveyor (Min. qualification- Diploma) for surveying work at Jabalpur airport premises as and when required as per satisfaction of Engineer-in-charge. The rate includes complete processing of surveyed data and preparation of site plan in autocad software as well as visiting charges to the site. Surveyor will bring his own calibrated Total station equipment and other required equipment and nothing shall be paid extra for it.	Per sqm	8182.10

Asah

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
48	Supply of 6 Volt Lithium Battery of Duracell brand having model no. FBA_DURDL223ABPLDL223ABPK for Jaquar Aquisense Sensor Concealed type Flushing valve for Urinal complete at site as per the direction of Engineer-in-charge.	Each	1443.76
49	Providing & Fixing of Automatic Soap Dispensers, capacity - 0.8L of Jaquar make model SDR-BCH-DJ0160AS complete at site as per the direction of Engineer-in-charge.	Each	7004.91
50	Providing & Fixing of Sensotronic Sensor Faucet for Wash Basin of Jaquar make model SNR-CHR-51027 complete at site as per the direction of Engineer-in-charge.	Each	10854.93
51	Providing & Fixing of Wall Hung Cistern with drainage L-Bend pipe with Gasket & Installation kit (suitable for EWC) of Jaquar make model WHC-WHT-184L complete at site as per the direction of Engineer-in-charge.	Each	1994.08
52	Providing & Fixing of Wall Hung WC with UF soft close slim seat cover,Hinges,Assessories set,Size - 360X570X360 mm of Jaquar make model ARS-WHT-39951UFMS complete at site as per the direction of Engineer-in-charge.	Each	19156.38
53	Providing & Fixing of Table Top Basin,Size - 515X365X120 mm of Jaquar make model FLS-WHT-5931 complete at site as per the direction of Engineer-in-charge.	Each	8,468.44
54	Providing & Fixing of Urinal with fixing accessories, Size - 370X315X620 mm of Jaquar make model URS-WHT-13253O complete at site as per the direction of Engineer-in-charge.	Each	9012.97
55	Providing & Fixing of Aquisense Sensor Concealed type Flushing valve for Urinal complete set with installation box with control cock of Jaquar make model SNR-STL-51077 complete at site as per the direction of Engineer-in-charge.	Each	14689.98

Asals

Sr. No.	DESCRIPTION OF ITEMS	UNIT	Rate
56	Providing & Fixing of Single Piece Slim Concealed Cistern with floor mounting frame, installation kit and "S-Type" drain pipe connection set for wall hung WC (without flush control plate) of Jaquar make model JCS-WHT-2400FC complete at site as per the direction of Engineer-in-charge.	Each	12475.69
57	Providing & Fixing of Flushing Control Plate Kubic of Jaquar make model JCS-WHT-352415 complete at site as per the direction of Engineer-in-charge.	Each	1944.26
58	Providing & Fixing of Hand Shower (Health Faucet) of Jaquar make model ALD-CHR-573 complete at site as per the direction of Engineer-in-charge.	Each	1791.33
59	Providing & Fixing of Bottle Trap of Jaquar make model ALD-CHR-769L 300x190 complete at site as per the direction of Engineer-in-charge.	Each	1951.75
60	Providing & Fixing of 2 Way Bib Cock with wall flange of Jaquar make model KUP-CHR-35041PM complete at site as per the direction of Engineer-in-charge.	Each	2673.63
61	Providing & Fixing of Grab Bar 300mm Long with of Jaquar make model AKP-35701P complete at site as per the direction of Engineer-in-charge.	Each	1871.54
62	Providing and fixing 15mm nominal bore C.P. Pressmatic Pillar cock of approved quality as per satisfaction of Engineer-in-charge. (Jaquar make Code no. PRS-CHR-031). 15mm nominal bore	Each	2459.74

NOTE :- The payment of Items shall be regulated as below (except for schedule A Part II Item no. 01 to 05)

Rate of Item as per Schedule A = X

Rate to be considered for payment = $(X / 1.1405) \times (100 \pm \frac{\text{Quoted Percentage Rate}}{100})$

Asal
2.5/100