



दिल्ली मेट्रो रेल कॉर्पोरेशन लि० DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का संयुक्त उपक्रम)

(A JOINT VENTURE OF GOVERNMENT OF INDIA AND GOVT. OF DELHI)

CIN: U74899 DL 1995 GOI 068150

No. DMRC/PD/IT Park/Civil/

Date 06.12.2021

Letter Of Acceptance

To,

M/s Zuri Construction

B-35, Johri Farm, Noor Nagar,

Extn. Okhla,

Delhi-110025

Mobile No. 9650307966

Sub: Contract no: (PD-28) Replacement of false ceiling and cracked façade glass including repair/rectification of water seepage from existing façade window at it park, shastri park

Ref: (i) Your online e-tender submission on date 27.09.2021.

(ii) Post bid clarifications asked on e-portal dated 14.10.2021.

(iii) Your reply to post bid clarifications submitted online on 25.10.2021.

(iv) Online opening of the financial bids on 08.11.2021

Dear Sir,

1. With reference to above, Letter of Acceptance (LOA) is hereby issued to you for the above mentioned work at the total cost of INR 31,19,287.83/- (Rupees Thirty one Lakh Nineteen Thousand Two Hundred Eighty seven and Eighty three Paise only) inclusive of all central/ state/local taxes/ GST, duties, levies, cess and all other incidental charges required to fulfil the tender conditions including statutory deduction.
2. The total period of contract is Three months from the date of commencement of work as per NIT clause 1.1.2.
3. The period of commencement of work is within Seven (7) days from the date of issue of "Letter of Acceptance" (LOA) or as per the instructions of Engineer-in-charge as per Appendix-1 of FOT.
4. The payment shall be made on the basis of measurement of the actual work done by the contractor.
5. Necessary deductions as per statutory requirement shall be made by DMRC at the time of payment.
6. The contractor shall adhere to guidelines of Delhi Pollution Control Committee (DPCC) to curtail pollution and follow all the statutory laws issued by Govt. of Delhi.
7. BOQ of works is attached as Annexure-A.
8. You shall ensure full compliance with Tax Laws and labour laws of India with regard to this contract and shall be solely responsible for the same. You shall keep the employer fully

25, अशोका रोड़, (पटेल चौक मेट्रो स्टेशन के पास) नई दिल्ली-110001

25, ASHOKA ROAD, (NEAR PATEL CHOWK METRO STATION) New Delhi-110001

Website : www.delhimetrorail.com


indemnified against your liability of tax, interest, penalty etc. respect thereof, which may arise.

9. DGM/E/PD of this organization will be the Engineer for this contract.
10. You are requested to contact this office immediately for further necessary action in this matter and to start the work.
11. All the work shall be executed in accordance with the specifications stipulated in Tender.
12. This Letter of Acceptance is sent herewith to you in duplicate. You are requested to return one copy of it duly signed by you on all pages indicating "Unconditional Acceptance" thereof so as to reach the undersigned within one week of the receipt of this letter (As per Clause F3 of Instructions to Tenderers (ITT)).
13. It may please be noted that until a formal agreement is executed, this letter will constitute a binding Contract between you and DMRC Ltd. Please take necessary action as required vide Clause Nos. F4 and F5 of Instructions to Tenderers (ITT), regarding signing of agreement and submission of performance security respectively.

Thanking you,

Encls: One copy of this letter in Duplicate

Yours faithfully,


(Rajesh Ranjan)

Dy. General Manager/Elect./PD

For and on the behalf of Delhi Metro Rail Corporation Ltd.

CC: CGM/PD for kind information please

DELHI METRO RAIL CORPORATION

Bill of Quantity

Name of Work: (PD-28) Replacement of false ceiling and cracked façade glass including repair/rectification of water seepage from existing façade window at it park, shastrri park

S. no.	Item No.	Description	Unit	Quantity	Rate (INR)	Amount (INR)
Schedule A (DSR 2018 items)						
1	DSR 2018 14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	SQM	4322	257.95	1114859.90
2	DSR 2018 21.10	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side, having 12 mm air gap, including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. as per specifications, drawings and direction of Engineer-in-charge complete.	SQM	21	3905.35	82012.35
Total Schedule A						1196872.25
Quoted Rate @25.00% less						299218.06
Grand Total Schedule A						897654.19
Schedule B (NDSR items)						
3	NDSR 1	Providing and fixing 25X200 baffle ceiling (25 mm width & 200 mm height) system comprising of closed box shaped profiles. Metal baffles shall be made out of 0.7-0.9mm thick electro galvanized steel material in lengths of upto 2400mm. The coil should be stove enamelled on a continuous application for pre-treatment, the coil to go through conversion coating, priming and finish coat ensuring superior adhesion, high corrosion resistance and good inside surface to have a primer of 5 microns and a coat of natural color of 5 microns, exposed surface to have a primer of 5 micron, binder of 5 micron and top coat of approved colour of 15 micron. Baffle ceiling shall mounted on slotted galvanized steel grid profile of minimum 2mm thickness means of minimum 6mm dia threaded suspended and supported by means of minimum 6mm dia threaded suspendors at a distance of 150mm from the edge and 1200c/c maximum spacing. baffle fixing brackets shall be used to keep the ceiling in correct place for the levelling purpose. metal baffles shall be coiled coated in desired color so that it resembles DMRC logo visible from ground, baffle ceiling system shall be installed in compliances with manufacturer's technical installation brochure and manual, all accessories like end caps column rings, scaffolding, any substructure etc. are included wherever required.	SQM	805	3064.94	2467274.49
4	NDSR 2	Providing and fixing EPDM rubber Beading (as per site requirement) including sealing of all joints as per instructions of Engineer-in-charge				
		a) Main Beading	RMT	2000	70.80	141600.00
		b) Packing Beading	RMT	2000	47.20	94400.00
5	NDSR 3	Providing and filling of PU foam and Capping with ACP Sheet with flashings if required at locations as per instructions of Engineer-in-charge	RMT	200	1354.00	270800.00
Total Schedule B						2974074.49
Quoted Rate @25.30% less						752440.85
Grand Total Schedule B						2221633.64
Grand Total of Schedule A + B						3119287.83

Signature Not Verified

Digitally signed by Gaurav Gupta
Date: 2021.12.07 11:42:40 IST
Location: eProcure-EPROC