



दिल्ली मेट्रो रेल कॉर्पोरेशन लि० DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का संयुक्त उपक्रम)

(A JOINT VENTURE OF GOVERNMENT OF INDIA AND GOVT. OF DELHI)

No.DMRC/Tender(O&M)/OEW-TR-03/2021

Dated: 02.12.2021

LETTER OF ACCEPTANCE

M/s JK GUPTA & CO.
D-22/2, Mohalla Madhuban,
North Ghonda,
Delhi-110053

Sub: Contract: OEW-TR-03: "Supply, Installation, Testing and commissioning of Return Conductor Marshalling box at various RSS of DMRC Ltd".

Ref:(i) Opening of Technical bids online on 02.11.2021

(ii) Opening of Financial bids online on 23.11.2021.

(iii) Contract No: 2021_DMRC_651892_1

Dear Sir,

1. With reference to above, Letter of Acceptance (LOA) is hereby issued to you for the above mentioned work at total cost of **INR 24,87,432.06 (Rupees Twenty Four Lakh Eighty Seven Thousand Four Hundred & Thirty Two and Paise Six Only)** including all taxes, duties, octroi, royalties etc.
2. This 'Letter of Acceptance' is sent herewith to you in duplicate. You are required to return one copy of it duly signed by you on all pages indicating "**Unconditional Acceptance**" thereof so as to reach the undersigned within seven days of the receipt of this letter.
3. This "Letter of Acceptance" shall be treated as "Notice to Proceed" as defined in clause 8.1 of GCC and the completion period for this work is **06 (Months)** from the stipulated date of commencement of work.
4. You shall ensure full compliance with Tax Laws of India with regard to this contract and shall be solely responsible for the same. You shall keep the employer fully indemnified against your liability of tax, interest, penalty etc. in respect thereof which may arise.
5. JGM/Traction/L-6&E of this organization will be the Engineer In-charge for this contract.

Page 1 of 2 (OEW-TR-03)

CHANDRAKANT SHRIVASTAVA
JGM/Tr.-6&E
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

(मेट्रो भवन, फायर ब्रिगेड लेन, बाराखम्बा रोड, नई दिल्ली-110001)

Metro Bhawan, Fire Brigade Lane, Barakhamba Road, New Delhi-110001

6. You are requested to contact the JGM/Traction/L-6&E immediately for further necessary action in this matter, and date of commencement of work shall be from 03.12.2021 or as per the instructions of Engineer In-charge.
7. All the works shall be executed in accordance with the specifications stipulated in Tender.
8. It may please be noted that until a formal agreement is executed, this letter will constitute a binding Contract between you and DMRC. Please take necessary action as required vide Clause Nos. F4 and F5 of Instructions to Tenderers (ITT) regarding signing of agreement within 45 days from the issue of Letter of Acceptance and submission of performance security within 30 days from the date of receipt of LOA. Further, it is pertinent to mention that delay in submission of performance security shall attract penal interest/lead to termination as per clause 4.2 of GCC.
9. Before commencing the work contractor is required to co-ordinate with Shri. Anil Kumar Parashar, AM/TR-6 Mob No- 995822690.
10. You are instructed to register yourself on vendor payment portal on receiving the LOA. The instructions to do the same are provided in Annexure-A.

Thanking you,

Yours sincerely,
For Delhi Metro Rail Corporation Limited


(Chandrakant Shrivastava)
JGM/TR-6&E (O&M)

Encl: -1-One Copy of this letter in Duplicate
2-Annexure-A
3- BOQ

Copy to GM/Traction: for kind information please.

CHANDRAKANT SHRIVASTAVA
JGM/Tr.-6&E
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

BOQ

Work: "Supply, Installation, testing and Commissioning of Return Conductor Marshalling box at various RSS of DMRC Ltd"					
S. No.	Description of Work	Unit	Quantity	Unit Rate (in INR) inclusive of All Taxes/GST	Total Amount (in INR) inclusive of All Taxes/GST
1	COPPER STRIP FOR RCMB BOX: Supply and installation of Copper Strip busbar for RCMB box of 99.90 % pure electrolytic copper, Size 100mmX 10mm(width x thickness).Length of copper strips is of different sizes as per requirement(Depends upon type of box).Same fixed inside RCMB box in rectangular form using brass nut bolts. Three different types of boxes designed as per site requirement and sizes of copper strips to be cut & fix accordingly are mentioned below. (i)TYPE-A:Rectangular busbar(1.7 m x 0.5 m) Total length=4.4mtr (5 nos.) (ii)TYPE-B:Rectangular busbar(2.3 m x 0.5 m) Total length=5.6mtr (5 nos.)	Mtr	50	17051	852550
2	RCMB BOX of Stainless steel: Supply and installation of a Marshaling box made of Stainless steel. As per under mentioned specification:-Protection IP-55,SS-304 grade of 2.0 mm Stainless steel enclosure ,totally enclosed, multiple leaf door, bottom entry, dust and vermin proof. The marshaling box having stainless steel cover. Three different types of boxes to be installed as per site requirement are tabulated below.				
2(i)	TYPE-A:2000mmx600mmx900mm(LxBxH) up to 19 cables with 3 leaf doors from front side	Nos.	5	49560	247800
2(ii)	TYPE-B:2600mmx600mmx900mm(LxBxH) for 20-24 cables with 4 leaf doors from front side	Nos.	5	58542.75	292713.75
3	POST INSULATORS FOR COPPER STRIP SUPPORT: Supply and installation of Post Insulator of synthetic rubber for rated voltage 3.3 kV (Creepage- 300mm) for supporting of installed copper strips of RCMB.6 nos. to be used for Type -A installation,8 nos. for type-B installation.	Nos.	70	1298	90860

CHANDRAKANT SHRIVAS
JGM/Tr.-6&E
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001


2-12-24

4	GI strips for earthing of RCMB SS BOX : Double earthing of RCMB box with its stand to be done using 50x5 mm GI strip(Where RSS earth mesh is MS type) .Welding work to be done at earth mesh end using GI L-strip(making a junction for proper strengthening).At box end welding and bolting to be done. (10 nos.X22 mtr each)	Mtr.	220	531	116820
5	EARTHING OF RCMB BUSBAR-(GI strip for earthing of RCMB busbar, use of bimetallic strip and required welding work): (i) 75x5mm GI strip to be used to connect installed copper strips of RCMB to RSS earth mesh & bimetallic strip to be used at GI & copper jointing spot. (ii) GI strip used for earthing to be joined with RSS earth mesh by welding and jointing point to be made proper by connecting 01 nos of L-strips at junction for proper strengthening. (bi directional welding on RSS earth mesh).	Mtr.	220	955.8	210276
6	HEAT SHRINK SLEEVE FOR TERMINATIONS OF RC and at earthing junction where welding and brazing to be done: Heat shrinkable sleeve at terminations of 240 sq.mm, 3.3kV return conductor to be provided. Same also to be provided at welding and brazing joints at RSS earth mesh end. A Heat shrink sleeve may be provided on RC if it is found damage at any location after exposong of burried rail. (10 nos. X 9 mtr each)	Mtr.	90	1424.85	128236.5
7	CANOPY: 6 nos. of SS studs(threaded) to be fixed on roof of RCMB box. Sizes of 3 nos. of front studs are 100mm height and 15 mm dia and 3 nos. of back side studs are 150mm height and 15 mm dia. A Sheet of SS of 3 mm thickness, grade SS-304 to be fixed on top of these studs in inclined form(Front side inclination).Sizes of different sheets are tabulated below.				
7(i)	TYPE-A:Size of SS sheet = (LxBxT)=2500x1100x2 mm (T for Thickness)	Nos.	5	47023	235115
7(ii)	TYPE-B:Size of SS sheet = (LxBxT)=3100x1100x2 mm	Nos.	5	59000	295000
8	Supply & Installation of 240 sq mm copper thimbles as per site requirement. (5 nos.X19 cables + 5 nosX24 cables)	Nos.	215	590	126850
9	Supply & Installation brass nut bolts of M-12 size for fixing of 240 sq mm cable with RCMB copper strip and inter connection of RCMB copper busbar. Other size nut bolts of SS or brass may be provided as per site requirement. (5nosX45+5 nosX55)	Nos.	500	271.4	135700

10	Supply and erection of stand of Mild Steel for installing RCMB box. Hollow tubular square shape vertical bars of size 80 mmx80 mmx 5 mm(width & thickness) having circular cross section(placed inside concrete material) inside at bottom portion having dia 100 mm to be used as pillar.100x100 x6mm MS angle to be used as horizontal bar to place RCMB box.				
10(i)	Size of MS stand for TYPE-A box: 2050mmx650mmx900mm(lxbxh)	Nos.	5	22774	113870
10(ii)	Size of MS stand for TYPE-B box:size:2650mmx650mmx900mm(lxbxh)		5	28880.5	144402.5
11	CONCRETE FOUNDATION: Suitable concrete foundation for iron stand of RCMB.Size of concrete foundation 300x 300 x 400 mm(lxbxh).	Nos.	40	7670	306800
12	TAG: Tagging and marking of all RC cables.(SS tag size25x80mmX 2mm thickness)	Nos.	220	354	77880
13	NAME PLATE: Name plate of RCMB box using retro reflective metallic board of SS .(size 200x 300 mmX 2mm thickness)	Nos.	10	1180	11800
14	DIGGING WORK: Labor charges for digging of pit for removing the existing buried Rail and refilling after cutting of return conductor. Proper dressing of RC may be done before refilling work.	Cu mtr.	370	590	218300
	Grand Total including taxes				₹ 36,04,973.75
	% quoted by bidder against Schedule-A			Less	31.00%
	Total amount of Schedule-A				₹ 24,87,432.06


2-12-24

CHANDRAKANT SHRIVAS
JGM/Tr.-6&E
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

Annexure A


In order to facilitate contract management and ensure timely processing of requests made by the vendor, DMRC has implemented the Vendor Payment Portal that will allow the vendor to register themselves, raise payment requests, modify vendor information and request variation in contract. The portal will provide updates to the vendor and DMRC of the current status of the process and help to ensure timely action.

To register on the portal follow these steps

1. Go to : <https://vpp.dmrc.org>
2. Click on vendor sign up button.
3. Enter the required contact information and contract details.
4. The information about nodal officer may be obtained from engineer-in-charge.
5. Click on submit button.
6. You will get the message "Your request has been sent to the nodal officer for verification. Once verified, you will receive notification via email and sms."

In case of any queries, click the help button on the landing page:

1. Queries can be sent on the following email id : vpp.support@dmrc.org
2. User manual is available by clicking the button: "Download vendor user manual" on the help page.



CHANDRAKANT SHRIVASTAVA
JGM/Tr.-6&E
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

Signature Not Verified

Digitally signed by OM TIWARI
Date: 2021.12.02 15:06:03 IST
Location: eProcure-EPROC