

**COMPARATIVE STATEMENT FOR FINANCE BIDS FOR THE WORK OF RAISING OF LOW LYING PORTION OF APPROACH ROAD TO IWT
TERMINAL AT KOTTAPPURAM IN NW-3.**

Sl. No.	Description	Unit	Quantity	As per Estimate		Rate Quoted by Sri. Joby Johny		Rate Quoted by Sri. Basil Mathew	
				Rate	Amount	Rate	Amount	Rate	Amount
1	Dewatering of stagnated water from the road by deploying 5 HP motor with pump set before starting the work and during the execution time as per requirement / directions of E-I-C including hire charges of motor, fuel, bata for operator etc., complete.	No.	1.00	15150.00	15150.00	15440.00	15440.00	15540.00	15540.00
2	Cleaning of the surface of existing road by removing sand, dirt, dust and waste materials accumulated during stagnation of water including removal algae, shells etc., from the top surface retaining walls and disposal of the same as and where directed by the Engineer in Charge.	LS	LS	15150.00	15150.00	15430.00	15430.00	15530.00	15530.00
3	Providing and laying quarry waste / concretewaste of average 50cm thickness for raising the level of subway of the road as per directions of E-I-C. The rate shall include cost of all materials, transportation, ramming, consolidation with 8 T road-roller in stages to proper grade and camber without causing any damage to side walls, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density etc., complete.	M ³	91.00	2424.00	220584.00	2440.00	222040.00	2543.00	231413.00
4	Providing and laying GSB of average 30cm thickness for raising the level of subway of the road as per directions of E-I-C. The rate shall include cost of all materials, transportation, ramming, consolidation with 8 T road-roller in stages to proper grade and camber without causing any damage to side walls, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density etc., complete.	M ³	49.35	3484.50	171960.08	3460.00	170751.00	3542.00	174797.70

Handwritten signature and date: 19.02.2021

Handwritten signature and date: 19/2/21

Sl. No.	Description	Unit	Quantity	As per Estimate		Rate Quoted by Sri. Joby Johny		Rate Quoted by Sri. Basil Mathew	
				Rate	Amount	Rate	Amount	Rate	Amount
5	Procuring and applying of two or more coats synthetic enamel paint of good quality to give an even shade to the inner retaining walls as directed by the Engineer, including cost of all material, applying of priming coat, labour etc....,	M ²	144.00	235.03	33844.50	228.00	32832.00	260.00	37440.00
Total estimated cost of repair works: Rs.					456688.58		456493.00		474720.70

(L-1) (L-2)
Overall Difference: -0.04 % (+) 3.95 %

Recommendation:

The FINANCIAL BID of the Technically Qualified bidder were opened on the scheduled time at 11.00 AM on 19.02.2021. On evaluation of the Finance Bid, it is noted that the bidder Sri. Joby Johny, JJ Construction, Pallikkara, Ernakulam has quoted an amount of Rs. 4,56,493/- (excluding GST @ 12%) which is (-) 0.04 % below estimated cost of Rs. 4,56,687/-. As per "Revised Delegation of Powers" the field Director are empowered to accept the lowest tender and the work. Hence, TEC recommends to accept the same and award the work to Sri. Joby Johny, JJ Construction, Pallikkara, Ernakulam, at a total cost of Rs. 4,56,493/- (excl. GST @ 12% but incl. Labour Welfare Cess @ 1%).

(Signature)
19.02.2021
(A Rehiman)
Assistant Director

(Signature)
(R Venkatesan)
Accounts Officer (I/C)

(Signature)
(Mathew George)
Director

DIRECTOR: