

संख्या : भा.वि.प्रा./गोवा/ अभि (सि)/ डेवेलोपमेंट वर्क /2022 /463-465
No: AAI/GOA/Engg(C)/ Development Work/2022 /463-465

दिनांक/ Date: 24.03.2022

द्रुतगति डाक द्वारा /By Speed Post

सेवा मे,
मेसर्स सिद्धार्थ लक्ष्मी इंजिटेक प्राइवेट लिमिटेड
3/113, विशाल खंड, गोमती नगर,
लखनऊ-226001

To,
M/s Siddhartha Laxmi Engitech Private Limited
3/113, Vishal Khand, Gomti Nagar,
Lucknow-226001

विषय :- सि ई, गोवा में सि आई एस एफ बेचलर आवास के लिए रिटेनिंग वॉल, कार पार्क, सड़क कार्य और अन्य विविध विकास कार्यों का अतिरिक्त कार्य।

Subject :- Additional works construction of Retaining wall, car park, road work and other miscellaneous development works for CISF Bachelor accommodation at C.E, Goa.

संदर्भ /Ref :- आपकी दिनांक 28.02.2022 को खोली गई ई निविदा (निविदा क्र . 2022_AAI_101562_1)
Your e-tender for the subject work opened on 28.02.2022.
(Tender ID : -2022_AAI_101562_1)

महोदय/ Dear Sir (s),

- उपर्युक्त कार्य के लिए ई निविदा संलग्न अनुसूची के अनुसार उद्धृत कुल रु. 8,43,77,970/- (बिना जी एस टी जोड़े) (रुपए आठ करोड़ तैंतालीस लाख सत्तर हजार नौ सौ सत्तर मात्र) जो अनुमानित लागत रु. 1065.43 लाख (बिना जी एस टी जोड़े) (रुपए दस करोड़ पैंसठ लाख तैंतालीस हजार मात्र) से 20.80 % (बीस दशमलव अस्सी प्रतिशत) से नीचे, की नियत मद दर पर, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार की जाती है।
- Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totalling to Rs. 8,43,77,970/- (Excluding GST)(Rupees Eight Crores Forty Three Lakhs Seventy Seven Thousand Nine Hundred Seventy only) which is 20.80 % (Twenty point Eighty Percent) below the estimated cost put to tender of Rs. 1065.43 Lakhs (Excluding GST) (Rupees Ten Crores Sixty Five Lakhs Forty three Thousand Only).
- उप महाप्रबंधक (अभि-सि), भा वि प्रा, गोवा अंतरराष्ट्रीय विमानक्षेत्र, दाबोलिम, गोवा इस कार्य के अभियंता प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु 08.04.2022 से पहले उप महाप्रबंधक (अभि-सि), भा वि प्रा, गोवा अंतरराष्ट्रीय विमानक्षेत्र, दाबोलिम, गोवा के कार्यालय में उपस्थित हो। संविदा करार 100/- (रुपये एक सौ मात्र) के न्यायिकेतर स्टेम्प पेपर पर निष्पादित किया जाएगा और पेपर की लागत आप द्वारा वहन की जाएगी।
- Dy. General Manager (Engg-C), AAI, Goa International Airport, Dabolim, Goa shall be Engineer-in-Charge of the work. You are requested to attend the office of the Dy. General Manager (Engg-C), AAI, Goa International Airport, Dabolim, Goa before 08.04.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.
- आपकी निविदा के साथ रु 21,30,860/- (रुपये इक्कीस लाख तीस हजार आठ सौ साठ मात्र) प्राप्त अग्रिम धन राशि को संविदा दस्तावेज़ के 14.5 पृष्ठ A19 के अनुसार प्रतिभूती जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूती जमा के रूप में

Signature
24.03.2022

रु 20,88,039/- (बीस लाख अठासी हजार उनतालीस मात्र) जमा करे। अन्यथा इस राशि की कटौती संविदा कागजात के पृष्ठ जी सी सी -16 के खंड 1 ए के अनुसार कर ली जाएगी।

3. The earnest money amount of Rs 21,30,860/- (Rupees Twenty One Lakh Thirty Thousand Eight Hundred Sixty only) received along with your tender has been converted as part of Security Deposit as per clause 14.5 on Page A19 of Contract Document. Please deposit Rs 20,88,039/- (Rupees Twenty Lakh Eighty Eight Thousand Thirty Nine only) towards Security Deposit within 10 days from the issue of this letter, failing which, the same will be deducted as per condition of clause 1 A on page GCC 16 of the contract agreement .
4. अनुबंध दस्तावेज़ की शर्त खंड 1, पृष्ठ संख्या GCC 15 के अनुसार कार्य आदेश जारी होने के 30 दिनों के भीतर आप भारतीय विमानपत्तन प्राधिकरण को रुपये 31,96,290/- (रुपए इकत्तीस लाख छियानबे हजार दो सौ नब्बे मात्र) राशि की एक कार्य निष्पादन गारंटी पृष्ठ संख्या GCC 108 - GCC 109 पर संलग्न प्रोफॉर्मा के अनुसार बैंक गारंटी के रूप में प्रस्तुत करेंगे ।
4. Within 30 days of issue of work order, you shall submit to AAI, a Performance Guarantee as per condition of Clause 1 on page No. GCC-15 for an amount of Rs. 31,96,290/- (Thirty One Lakh Ninety Six Thousand Two Hundred Ninety only) in the form of Bank Guarantee on the proforma appended at page no. GCC-108 & GCC -109 of tender document.
5. आपसे अनुरोध है कि आप कोन्ट्रक्ट लेबर (रेग्युलेशन एंड अबोलीशन) एक्ट 1970, कोन्ट्रक्ट लेबर (रेग्युलेशन एंड अबोलीशन) सेंट्रल रूल 1971, बाल मजदूरी (प्रोहिबिशन एंड रेग्युलेशन) एक्ट 1986, कंस्ट्रक्शन वर्कर्स (रेग्युलेशन ऑफ़ एम्प्लोयमेंट एंड कंडीशन ऑफ़ सर्विस) एक्ट 1996, बिल्डिंग एवं कंस्ट्रक्शन वर्कर्स वेल्फर सेस एवं कंडीशन ऑफ़ सर्विस) एक्ट 1996, बिल्डिंग एवं अन्य कंस्ट्रक्शन वर्कर्स वेल्फर सेस, एक्ट 1996 के प्रावधानों एवं जी सी सी टी टेंडर खंड 19 पृष्ठ क्र. 49 और केंद्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।
5. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 Child Labour (Prohibition & Regulation), Act 1986, Construction workers (Regulation of Employment and condition of service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause 19 page no. 49 of GCC tender and rules of Central and State Government.
6. आपको सहा महाप्रबंधक (अभि-सि), भा. वि. प्रा. गोवा अंतरराष्ट्रीय विमानपत्तन, दाबोलिम, गोवा से तत्काल संपर्क करने का निर्देश दिया जाता है जो आपको कार्य स्थल सौंपेंगे ।
6. You are also directed to contact **Asst. General Manager (Engg-Civil), Airports Authority of India, Goa International Airport, Dabolim, Goa** immediately who will arrange to hand over the site to you.
7. कृपया ध्यान दें कि कार्य पूरा करने के लिए आपको बरसात के दिनों रहित 09 (नौ) महिने का समय प्रदान किया जाता है । जो इस पत्र के जारी होने की तारीख के बाद दसवें दिन से माना जाएगा।
7. Please note that the time allowed for carrying out the work shall be 09 (Nine) Months excluding rainy days and same shall be reckoned from tenth day after the date of issue of this letter.
8. अनुबंध के संबंध में कोई भी पत्राचार समान्य रूप से अभियंता प्रभारी को संबोधित किया जाना चाहिए।

Handwritten signature and date:
24/03/2020

8. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
9. कृपया पत्र की पावती भेजे और इस पत्र नकल पर स्वीकृती की निशानी के रूप में हस्ताक्षर करने के बाद हमें भेजे।
9. Please acknowledge the receipt & return the duplicate of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
10. यह पत्र अनुबंध दस्तावेज़ का भाग बनेगा।
10. This letter under reference shall form part of agreement.
11. यदि कोई विसंगति अंग्रेजी या हिन्दी संस्करण में पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।
11. In case any discrepancy is found between English or Hindi version then English version will be taken as correct.

धन्यवाद /Thanking you.

अनुलग्नक/ Encl: Schedule -A (BOQ)

भवदीय/ Yours faithfully,



Dy. General Manager (Engg-C)

उप महाप्रबंधक (अभि-सि)

कृते तथा ओर से अध्यक्ष,

For and on behalf of chairman,

भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

Government eProcurement System

Created By: Vinay Hedao

Created Date/Time: 28-Feb-2022 01:49 PM

Tender Title: Additional works construction of Retaining wall car park road work and other Miscellaneous development works for CISF Bachelor accommodation at CE Goa

Tender ID: 2022_AAI_101562_1

Tender Inviting Authority: Asst. Gen. Manager (Engg-C)-II, AAI, Goa Airport

Name of Work: Additional works construction of Retaining wall, car park, road work and other Miscellaneous development works for CISF Bachelor accommodation at C.E, Goa.

Contract No: 2022_AAI_101562_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
1.00	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 m : All kinds of soil by crushing stones/boulders	9100.00	cum	108.00	982800.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	2300.00	cum	108.00	248400.00

Sul
24/03/2022
S. C. NEWA (Pvt.)
Dy. Gen. Manager (Engg-C)-II,
AAI, Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
3.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Ordinary/ Laterite rock	13910.00	cum	207.00	2879370.00
4.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	220.00	cum	207.00	45540.00
5.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	630.00	cum	306.00	192780.00
6.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	2300.00	cum	90.00	207000.00

Sd/-
 24/04/2022
 S. C. NEVATIA
 Dy. Gen. Manager (Eng.-Civil)
 4. A. I. Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
7.00	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. Ordinary or hard rock	4100.00	cum	108.00	442800.00
8.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	630.00	cum	7020.00	4422600.00
9.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	90.00	cum	6300.00	567000.00
10.00	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	520.00	sqm	306.00	159120.00
11.00	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, butresses, plinth and string courses etc.	6300.00	sqm	306.00	1927800.00
12.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	405600.00	Kg	66.60	27012960.00

Sd/-
 24/03/2022
 एम. सी. नेवाले
 S. C. NEWALE
 उप महासंचालक (अभ्य-प्रि.)
 Dy. Gen. Manager (Eng.-Civil)
 आ. वि. प्रा. गोवा विमानतल, गोवा.
 A. A. I. Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
13.00	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/less cement used as per design mix is payable/recoverable separately). All works upto plinth level	3120.00	cum	7200.00	22464000.00
14.00	Extra for providing richer mixes at all floor levels. Note:- Excess/less cement over the specified cement content used is payable /recoverable separately. Providing M-30 grade concrete instead of M-25 grade BMC/ RMC. (Note:- Cement content considered in M-30 is @340 kg/cum)	3120.00	cum	108.00	336960.00
15.00	Add for using extra cement in the items of design mix over and above the specified cement content therein.	1410.00	Quintl e	810.00	1142100.00
16.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	18200.00	Kg	92.70	1687140.00

24/03/2021

4


Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
17.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	500.00	Kg	108.00	54000.00
18.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	2200.00	sqm	306.00	673200.00
19.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	1100.00	sqm	108.00	118800.00
20.00	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion On W.B.M / W.M.M. @ 0.4kg/sqm	3100.00	sqm	27.00	83700.00
21.00	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With medium setting bitumen emulsion. On bituminous surface @ 0.25kg/sqm	3100.00	sqm	27.00	83700.00


 24/03/2022
 एच. सी. नैवाले
 S. C. NEWALE
 ज्य. प्रबन्धक (अभिन. प्र.)
 Dy. Gen. Manager (Eng.-Civil)
 भा. वि. प्रा. गोवा विमानतळ, गोवा.
 A. A. I. Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
22.00	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. New work (Two or more coats)	150.00	sqm	180.00	27000.00
23.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineerin-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	1100.00	meter	450.00	495000.00


 24/03/2022
 ए. सी. नेवाले
 S. C. NEVALE
 उ. वि. प्र. (अ. वि. वि.)
 Dy. Gen. Manager (Eng.-Civil)
 भा. वि. प्र. भा. विमानपत्तन, गोवा.
 A. A. I. Goa Airport, Goa.


Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
24.00	Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge.50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	160.00	Cum	9270.00	1483200.00
25.00	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge.50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	230.00	Cum	8100.00	1863000.00


 24/03/2022
 S. C. NEUWALE
 Gen. Manager (Civil)
 Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
26.00	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge	2460.00	sqm	540.00	1328400.00
27.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in charge. Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade	1700.00	sqm	603.00	1025100.00
28.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	460.00	cum	3600.00	1656000.00

एस. सी. नेवाले
 S. C. NEWALE
 उप महाप्रबन्धक (अमि.-सि.)
 Dy. Gen. Manager (Eng.-Civil)
 भा. वि. प्रा. गोवा विमानपत्तन, गोवा.
 A. A. I. Goa Airport, Goa.


Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
29.00	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes.	60.00	Meter	1710.00	102600.00
30.00	Providing and laying of Geo Composite side of the Retaining wall for the protection of wipe hole blockage and easy flow of rain water as per direction of Engineer In Charge.	2600.00	sqm	270.00	702000.00
31.00	Providing and constructing masonry walls with precast solid concrete Block (having individual block compressive strength not less than 3.2 N/sq.mm) in C.M. 1:6 (1cement:6coarse sand) including striking joints on unexposed faces, racking out joints on exposed faces, watering, curing and scaffolding wherever required etc. complete as per the specification and directions of Engineer Incharge. In foundation and plinth.	700.00	Cum	7200.00	5040000.00
32.00	Crushing of stone bolders of 75 mm size or more in an integrated stone crushing unit of 200 tones per hour capacity with arrangement of noise and dust adoptor comprising of primary and secondary crushing unit, belt conveyer and vibrating screens to obtain stone aggregate of 75 mm nominal size and transporting the same materials deposited from crushing unit to site with a lead of 5km.	9100.00	Cum	504.00	4586400.00


 24/3/2022
 एम. सी. नेवाले
 S. C. NEWALE
 उपा. प्रबन्धक (सि. प्र.)
 Dy. Gen. Manager (Eng.-Civil)
 ज. गोवा विमानतळ, गोवा
 J. Goa Airport, Goa.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	M/S SIDDHARTHALAXMI ENGITECH PRIVATE LIMITED(GSTN-NA)	
				Rate	Amount
33.00	Boring/ Drilling of bore well of size 200mm dia for casing /strainer pipe, by suitable method prescribed in IS:2800 (Part-1), including hire and running charges of all equipments, tools, plants & machineries required for the jobs, all complete as per direction of Engineer In Charge.	250.00	Meter	540.00	135000.00
34.00	Supplying, assembling, lowering and fixing in vertical position in bore well, PVC (Indian bore well make) casing pipe of 150mm dia, conforming to IS: 12818, including required hire and labour charges, fittings and accessories etc. all complete as per direction of Engineer In Charge.	250.00	Meter	270.00	67500.00
35.00	Supplying, assembling, lowering and fixing in vertical position in bore well, UPVC outlet pipe (Ashirvad make) 1.25" or 1.5' including required hire and labour charges, fittings and accessories etc. all complete as per direction of Engineer In Charge.	250.00	Meter	540.00	135000.00

Total in Figures

84377970.00


 एस. सी. नेवाले
 S. C. NEWALE
 उप मा. प्रबंधक (अभि. - सि.)
 Dy. Gen. Manager (Eng.-Civil)
 भा. वि. प्रा. गोवा विमानपत्तन, गोवा.
 A. A. I. Goa Airport, Goa.