



No. AAI/ SR/Salem/Engg(C)/Grading/2022-23/13

Dt. 02.05.2022

To,

M/s. SRI MARUTHI CONSTRUCTIONS,
No.4/474, Kodikadu,
Pottipuram,
Kadayampatti,
Salem-636 309.

Sub: Grading of basic strip near ARP at Salem Airport.

Ref: 1. Your e-tender (Envelope II - Price bid) opened on 21.02.2022

* 2. Tender ID No. 2022_AAI_101565_1

Sir,


1. Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 1,36,10,500.00 (Rupees One Crore thirty six lakhs ten thousand and five hundred only) plus applicable GST @ 18%, which is 18.39% below the estimated cost put to tender of Rs. 166.77 Lakhs.
2. Jt. Gen. Manager (Engg-Civil), AAI, RHQ-SR, Operational offices, Chennai-600 016 shall be the Engineer- in- Charge of the work. You are requested to attend the office of the Asst. Gen. Manager (Engg-Civil), AAI, RHQ-SR, Chennai – 600 016 within 15 days from the stipulated date of start of work to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees One hundred only) and the cost of stamp paper shall be borne by you.
3. You are directed to deposit Rs. 13,61,050.00 (Rupees Thirteen lakhs sixty one thousand and fifty only) towards security deposit within 10 days from the date of issue of this letter, failing which, 10% of value of work done will be deducted from the running account bills as security deposit as per condition of Clause No.1(A) on page No. 16 of the Tender Document. The Earnest Money Amount of Rs. 3,34,000.00 (Rupees Three lakhs and thirty four thousand only) received on line payment through CPP portal along with your tender will be refunded after depositing of security deposit or after deduction of the EMD amount as security deposit from the running bills.

Contd...2

//2//

4. You are requested to comply with the provisions of contract labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and minimum wages Act and rules thereof Central and State Governments.
5. You are also directed to contact Asst. Gen. Manager (Engg-Civil), AAI, RHQ-SR, Chennai – 600 016 immediately who will arrange to hand over the site to you.
6. Please note that the time allowed for carrying out the work shall be **4 (Four) Months** and same shall be reckoned from the tenth day after issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned, as a token of acceptance.

Yours faithfully,


02/05/22

(K. Prabha)

Jt. Gen. Manager (Engg-Civil)

AAI, RHQ-SR, Chennai-600 016.

FOR AND ON BEHALF OF CHAIRMAN, AAI

Encl:

Schedule 'A'

Copy To:

By Mail

1. GM (Engg), RHQ-SR, Chennai.
2. JGM(F&A), RHQ-SR, Chennai.
3. The Airport Director, Salem Airport.
4. AGM (OL), RHQ-SR, Chennai. - May please submit Hindi Version
5. AGM (Engg-Civil), RHQ-SR, Chennai.
6. JE (Engg-Civil), Salem Airport.
7. Labour Commissioner, No.26, Illrd street, 5th floor, Shastri Bhawan, Haddows Road, Nungambakkam, Chennai 600 006
8. Regional Provident Fund Commissioner, No.2, Rajaji Salai, West Tambaram, Chennai – 600 045

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM (Engg-Civil), Operational Office Complex, RHQ-SR, Chennai 600 016.

Name of Work: "Grading of basic strip near ARP at Salem Airport."

Contract No: 2022_AAI_101565_1

Name of the Bidder/ Bidding Firm / Company :	SRI MARUTHI CONSTRUCTIONS					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE Excluding GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT WITHOUT GST in Rs. P	TOTAL AMOUNT WITHOUT GST In Words
1	2	4	5	7	8	10
1	Carriage of materials by mechanical transport including loading, unloading and stacking etc., complete for a lead of 1Km a) Excavated rock.	100.00	Cum	300.00	30000.00	INR Thirty Thousand Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m inwidth or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	210.00	Cum	300.00	63000.00	INR Sixty Three Thousand Only
3	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. a). Hard rock (blasting prohibited)	100.00	Cum	1500.00	150000.00	INR One Lakh Fifty Thousand Only
4	Supply of Good earth at site including spreading, levelling at required slope etc. complete as per the direction of Engineer-in-charge. (For payment purpose, 20% voids will be deducted).	2100.00	Cum	400.00	840000.00	INR Eight Lakh Forty Thousand Only

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a). 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	240.00	Cum	5000.00	1200000.00	INR Twelve Lakh Only
6	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : a). Cement mortar 1:6 (1 cement : 6 coarse sand)	260.00	Cum	5500.00	1430000.00	INR Fourteen Lakh Thirty Thousand Only
7	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete.	1850.00	Sqm	650.00	1202500.00	INR Twelve Lakh Two Thousand Five Hundred Only
8	Construction of Subgrade embankment with Moorum/gravel soil brought out from approved quarry out side the airport premises. The complete operation will include spreading the Moorum with dozer, dressing, levelling, providing camber, grading with motor grader and consolidating with vibratory roller 8-10 tonne capacity in layers not exceeding 20cm in depth to achieve 95% of the field density including making good the undulation etc. as per technical specifications and drawings complete and directions of Engineer-in-Charge. (Cost includes all leads ,taxes, royalty, operations and obtaining field density from the approved land or Govt Engineering college)	12100.00	Cum	450.00	5445000.00	INR Fifty Four Lakh Forty Five Thousand Only
9	Preparation of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by Mechanical transport to work site, for all leads & lifts, spreading in uniform layers of specified thickness with mechanical means including neatly levelling and dressing on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge : a). With material conforming to Grade-I having CBR Value-30 as per table -1 of technical specification.	2500.00	Cum	1300.00	3250000.00	INR Thirty Two Lakh Fifty Thousand Only
Total in Figures					13610500.00	INR One Crore Thirty Six Lakh Ten Thousand Five Hundred Only
Quoted Rate in Words		INR One Crore Thirty Six Lakh Ten Thousand Five Hundred Only				