

संदर्भ संख्या : भाविप्रा/ इंदौर/अभि.-वि/कार्य आदेश-15/2021-22/139-52

दिनांक : 24/02/2022

Ref. No.: AAI/ID/ENGG(E)/WO-15/2021-22

Date: 24/02/2022

प्रति,

1338-50 (अभे)

मेसर्स वर्धमान एयरपोर्ट सॉल्यूशन्स प्रा.लिमि.,
1st एण्ड 2nd फ्लोर, प्लॉट नं. 13/सी एण्ड 13/3,
रामा रोड साईड, इन्डस्ट्रियल एरिया, नजफगढ़ रोड,
दिल्ली - 110015

M/s Vardhman Airport Solutions Pvt. Ltd.,
1st and 2nd Floor, Plot No. 13/C and 13/3,
Rama Road Side, Industrial Area, Najafgarh Road,
Delhi - 110015

विषय :- डेक्कपमेंट ऑफ 15 नं. पार्किंग बेज, पेरालल टैक्सी ट्रेक एण्ड अदर एसोसिएटेड वर्क्स एट डी.ए.बी.एच. एयरपोर्ट, इन्दौर।

सबहेड : सप्लाय एण्ड लेईंग ऑफ सेकण्डरी लीड्स फॉर एप्रन एण्ड टैक्सी वे एज लाईट्स बाय कर्फ कटिंग ऑफ एप्रन/टैक्सीवे एण्ड एसोसिएटेड वर्क्स एज रिक्वायर्ड।

NAME OF WORK:- "Development of 15 Nos. Parking Bays, Parallel Taxi Track and Other associated works at DABH Airport, Indore.

SH: Supply and Laying of Secondary Leads for Apron and Taxiway Edge Lights by Kerf Cutting of Apron/ Taxiway and associated works as required."

संदर्भ :- आपकी ई-निविदा 2022_AAI_101607_1 जो दिनांक 16.02.2022 को खोली गई।

Your E-Tender No. 2022_AAI_101607_1 opened on dated 16.02.2022

प्रिय महोदय/ Dear Sir,

- उपरोक्त कार्य हेतु आपका टेण्डर, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताये गये मद मुल्यों पर आपकी टेण्डर राशि कुल लागत ₹ 13,27,962/- (रुपये तेरह लाख सत्ताईस हजार नौ सौ बासठ मात्र जी.एस.टी. रहित) है, जो कि टेण्डर की अनुमानित लागत राशि ₹ 13,88,000/- जी.एस.टी. रहित से 4.33 % कम है, पर स्वीकृत किया जाता है।

Your Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to ₹ 13,27,962/- (Rupees Thirteen Lakh Twenty Seven Thousand Nine Hundred Sixty Two Only Excluding GST) which is 4.33 % below the Estimated cost put to tender of ₹ 13,88,000/- Excluding GST.

- सहायक महाप्रबंधक (अभि.-विद्युत), भाविप्रा, दे.अ.बा.हो. विमानतल, इन्दौर कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो कि करारनामों पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 10.03.2022 तक सहायक महाप्रबंधक (अभि.-विद्युत), भाविप्रा, दे.अ.बा.हो. विमानतल, इन्दौर के कार्यालय में उपस्थित हो तथा करारनामों को पूरा करें। ठेके का करारनामा रु 100/- के नॉन ज्युडिशियल स्टेम्प पेपर पर निष्पादित किया जाएगा, तथा स्टेम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।

The Asstt. General Manager (Engg.-Elect.), AAI, DABH Airport, Indore shall be the Engineer-in-charge of the work. You are requested to depute your accredited representative empowered to sign the contract Agreement on your behalf to attend the office of the Asstt. General Manager (Engg.-Elect.), AAI, DABH Airport, Indore by 10-03-2022 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of Rs. 100/- and the cost shall be borne by you.

Continued on page No. ...02

-02-

3. आपके टेण्डर के साथ प्राप्त धरोहर राशि रुपये 27,760/- क्लॉज 1 ए के अनुसार जमानत राशि में परिवर्तित की जाएगी। कृपया ₹ 1,05,036.00 (रुपये एक लाख पाँच हजार छत्तीस मात्र) प्रतिभूति जमा के रूप में यह पत्र के जारी करने की तारीख से 10 दिन के अंदर जमा कीजिए। जमा करने की असफलता के फलस्वरूप यह राशि ठेका दस्तावेज के जीसीसी के पृष्ठ क्र.16 के Clause '1A' की शर्त के अनुसार काट दी जाएगी।

The earnest money amount of Rs. 27,760/- received along with your tender will be treated and converted as part of security deposit as per Clause 1A. Please deposit ₹ 1,05,036.00 (Rupees One Lakh Five Thousand Thirty Six Only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per condition of Clause '1A' on page no. 16 of GCC of the contract document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम (नियमन तथा उन्मुलन) तथा 1971 के केन्द्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मुलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों का अनुपालन करें।

You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Government.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि.-विद्युत), भाविप्रा, दे.अ.बा.हो. विमानतल, इन्दौर से मिलें वह आपको साईट सौंपने की व्यवस्था करेंगे। कृपया नोट कर लें कि काम करने का अनुमानित समय 02 (दो) माह है जो कि दिनांक 01.03.2022 से गिना जाएगा।

You are also directed to contact Asstt. Manager (Engg-E), AAI, DABH Airport Indore immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work is 02 (Two) Months which shall be reckoned from Dtd. 01.03.2022.

6. इस ठेके के संबंध में आगे कोई भी पत्राचार सहायक महाप्रबंधक (अभि.-विद्युत), भा.वि.प्रा., दे.अ.बा.हो. विमानतल, इन्दौर म.प्र. - 452005 के पते पर किया जाएगा।

Any further correspondence in connection with this contract should normally be addressed to Asstt. General Manager (E-E), AAI, DABH Airport Indore, M.P.- 452005.

7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All letters referred above shall form part of contract.

8. ठेके दस्तावेज की शर्त के अनुसार त्रुटि दायित्व अवधि 12 (बारह) माह होगी।

The Defects Liability Period will be of 12 (Twelve) Months as per terms of Contract.

9. कृपया पावती भेजें एवं आपकी स्वीकृति के प्रतीक के रूप में इस कार्य आदेश की डुप्लीकेट प्रति पर हस्ताक्षर कर अधोहस्ताक्षरी को पुनः भेजने का कष्ट करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Continued on page No.03

-03-

10. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जायेगा ।

If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

धन्यवाद / Thanking You,
संलग्न / Enclosure : 1) Schedule 'A' – 04 Pages

भवदीय / Your's Faithfully,


24/02/2022

सहायक महाप्रबंधक (अभि.विद्युत),
Asstt. General Manager (Engg-Elect)

भा.वि.प्रा. इन्दौर विमानतल, इन्दौर
AAI, DABH AIRPORT, INDORE

कृते तथा ओर से, अध्यक्ष

For and on behalf of Chairman
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India

SCHEDULE OF QUANTITIES

Name of work :Development of 15 Nos. Parking Bays, Parallel Taxi Track and Other associated works at DABH Airport, Indore.

SH: Supply and Laying of Secondary Leads for Apron and Taxiway Edge Lights by Kerf Cutting of Apron/ Taxiway and associated works as required.


S.No.	Description of Work / Item(s)	QTY	UNIT	RATE	AMOUNT
1	Supply of 2 nos. of 1 core x 2.50 sq.mm. EPR/ elastomer insulated secondary leads as a pair of following lengths with suitable male/ female connector mouldings on both sides of the pair for connecting Isolating Transformer at one end and GLF fitting at the other end.				
(i)	6 - 8 Mtr.	70	Set	1751.00	122,570.00
(ii)	10 Mtr.	15	Set	2083.00	31,245.00
(iii)	14-16 Mtr.	10	Set	3019.00	30,190.00
(iv)	21 Mtr.	7	Set	3864.00	27,048.00
2	Laying of 2 Nos. 1 x 2.50 sq. mm. Secondary lead after cutting kerf upto a depth of 175 mm. as required, with the help of kerf cutting machine including chipping, cleaning and removing the concrete/ stone, dust etc. and priming the kerf channel, filling with protective backing rod and polysulphide sealant etc. as required.	525	Mtr.	500.00	262,500.00



S.No.	Description of Work / Item(s)	QTY	UNIT	RATE	AMOUNT
3	Supply of C.I. Isolating Transformer housing box, water tight round type, metal container of outside size 330mm height 450mm made of 10mm thick cast iron moulding suitable to receive a light fitting base plate/ dummy plate on the top and underground housing associated with transformer power cable and having a clear hole centre at one/ two side surface centre 75mm above bottom surface suitable to receive one /two nos. of 50mm dia "B" class GI pipe and including check nuts as required and another hole at 225 mm from the bottom of the CI Box to receive one no. 40mm dia "B" class GI pipe and check nut as required. The box should have two SS earth bolts of M10 x 30mm tapped inside near the hole (4" away from the hole centre) and having a drain hole at the bottom suitably tapped to receive 15mm dia "B" class GI pipe and having clear opening of 220 mm at the top surface and 6 nos. M10 tapped hole at the hole centre 260 mm to receive fitting base plate and bolts complete as required.				
a)	Single Hole Type	47	Each	4934.00	231,898.00
b)	Double Hole Type	33	Each	5187.00	171,171.00
4	Installation of Transformer housing boxes with a base concrete of 1:3:6 of size 630x630x100 mm thick and all round concrete of 1:2:4, 150mm thick, the top sloped with 1:2:4 cement concrete including providing and fixing 250 mm long 15mm dia "B" class GI pipe with check nut for drainage of water and providing and fixing 200 mm long 40mm dia "B" class GI pipe with check nut for receiving secondary lead including excavation of earth and refilling etc. complete as required. Due care to be taken to keep all the activities in synch to ensure suitable connection of GI/ DWC Pipes as required.	50	Job	1500.00	75,000.00




S.No.	Description of Work / Item(s)	QTY	UNIT	RATE	AMOUNT
5	Installation of Transformer housing boxes with a base concrete of 1:3:6 of size 630x630x100 mm thick and all round concrete of 1:2:4, 150mm thick, the top sloped with 1:2:4 cement concrete including providing and fixing 250 mm long 15mm dia "B" class GI pipe with check nut for drainage of water including excavation of paver blocks/ earth and refilling (wherever the transformers boxes are to be installed in a line the same has to be aligned in such a way that the centre fall in a straight line) etc. complete as required. Due care to be taken to keep all the activities in synch to ensure suitable connection of GI/ DWC Pipes as required.	30	Job	1500.00	45,000.00
6	Supply of 10 mm. thick round MS dummy plate of dia 330 mm. and having 6 nos. M10 tapped hole at the hole centre 260 mm. suitable for fixing over above CI Housing Boxes, alongwith supply of 6 Nos. Stainless Steel M10x40 bolts and suitable neoprene gasket etc. complete as required.	80	Set	918.00	73,440.00
7	Making field connections by crimping of 6 sq.mm. plug & receptable with existing 6 sq.mm. single core PVC Cu. Conductor cable, making connection of Plug & Receptacle and connector of secondary lead with Isolating Transformer inside the CI Housing Box including filling the gaps with water sealant material, applying PVC insulation tape etc., and thereafter fixing the MS Dummy Plate over the CI Box with gasket and M10 bolts etc. complete as required.	80	Job	50.00	4,000.00
8	Installation, Testing and Commissioning of Taxiway/ Apron edge light on existing transformer housing box with all accessories including lamp, lens, gasket, nut bolts etc. and making connection with the secondary lead connector etc. as required.	80	Job	50.00	4,000.00
9	Supply and laying of 40 mm dia B class GI pipe of length approx. 1.15 mtr. (+/- 0.10 mtr.) as per site requirement, for crossing existing culvert by making suitable hole on walls of the culvert and filling/ finishing the surrounding void with concrete after laying the pipe. One end of the pipe shall be connected to existing CI Housing box with proper check nut and the other end shall be open to receive secondary lead as required.	30	Job	450.00	13,500.00



S.No.	Description of Work / Item(s)	QTY	UNIT	RATE	AMOUNT
10	Supply and laying of 50 mm dia B class GI pipe including sockets, all accessories etc. as required, by removing paver blocks, coarse sand etc. and refilling/ making good the same after laying. The pipe shall be connected to existing CI Housing Boxes at both end alongwith providing suitable check nuts etc. as required.	300	Mtr.	550.00	165,000.00
11	Laying of 1 no. 63 mm dia OD DWC Pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. direct in ground including excavation, trenching (75 cm deep) and refilling etc. complete as required. The DWC Pipe shall be provided by AAI.	335	Mtr.	90.00	30,150.00
12	Laying of 1 no. additional 63 mm dia OD DWC Pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. direct in ground in existing trench complete as required. The DWC Pipe shall be provided by AAI.	75	Mtr.	40.00	3,000.00
13	Laying of 1 no. 63 mm dia OD DWC Pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. in existing culvert duly clamped (clamped with 25x3mm MS flat clamp) on its wall etc. complete as required. The DWC Pipe shall be provided by AAI.	175	Mtr.	18.00	3,150.00
14	Laying of one. PVC insulated and PVC sheathed/ XLPE power cable of 5 KV grade size upto 16 sq mm in existing RCC/Hume/Stoneware/GI pipes /DWC pipe as required.	900	Mtr.	18.00	16,200.00
15	Providing and fixing 6 SWG GI wire on surface or in recess for loop earthing in existing surface/recess pipe along with submain wiring/ cable etc. as required.	900	Mtr.	21.00	18,900.00
Total					1327962.00

(Rupees Thirteen Lakh Twenty Seven Thousand Nine Hundred Sixty Two Only)

Note : GST extra, as applicable.


 24/02/2022
Asstt. General Manager (E-E)
 AAI, D.A.B.H. Airport, Indore