



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

No: AAM/ENGG/ELEC/AMED-XI/SNI Boards/2021-22/A-09

Date: 04.03.2022

To
M/s. AMA Private Limited,
Canada Building,
224, Dr. D.N. Road,
Mumbai - 400001.

Name of Work: Trans-installation of Stand Number Indicator and WGS84 Sign boards i/c
Provision of new SNI/WGS84 Boards at Remote bays at Chennai
International Airport.

Ref: 1) e-Tender ID: 2022_AAI_102960_1.
2) Price Bid opened on 23.02.2022.

Dear Sir(s),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.40,56,000.00** (Rupees Forty Lakhs Fifty Six Thousand Only), which is 26.38% below than the estimated/justified cost of Rs.55,09,324.00 put to tender. The rates are exclusive of GST.
2. Joint General Manager (Engg-Elect)-I, AMED, AAI, Chennai Airport shall be the Engineer-In-Charge of the work. You are requested to attend the office of Joint General Manager (Engg. -Elect)-I, AAI, Chennai Airport by 15.03.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100.00 (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. The Earnest Money amount of Rs. 1,10,190.00 (Rupees One Lakh Ten Thousand One Hundred and Ninety Only) paid through payment gateway in CPP portal will be refunded after adjustment of Security Deposit. Please deposit Rs. 4,05,600.00 (Rupees Four Lakhs Five Thousand Six Hundred Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no.1A of GCC at page no. GCC-16 of Contract document.
4. You are requested to comply with the Provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause No.19 of GCC of AAI and rules of Central and State Government.

Contd./2...

फैक्स : 044 - 2256 0008 इ पी ए बी एक्स : 2256 0551, चेन्नई हवाईअड्डा, चेन्नई - 600 016.

Fax : 044 - 2256 0008 EPABX : 2256 0551, Chennai Airport, Chennai - 600 016.



::2::

5. You are also directed to contact Asst. General Manager (Engg.-Elect), AMED-XI, Chennai Airport immediately who will arrange to handover the site to you.
6. Please note that the time allowed for carrying out the work shall be **03 (Three) Months** and same shall be reckoned from the 10th day of issue of this letter. (i.e. 14.03.2022)
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge i.e., Joint General Manager (Engg-Elect)-I, AMED, Chennai Airport.
8. All other Terms and Conditions shall be as per Agreement.
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule of Quantities (02 Sheets).

Yours faithfully,

(G.N.D. Kennedy)

Jt. General Manager (Engg-Elect.)-I
AMED, AAI, Chennai Airport
For and on behalf of the Chairman,
Airports Authority of India.

AIRPORTS AUTHORITY OF INDIA
CHENNAI AIRPORT :: CHENNAI - 600016

SCHEDULE OF QUANTITIES

NAME OF WORK: **Trans-installation of Stand Number Indicator and WGS84 Sign boards i/c Provision of new SNI/WGS84 Boards at Remote bays at Chennai International Airport.**

S.No.	Description of Item	Qty	Unit	Basic Rate (Excluding GST) (Rs.)	Amount (Excluding GST) (Rs.)
1	Dismantling of existing Stand Indication poles (6Mtr) i/c Retroreflective Stand Number Indicator (SNI) Triangular board [each face 1200(L)mm x 1200(H)mm] and WGS84 Board [size 1200(L)mmx800(H)mm]at various remote bays by removing/cutting anchor fastners, de-welding and reinstallation of above dismantled SNI and WGS 84 Boards on the existing AVDGS pole (9 Mtr) as per the Schematic drawing attached under SCC with necessary fabrication of MS flat/angles/pipes of suitable sizes with GI coating for installation of above boards and shifting the dismantled pole(6Mtr) to the AAI stores and as directed by Engineer-In-charge as required. Note: The rate shall including the necessary lifting arrangement for installation of above boards in order to safeguard the existing AVDGS unit (installed on the 9 Mtr pole).	33	Job	25,000.00	8,25,000.00
2	Supply of Stand Number Indicator (SNI) Triangular board (Each face sized 1200(L)x 1200(H)mm) made up of 3 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro-reflective sheeting pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure and fixing the same with suitable sized aluminium alloy rivets @20cm c/c to back support to Aluminium sheet made of powder coated. The provision shall be made for fixing the triangular board to the pole. The background colour and size / colour of lettering shall be as per ICAO specifications. Note: The signage matter will be provided by AAI.	17	No.	35,000.00	5,95,000.00
3	Supply of World Geodetic System 84(WGS 84) Rectangular board (Size 1200(L)x 800(H)mm) made up of 3 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro-reflective sheeting pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure and fixing the same with suitable sized aluminium alloy rivets @20cm c/c to back support to Aluminium sheet made of powder coated. The provision shall be made for fixing the Rectangular board to the pole. The background colour and size / colour of lettering shall be as per ICAO specifications. Note: The signage matter will be provided by AAI.	17	No.	28,000.00	4,76,000.00

S.No.	Description of Item	Qty	Unit	Basic Rate (Excluding GST) (Rs.)	Amount (Excluding GST) (Rs.)
4	Installation of SNI/WGS84 Boards (under S.No.2/3) on the existing AVDGS pole (9 Mtr) (as per the Schematic drawing attached under SCC) with necessary fabrication of MS flat/angles/pipes of suitable sizes with GI coating for installation of above boards and complete as required. Note: The rate shall including the necessary lifting arrangement of above boards (under S.No.2 /3) for installation in order to safeguard the existing AVDGS unit (installed on the 9 Mtr pole). (Note: The Qty of 1 Job Consists of Installation of 1 Board.)	34	Job	15,000.00	5,10,000.00
5	Providing and erecting a MS barricade (of MS 'C' Channel size 150x75x5.7mmthick) around AVDGS pole/electrical installtion with required riveting, welding, anchor fastening on the floor etc., including primer coat and approved synthetic enamel paint and complete as required. (Note: The Qty is in Running Meter)	1200	Mtr	1,300.00	15,60,000.00
6	Providing and fixing a MS Sheet (of MS Flat size 600x600x2mm thick) for covering the stand of Outdoor feeder pillar with required riveting/nut and bolts etc., including primer coat and approved synthetic enamel paint and complete as required.	9	Job	10,000.00	90,000.00
Total Amount (Excluding GST) Rs.					40,56,000.00

(Rupees Forty Lakhs Fifty Six Thousand Only)

Note: Applicable GST shall be paid on submission of taxable invoice.


 (G.N.D.KENNEDY)
 Jt.Gen.Manager(Engg-E)-I
 AAI/AMED/Chennai Airport