



दूरभाष कार्यालय : 2511-9600
भारतीय विमानपत्तन प्राधिकरण
पूर्वी क्षेत्र, ने.सुच.ब.अ. विमानपत्तन., कोलकाता

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

Tel. Office : - 2511-9600
AIRPORTS AUTHORITY OF INDIA
Eastern Region, N.S.C.B.I. Airport, Kolkata - 52

संदर्भ सं/Ref. No:- AAI/KOL/ENGG(C)/W.O. – 15/2021-22/ 477

दिनांक /Date: 24.03.2022

सेवा में/To

मे. एस. आर. एंटरप्राइज़

M/s S.R. Enterprise

छोटो घाँटी, पी. ओ. - घाँटी,

Choto Ganti, P.O. – Ganti,

पी. एस. - नारायणपुर,

P.S. – Narayanpur,

कोलकाता / KOLKATA – 700 132.

विषय/Sub :- मिसकेलनेऔस अनफोरसीन वर्क्स (एसएच: अपग्रेडेसन ऑफ गेस्ट हाउस एंड फ्रंट एरिया ऑफ बैडमिंटन कोर्ट इन न्यू क्वार्टर रेज़िडेन्शियल कॉम्प्लेक्स एट एनएससीबीआई एयरपोर्ट, कोलकाता।
Misc. Unforeseen works (SH: - Upgradation of Guest House and front area of Badminton Court in New Quarter Residential Complex at NSCBI Airport, Kolkata.

संदर्भ/ Ref. : (i) आपकी इ निविदा खोला गया 16-03-2022

Your E-Bid opened on 16-03-2022.

खुली निविदा आईडी: 2022_AAI_106814_1

[Open Tender ID : 2022_AAI_106814_1]

महोदय /Dear Sir (s),

- उपरोक्त कार्य की रूपया 4670355.00 (छियालीस लाख सत्तर हजार तीन सौ पचपन रूपये मात्र) की मद दर निविदा, जो कि कार्य कि अनुमानित लागत रूपया 7891789.00 (अठत्तर लाख एकानब्बे हजार सात सौ नवासी रूपये मात्र) से 40.82% (चार ज़ीरो दशमलव आठ दो) कम है, आपके द्वारा निविदा प्रपत्र मे दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totalling to **Rs. 4670355.00 (Rupees Forty Six Lakh Seventy Thousand Three Hundred Fifty Five Only)** which is **40.82% (Four Zero Point Eight Two Percent)** below the estimated cost put to tender of **Rs. 7891789.00 (Rupees Seventy Eight Lakh Ninety One Thousand Seven Hundred Eighty Nine Only)**.

Contd./-2

Rumal

M/s. S. R. ENTERPRISE

Sandeep Kumar

Proprietor

2. संयुक्त महाप्रबन्धक (अभि- सिविल), क्षेत्रीय कार्यपालक निदेशक (पूर्वी क्षेत्र) का कार्यालय, ए ए आइ, एन एस सी बी आइ एयरपोर्ट, कोलकाता -52 इस कार्य के कार्य प्रभारी अभियन्ता होंगे। आपसे अनुरोध है कि दिनांक 02 अप्रैल 2022 तक संयुक्त महाप्रबन्धक (अभि- सिविल), ए ए आइ, एनएससीबीआई एयरपोर्ट कोलकाता-52 के कार्यालय में उपस्थित होकर संविदा अनुबंध को हस्ताक्षरित कर पूर्ण करें। अनुबंध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

Jt. Gen. Manager (E-C), O/o The Regional Executive Director (E/R), Airports Authority of India, N.S.C.B.I. Airport, Kolkata - 52 shall be the Engineer-in-charge of the work. You are requested to attend the office of Jt. Gen. Manager (E-C), O/o The Regional Executive Director (E/R), Airports Authority of India, NSCBI Airport, Kolkata - 52 by **02-04-2022** to sign and complete the agreement. The contract agreement shall be executed on a **non-judicial stamp paper of value of Rs.100/- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.

3. कृपया शेष प्रतिभूति निक्षेप राशि रुपये 3,09,200.00 (तीन लाख नौ हजार दो सौ रुपये मात्र) इस पत्र के जारी होने की तारीख से 10 (दस) दिनों के भीतर बैलेंस सिक्योरिटी डिपॉजिट की दिशा में, असफल होना जो अनुबंध की सामान्य शर्तों के पृष्ठ 37 पर खंड 1 ए के अनुसार घटाया जाएगा।

Please deposit **Rs. 3,09,200.00 (Rupees Three Lakh Nine Thousand Two Hundred Only)** towards balance security deposit within **10 (Ten) days** from the date of issue of this letter, failing which the same will be deducted as per **clause 1A on page 37 of General Conditions of Contract**.

4. आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनियम एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनियम एवं उन्मूलन) - केन्द्रीय नियम 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार और सेवा की शर्तों का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 आदि में समय-समय पर या किसी अन्य कानून से संबंधित संशोधन और नियमों से संबंधित नियम बनाए गए केंद्र और राज्य सरकारों के समय-समय पर नियमों का पालन करना सुनिश्चित करें।

You are requested to comply with the provision of contract labour (Regulation & Abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules, 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers Welfare Cess Act 1996 etc. amended from time to time or any other laws relating thereto and rules made there under from time to time of Central and State Governments.

5. आपको निर्देशित किया जाता है कि आप तुरंत प्रभाव से सहायक महा प्रबंधक (इंजी-सिविल), ए ए आइ, एनएससीबीआई एयरपोर्ट, कोलकाता से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact **The Asstt. Gen. Manager (E-C), AAI, NSCBI Airport, Kolkata** immediately, who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 04 (चार) महीना है जो इस पत्र के जारी होने की तिथि से दसवें दिन से प्रभावी मानी जाएगी।

Please note that the time allowed for carrying out the work is **04 (Four) Months** and shall be reckoned from the tenth day after issue of this letter.

7. संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यता अभियंता प्रभारी को सम्बोधित करें।

Any further correspondence in connection with the contract should normally be addressed to the **Engineer-In-Charge**.

8. कृपया इस पत्र कि पावती भेजे एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. उपरोक्त के हिन्दी पाठ में कोई अंतर या द्विधरथकथा होने की स्थिति में अंग्रेजी पाठ मान्य होगा।

In case of difference or ambiguity in Hindi and English version, the English version will prevail.

भवदीय /Yours faithfully,

Encl:- BOQ

(जे। गांगुली/J. Ganguly)

सं. महाप्रबन्धक (इंजी -सि)/ Jt. Gen. Manager (E-C)

प्रथम तल, परिचालन कार्यालय

1st Floor, Operational Office,

भाविप्रा, नेसुचबोअ हवाईअड्डा, कोलकाता - 52

AAI, N.S.C.B.I. Airport, Kolkata – 700 052.

अध्यक्ष, भा वि प्रा के लिए व उनकी तरफ से

For and behalf of the Chairman, AAI.

Government eProcurement System Created By: Swapan Kumar Karmakar Created Date/Time: 16-Mar-2022 12:54 PM Tender Title: Misc. Unforeseen works (SH Upgradation of Guest House and front area of Badminton Court in New Quarter Residential Complex at NSCBI Airport, Kolkata. Tender ID: 2022_AAI_106814_1
--

Tender Inviting Authority: S.K. Karmakar, AGM (E-C), AAI, Operational Building, NSCBI Airport, Kolkata- 700 052.

Name of Work: Misc. Unforeseen works (SH: Upgradation of Guest House and front area of Badminton Court in New Quarter Residential Complex at NSCBI Airport, Kolkata.

Contract No: 2022_AAI_106814_1

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	M/S. S.R.ENTERPRISE(GSTN-NA)		Sanjib Saha(GSTN-19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
1.00	Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF/ Lumiflon based fluoropolymer resin coating of approved colour an shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of	230.00	Sqm		1790.00	411700.00	1900.00	437000.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
SI.No	Description of Work / Item(s)	No.of Qty	Units	Estima ted Rate	M/S. S.R.ENTERPRISE(GSTN- NA)		Sanjib Saha(GSTN- 19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
2.00	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels Granite of any colour and shade Area of slab over 0.50 sqm	63.00	Sqm		2280.00	143640.00	2600.00	163800.00
3.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC15)	1830.00	Kg.		430.00	786900.00	440.00	805200.00
4.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	120.00	Sqm		845.00	101400.00	800.00	96000.00
5.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	176.00	Kg.		400.00	70400.00	430.00	75680.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estima ted Rate	M/S. S.R.ENTERPRISE(GSTN- NA)		Sanjib Saha(GSTN- 19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
6.00	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	165.00	Kg.		500.00	82500.00	450.00	74250.00
7.00	Providing and fixing GI Clip in Metal Ceiling System of 600x600 mm module which includes providing and fixing 'C' wall angle of size 20x30x20 mm made of 0.5 mm thick pre painted steel along the perimeter of the room with help of nylon sleeves and wooden screws at 300 mm center to centre, suspending the main C carrier of size 10x38x10 mm made of G.I steel 0.7 mm thick from the soffit with help of soffit cleat 37x27x25x1.6 mm, rawl plugs of size 38x12 mm and C carrier suspension clip and main carrier bracket at 1000 mm c/c. Inverted triangle shaped Spring Tee having height of 24 mm and width of 34 mm made of GI steel 0.45 mm thick is then fixed to the main C carrier and in direction perpendicular to it at 600 mm centers with help of suspension brackets. Wherever the main C carrier and spring T have to join, C carrier and spring T connectors have to be used. All sections to be galvanized @ 120 gms/sqm (both side inclusive), fixing with clip in tiles into spring T with : GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height, made of G I sheet having galvanizing of 100 gms/ sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation.	10.00	Sqm		1800.00	18000.00	1600.00	16000.00
8.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	2000.00	Kg.		80.00	160000.00	75.00	150000.00
9.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	15100.00	Kg.		85.00	1283500.00	87.00	1313700.00
10.00	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	6.00	Cum		9890.00	59340.00	10000.00	60000.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	M/S. S.R.ENTERPRISE(GSTN-NA)		Sanjib Saha(GSTN-19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
11.00	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood 35 mm thick shutters	15.00	Sqm		4435.00	66525.00	3500.00	52500.00
12.00	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick Second class teak wood	12.00	Sqm		3345.00	40140.00	3500.00	42000.00
13.00	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick Float glass panes 5.0 mm thick glass panes (weight not less than 12.5 kg per sqm)	5.00	Sqm		750.00	3750.00	800.00	4000.00
14.00	Providing and fixing chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete 20 mm dia	15.00	Mtr.		375.00	5625.00	600.00	9000.00
15.00	Providing and fixing bright finished brass butt hinges with necessary screws etc. complete : 100x85x5.5 mm (heavy type)	25.00	Each		210.00	5250.00	200.00	5000.00
16.00	Providing and fixing bright finished brass door latch with necessary screws etc. complete : 250x16x5 mm	12.00	Each		420.00	5040.00	300.00	3600.00
17.00	Providing and fixing bright finished brass handles with screws etc. complete: 125 mm	24.00	Each		215.00	5160.00	225.00	5400.00
18.00	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete :150x10 mm	12.00	Each		310.00	3720.00	250.00	3000.00
19.00	Extra for providing frosted glass panes 4 mm thick instead of ordinary float glass panes 4 mm thick in doors, windows and clerestory window shutters. (Area of opening for glass panes excluding portion inside rebate shall be measured).	10.00	Sqm		810.00	8100.00	750.00	7500.00
20.00	Providing and fixing chromium plated brass 100 mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete.	12.00	Each		655.00	7860.00	800.00	9600.00
21.00	Providing and fixing chromium plated brass 50 mm cupboard or wardrobe knobs with nuts complete.	24.00	Each		115.00	2760.00	100.00	2400.00
22.00	Providing and fixing chromium plated brass handles with necessary screws etc. complete:75 mm	48.00	Each		165.00	7920.00	160.00	7680.00
23.00	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	12.00	Each		830.00	9960.00	800.00	9600.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estima ted Rate	M/S. S.R.ENTERPRISE(GSTN- NA)		Sanjib Saha(GSTN- 19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
24.00	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	30.00	Cum		135.00	4050.00	100.00	3000.00
25.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size	45.00	Cum		5100.00	229500.00	4400.00	198000.00
26.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	20.00	Cum		5200.00	104000.00	5900.00	118000.00
27.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	2400.00	Kg.		79.00	189600.00	72.00	172800.00
28.00	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	300.00	Sqm		475.00	142500.00	500.00	150000.00
29.00	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter (600 mm over all girth)	60.00	Mtr.		240.00	14400.00	360.00	21600.00
30.00	Extra for providing and fixing wind ties of 40x 6 mm flat iron section.	160.00	Mtr.		85.00	13600.00	40.00	6400.00
31.00	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete On steel work	300.00	Sqm		81.00	24300.00	85.00	25500.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	M/S. S.R.ENTERPRISE(GSTN-NA)		Sanjib Saha(GSTN-19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
32.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	80.00	Sqm		590.00	47200.00	800.00	64000.00
33.00	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	2.00	Cum		5700.00	11400.00	7000.00	14000.00
34.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size)	65.00	Cum		4850.00	315250.00	5200.00	338000.00
35.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	3.00	Cum		750.00	2250.00	800.00	2400.00
36.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	3.00	Cum		205.00	615.00	200.00	600.00
37.00	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	12.00	Each		175.00	2100.00	200.00	2400.00
38.00	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	35.00	Sqm		150.00	5250.00	170.00	5950.00
39.00	Polishing on wood work with ready mixed wax polish of approved brand and manufacture : New work	80.00	Sqm		110.00	8800.00	80.00	6400.00
40.00	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	300.00	Sqm		70.00	21000.00	60.00	18000.00
41.00	Providing and fixing beveled edge mirror of superior glass (min 6mm thickness of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete	15.00	Sqm		690.00	10350.00	1000.00	15000.00

SCHEDULE OF WORK / ITEM(S)					L 1 Bidder		L 2 Bidder	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estima ted Rate	M/S. S.R.ENTERPRISE(GSTN- NA)		Sanjib Saha(GSTN- 19ALGPS1804B1ZD)	
					Rate	Amount	Rate	Amount
42.00	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Dark shade pigment using ordinary cement	350.00	Sqm		600.00	210000.00	700.00	245000.00
43.00	Consultancy charges for providing detailed structural design and drawings of roof truss and footings, beam, column to support profile sheet including vetting from IIT, NIT, or any Govt. Engineering Colleges. (3 sets of each approved drawings by AAI are to be submitted.)	1.00	Job		25000.00	25000.00	20000.00	20000.00
Total in Figures						4670355.00		4779960.00

Lowest Amount Quoted BY: M/S. S.R.ENTERPRISE(4670355.00)

Handwritten signature
24.03.2022

Signature Not Verified

Digitally signed by SWAPAN KUMAR
KARMAKAR
Date: 2022.08.12 13:53:11 IST
Location: eProcurement System for Central
PSUs