



संदर्भ सं:भा.वि.प्रा./प.क्षे./मुंबई/ए.प्र.का.भ./सहा.मप्र(अभि.-वि.)/एम डब्लू-02/2022-23/241 दि:29.04.2022

स्पीड पोस्ट

सेवा में,

मेसर्स आर्क पावर सोल्यूशन्स प्रा. लिमिटेड,
नं.62, ग्राउंड फ्लोर, 15वां 'ए' क्रॉस, 6वां मेन,
मल्लेश्वरम, बेंगलूर - 560 055 (कर्नाटका)
ई-मेल / e-mail : vijaykumar@arkpower.co.in; ps@arkpower.co.in;

To,

M/s. ARK Power Solutions Pvt. Ltd.,
No. 62, Ground floor, 15th 'A' Cross, 6th Main,
Malleshwaram, Bangalore - 560 055 (Karnataka)

विषय : एटीसी स्काई टॉवर, न्यू एयरपोर्ट कॉलोनी और एकीकृत परिचालन कार्यालय भवन,
मुंबई के पावर हाउस में स्थापित एचटी पैनल वीसीबी, एसीबी और ट्रांसफार्मर की
सर्विसिंग और परीक्षण।

Subject : Servicing and testing of HT Panel VCBs, ACBs & Transformer installed at Power
House of ATC Sky Tower, New Airport Colony and Integrated Operational Offices
Building, Mumbai.

संदर्भ : 1) निविदा आई.डी. संख्या - 2022_AAI_107173_1
2) आपकी ई-निविदा दिनांक - 01/04/2022

महोदय / Sir,

1. ऊपर उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दरों पर कुल राशि रु.3,56,200.00 (रुपये तीन लाख छप्पन हजार दो सौ मात्र) (जी.एस.टी. रहित) के लिए, जो कि ई-निविदा की अनुमानित लागत राशि रु.3,83,720.00 (जी.एस.टी. रहित) से 7.17% नीचे है, स्वीकृत की जाती है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs.3,56,200.00 (Rupees Three Lakh Fifty Six Thousand Two Hundred Only) (excluding GST), which is 7.17% below the estimated cost put to E-tender of Rs.3,83,720.00 (excluding GST).

2. सहा. महाप्रबंधक (अभि.-वि.), भाविप्रा, क्षेत्रीय मुख्यालय, पश्चिमी क्षेत्र, मुंबई कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामे पर हस्ताक्षर करने एवं करारनामे को पूरा करने के लिए दिनांक - 23/05/2022 तक सहा. महाप्रबंधक (अभि.-वि.), भाविप्रा, क्षेत्रीय मुख्यालय, पश्चिमी क्षेत्र, मुंबई के कार्यालय में उपस्थित हो। ठेके का करारनामा रु.100/- (रुपये सौ मात्र) के नोनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asst. Gen. Manager (E-E), AAI, RHQ-WR, Mumbai shall be the Engineer-In-Charge of the work. You are requested to attend the office of Asst. Gen. Manager (E-E), AAI, RHQ-WR, Mumbai by 23/05/2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred Only) and the cost of stamp paper shall be borne by you.

जारी --/Contd. --



अनवरत पृष्ठ / Continuation sheet..

3. आपकी ई-निविदा के साथ प्राप्त धरोहर राशि रु.00.00 संविदा दस्तावेज के पृष्ठ 16 पर दी गई धारा 1(ए) की शर्त के अनुसार जमानत राशि में परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि की बकाया रु.35,620/- (रुपये पैंतीस हजार छह सौ बीस मात्र) जमा करवायें, अन्यथा ठेके के दस्तावेज पृष्ठ 16 पर दी गई धारा 1(ए) की शर्त के अनुसार इसे आप के चालू बिलों में से काट लिया जायेगा।

The earnest money amount of Rs.00.00 received along with your E-tender will be treated and converted as part of Security Deposit as per condition of Clause no 1(a) on page 16 of contract document. Please deposit Rs.35,620.00 (Rupees Thirty Five Thousand Six Hundred Twenty Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1 (a) on page 16 of the Contract Document.

4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केंद्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहा.प्रबंधक (अभि.-वि.), भाविप्रा, क्षेत्रीय मुख्यालय, पश्चिमी क्षेत्र, मुंबई से मिलें, जो आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. Manager (E-E), AAI, RHQ-WR, Mumbai immediately who will arrange to hand over the site to you.

6. कृपया नोट कर ले कि काम करने का अनुमत समय 1 (एक) साल रहेगा और वह इस पत्र के जारी होने के बाद 10वें दिन यानि दिनांक 09.05.2022 से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 1 Year and same shall be reckoned from the 10th day after issue of this letter i.e. from 09.05.2022.

7. इस ठेके के संबंध में आगे कोई भी पत्राचार सामान्यतः प्रभारी अभियंता के पते किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

जारी --/Contd. --



8. कृपया स्वीकृति की पावती दें और निशानी के रूप में इस पत्र के साथ संलग्न प्रतिलिपि पर हस्तक्षर कर अधोहस्तक्षरी को वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

धन्यवाद,

भवदीय

(Handwritten signature)
29.04.2022

(नंदकुमार बा.कुंडले)

(NANDKUMAR B. KUNDALE)

सहा. महाप्रबंधक (अभि.-वि.)

Asst. Gen. Manager (Engg.-Elect.)

भाविप्रा अध्यक्ष की ओर से,

On behalf of Chairman, AAI

संलग्नक -

1. मात्रा की अनुसूची / Schedule of Quantity - 01 (एक) पृष्ठ / Page

प्रतिलिपि:-

1. मुख्य आयुक्त आयुक्त (टी डी एस), 10वीं मंज़ील, श्रीमति के जी मित्तल आयुर्वेदिक प्रचार संस्था बिल्डिंग, चर्नी रोड (पश्चिम), मुंबई - 400 002.
2. श्रम आयुक्त (बाह्य), श्रम रक्षा भवन, शिवश्रुष्टि रोड, पूर्वी द्रुतगति महामार्ग, सायन, मुंबई - 400 022.
3. आयुक्तालय, बिक्री कर, माझगाव, मुंबई 400 010.
4. जी एस टी, मुंबई आयुक्तालय, नया केंद्रीय आबकारी भवन, 115, महर्षि कर्वे रोड, चर्चगेट, मुंबई-400 020.
5. क्षेत्रीय भविष्य निर्वाह निधि आयुक्त, 341, भविष्य निधि भवन, पश्चिमी द्रुतगति महामार्ग, बांद्रा (पूर्व), मुंबई - 400 051.

सहा. महाप्रबंधक (अभि.-वि.)
Asst. Gen. Manager (Engg.-Elect.)

मात्रा की अनुसूची / SCHEDULE OF QUANTITY

विषय : एटीसी स्काई टॉवर , न्यू एयरपोर्ट कॉलोनी और एकीकृत परिचालन कार्यालय भवन , मुंबई के पावर हाउस में स्थापित एचटी पैनल वीसीबी , एसीबी और ट्रांसफार्मर की सर्विसिंग और परीक्षण।

Subject : Servicing and testing of HT Panel VCBs, ACBs & Transformer installed at Power House of ATC Sky Tower, New Airport Colony and Integrated Operational Offices Building, Mumbai.

क्र. सं.	विवरण Description of Item	मात्रा Qty.	इकाई Unit	दर (रु.) Rate (Rs.)	राशि (रु.) Amount(Rs.)
1.00	SH-I : OVERHAULING /SERVICING (LOCATION : ATC SKY TOWER, MUMBAI)				
1.01	Servicing and testing of following 11 KV, HT Panels including Overhauling/Servicing of all VCBs, maintenance of complete HT panel including checking all operational mechanisms, functions, positions, tripping actions, calibration of protective relays and checking their proper operation by secondary current injection technique and submitting the test reports accordingly etc. complete as required. Incomer Panel:- 630A, TP VCB :- 03 Nos Outgoing Panel:- 630A, TP VCB :- 03 Nos Bus Coupler :-630A, TP VCB 02 Nos Make & Model : L&T-EBG & EDO type	1	Job	40,000.00	40,000.00
1.02	Overhauling /servicing of following L& T make 415V electrical draw out type ACBs (MODEL -C Power) integrated in Main LT Panel & AMF panel including checking all operational mechanisms, functions, positions, tripping actions as per OEM guidelines & submitting test reports accordingly etc. complete as required. 1600 Amp, FP (Microprocessor Based Release - SR186)	7	Job	4,500.00	31,500.00
1.03	Overhauling /servicing of following L& T make 415V electrical draw out type ACBs (MODEL -C Power) integrated in Main LT Panel & AMF panel including checking all operational mechanisms, functions, positions, tripping actions as per OEM guidelines & submitting test reports accordingly etc. complete as required. 1600 Amp, TPN (Microprocessor Based Release - SR186)	2	Job	4,500.00	9,000.00
1.04	Servicing & Testing of following 11/0.433 KV, Dry type cast resin transformers of 1000 KVA, Kirloskar Make by carrying out preventive maintenance activity of transformer as per OEM recommendations to keep the transformer in serviceable condition. Work includes opening the complete enclosure, bus bars, HT & LT side boxes, cable etc. checking of all the safety equipment's, cleaning, servicing & Testing and submission of service reports accordingly after completion of the work as per the requirement.	2	Job	12,000.00	24,000.00

क्र. सं.	विवरण Description of Item	मात्रा Qty.	इकाई Unit	दर (रु.) Rate (Rs.)	राशि (रु.) Amount(Rs.)
2.00	LOCATION : INTEGRATED OPERATIONAL OFFICES BUILDING, MUMBAI				
2.01	Servicing and testing of following 11 KV, HT Panels including Overhauling/Servicing of all VCBs, maintenance of complete HT panel including checking all operational mechanisms, functions, positions, tripping actions, calibration of protective relays and checking their proper operation by secondary current injection technique and submitting the test reports accordingly etc. complete as required. Incomer Panel:- 630A, TP VCB :- 01 Nos Outgoing Panel:- 630A, TP VCB :- 03 Nos Make & Model : Schneider & HVX-X type	1	Job	24,000.00	24,000.00
2.02	Overhauling /servicing of following L&T make 415V electrical draw out type ACB (MODEL -U-power Omega) integrated in Main PCC Panel, APFC panel & synchronizing panel including checking all operational mechanisms, functions, positions, tripping actions as per OEMs guidelines & submitting test report accordingly etc. complete as required. 2500 Amp, FP (Matrix releases - MTX 3.5)	5	Job	4,500.00	22,500.00
2.03	Overhauling /servicing of following L&T make 415V electrical draw out type ACB (MODEL -U-power Omega) integrated in Main PCC Panel, APFC panel & synchronizing panel including checking all operational mechanisms, functions, positions, tripping actions as per OEMs guidelines & submitting test report accordingly etc. complete as required. 1600 Amp, TP, (Matrix releases - MTX 3.5)	3	Job	4,500.00	13,500.00
2.04	Overhauling /servicing of following L&T make 415V electrical draw out type ACB (MODEL -U-power Omega) integrated in Main PCC Panel, APFC panel & synchronizing panel including checking all operational mechanisms, functions, positions, tripping actions as per OEMs guidelines & submitting test report accordingly etc. complete as required. 1250 Amp, TP, (Matrix releases - MTX 3.5)	2	Job	4,500.00	9,000.00
2.05	Overhauling /servicing of following L&T make 415V electrical draw out type ACB (MODEL -U-power Omega) integrated in Main PCC Panel, APFC panel & synchronizing panel including checking all operational mechanisms, functions, positions, tripping actions as per OEMs guidelines & submitting test report accordingly etc. complete as required. 800A, TP, (Matrix releases - MTX 3.5)	3	Job	4,500.00	13,500.00

क्र. सं.	विवरण Description of Item	मात्रा Qty.	इकाई Unit	दर (रु.) Rate (Rs.)	राशि (रु.) Amount(Rs.)
2.06	Servicing & Testing of following 11/0.433 KV, Dry type cast resin transformers of 1500 KVA, VoltAmp Make by carrying out preventive maintenance activity of transformer as per OEM recommendations to keep the transformer in serviceable condition. Work includes opening the complete enclosure, bus bars, HT & LT side boxes, cable etc. checking of all the safety equipment's, cleaning, servicing & Testing and submission of service reports accordingly after completion of the work as per the requirement.	2	Job	12,000.00	24,000.00
3.0	LOCATION : NEW AIRPORT COLONY, MUMBAI				
3.01	Servicing and testing of following 11 KV, HT Panels including Overhauling/Servicing of all VCBs, maintenance of complete HT panel including checking all operational mechanisms, functions, positions, tripping actions, calibration of protective relays and checking their proper operation by secondary current injection technique and submitting the test reports accordingly etc. complete as required. For New Airport Colony Incomer Panel:-800A, TP VCB :- 01 Nos Outgoing Panel:-800A, TP VCB :- 04 Nos Make & Model : ABB & VD4	1	Job	30,000.00	30,000.00
3.02	Servicing and testing of following 11 KV, HT Panels including Overhauling/Servicing of all VCBs, maintenance of complete HT panel including checking all operational mechanisms, functions, positions, tripping actions, calibration of protective relays and checking their proper operation by secondary current injection technique and submitting the test reports accordingly etc. complete as required. For Porta Cabin Incomer Panel:- 800A, TP VCB :- 01 Nos Make & Model : ABB & VD4	1	Job	6,000.00	6,000.00
3.03	Overhauling /servicing of following L& T make 415V electrical draw out type ACBs (MODEL-C Power) integrated in Main LT Panel & AMF panel including checking all operational mechanisms, functions, positions, tripping actions as per OEM guidelines & submitting test reports accordingly etc. complete as required. 1250 Amp, TP (Thermo-magnetic Release Type - DN1)	1	Job	4,500.00	4,500.00

क्र. सं.	विवरण Description of Item	मात्रा Qty.	इकाई Unit	दर (रु.) Rate (Rs.)	राशि (रु.) Amount(Rs.)
3.04	Overhauling /servicing of following L& T make 415V electrical draw out type ACBs (MODEL-C Power) integrated in Main LT Panel & AMF panel including checking all operational mechanisms, functions, positions, tripping actions as per OEM guidelines & submitting test reports accordingly etc. complete as required. 1000 Amp, TP (Thermo-magnetic Release Type - DN1)	1	Job	4,500.00	4,500.00
3.05	Overhauling /servicing of following L& T make 415V electrical draw out type ACBs (MODEL-C Power) integrated in Main LT Panel & AMF panel including checking all operational mechanisms, functions, positions, tripping actions as per OEM guidelines & submitting test reports accordingly etc. complete as required. 800 Amp, TP (Thermo-magnetic Release Type - DN1)	1	Job	4,500.00	4,500.00
3.06	Overhauling /servicing of following L&T make 415V electrical draw out type ACB (MODEL-U power Omega) integrated in Main PCC Panel, APFC panel & synchronizing panel including checking all operational mechanisms, functions, positions, tripping actions as per OEMs guidelines & submitting test report accordingly etc. complete as required. 1600 Amp, FP, (Matrix releases - MTX 3.5)	3	Job	4,500.00	13,500.00
3.07	Servicing & Testing of following 11/0.433 KV, Dry type cast resin transformers of 1000 KVA, Kirloskar Make by carrying out preventive maintenance activity of transformer as per OEM recommendations to keep the transformer in serviceable condition. Work includes opening the complete enclosure, bus bars, HT & LT side boxes, cable etc. checking of all the safety equipment's, cleaning, servicing & Testing and submission of service reports accordingly after completion of the work as per the requirement.	2	Job	12,000.00	24,000.00
3.08	Servicing & Testing of 11 KV/ 433 Volts, 1000 KVA of Oil Transformers including checking & tightening of HT/LT cable termination, operation of tap changer, testing of transformer oil i/c acidity test, insulation resistance of transformer. The job includes complete filtration of transformer oil and top-up of oil to maintain the withstand capacity of oil minimum 40KV at least for two minutes, checking of all safety equipment and submission of test reports etc. complete as required.	1	Job	20,000.00	20,000.00

क्र. सं.	विवरण Description of Item	मात्रा Qty.	इकाई Unit	दर (रु.) Rate (Rs.)	राशि (रु.) Amount(Rs.)
4.0	SH-II: Supply of Spares				
4.01	Service position micro-switch - (C 6) (Make: L&T)	3	Nos	2,500.00	7,500.00
4.02	Micro-switch for Releases (C1) (Make: L&T)	2	Nos	3,300.00	6,600.00
4.03	Test or isolated position micro-switch - (C 8) (Make: L&T)	1	Nos	2,500.00	2,500.00
4.04	ACB door bezels (Make: L&T)	9	Nos	2,400.00	21,600.00
				कुल (रु.)	3,56,200.00

(रुपये तीन लाख छप्पन हजार दो सौ मात्र)

नंदकुमार बा. कुंडले
29.04.2022

(नंदकुमार बा. कुंडले)
सहा. महाप्रबंधक (अभि.-वि.)