



भारतीय विमानपत्तन प्राधिकरण
(मिनी रत्न – श्रेणी-1सार्वजनिक क्षेत्र का उद्यम)
Airports Authority of India
(A Miniratna- Category-I Public Sector Enterprise)

Ref: AAI/BZ/ENGG (E)/Jt.GM/CW/WO-01/2022-23/387

Dated: 13.05.2022

M/s. GLYPTIC,
Raipur, Bhita,
Burdwan - 713102
West Bengal.
E-mail: glyptic.sales@gmail.com

Name of Work: - Providing Fire Detection and Alarm System for I.T.B and other ancillary buildings at Vijayawada Airport.

Ref: Your Price Bid (**Tender ID No. 2022_AAI_107939_1**)

Dear Sir,

1. Your e-tender for the above mentioned work is hereby accepted by the Competent Authority on behalf of the Chairman, AAI at the item rates quoted by you, for an amount of Rs. **23,02,679.00** (Rupees Twenty Three Lakhs Two Thousand Six Hundred and Seventy Nine Only) Excluding GST which is **16.29%** Below the Justified Cost of **Rs.27,50,654.00** (Rupees Twenty Seven Lakhs Fifty Thousand Six Hundred and Fifty Four only).
2. The Joint General Manager [Engg-E], Airports Authority of India, Vijayawada Airport, Vijayawada-521 102 is the Engineer-In-Charge of the work. You are requested to depute your accredited representative empowered to sign the contract agreement on your behalf to the office of the Jt. General Manager [Engg-E] AAI, Vijayawada Airport by **23/05/2022** to sign and complete the agreement. The contract agreement shall be executed on a Non-Judicial stamp paper **Andhra Pradesh** of value Rs. 100/- and the cost of the stamp paper shall be borne by you.
3. Please Deposit amount of Rs. **2,30,268/-** (Rupees Two Lakhs Thirty Thousand Two Hundred and Sixty Eight Only) towards Security Deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your bill as per relevant Clause No.1A of GCC.
4. You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central Rules, 1971, Minimum Wages Act 1948, Employees Provident Fund & Misc. Provisions Act 1952, ESI Act 1948 and Rules thereof Central/ State Governments.

(Contd....2/-



भारतीय विमानपत्तन प्राधिकरण

(मिनी रत्न – श्रेणी-1सार्वजनिक क्षेत्र का उद्यम)

Airports Authority of India


(A Miniratna- Category-I Public Sector Enterprise)

2

5. You are also directed to contact the Sr. Manager [Engg-E], AAI, and Vijayawada Airport immediately who will arrange to handover the site to you. Please note that the time allowed for completion of the work is **04** (Four) Months i.e. with effect from **30/05/2022 to 29/09/2022**.
6. Your offer for this work shall form part of the agreement along with this award letter and all the technical particulars, undertaking uploaded in the folder. All other terms & conditions shall be as per NIT.
7. Any further correspondence in connection with the contract should normally be addressed to The Jt. G.M. Engg (E), AAI, Vijayawada Airport, Vijayawada – 521 102.
8. Airports Authority of India, Vijayawada Airport(A.P) GST No: **37AAACA6412D1Z7** shall be included in all invoices generated by the Agency.
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of your acceptance.

Thanking you,

Yours faithfully


(P. V. Rama Rao)
Jt. General Manager [Engg-E]
AAI, Vijayawada Airport

Encls: (Schedule of Quantities) Page - 1

SCHEDULE OF QUANTITIES

Name of Work: Providing Fire Detection and Alarm System for I.T.B and other ancillary buildings at Vijayawada Airport.

Item No.	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
1	Supply, Installation, Testing & Commissioning of UL / EN listed (latest version) Modular Microprocessor based expandable intelligent Addressable Type Fire Alarm Control Panel of following loops, with minimum 320 character graphics / LCD display with touch screen or other keypad and minimum 4000 events history log in the non volatile memory (EPROM) ,The panel should be equipped with loop capacity to take minimum 240 intelligent addressable detectors/ devices (In any combination) in one loop. 230 volts, 50 Hz AC power supply, automatic battery charger, 24 volts sealed maintenance free lead acid batteries sufficient for 2 hours normal working and then be capable of operating the system for 30 minutes during an emergency / fault conditions along with battery stand as required. The panel shall have facility for seamless integration. The panel shall be compatible for Building Management System with open protocol BACNET / MODBUS / Auto Dialler etc. as per specification, complete as required. a) Four Loop Panel	1.00	Each	252580.00	252580.00
2	Supply, Installation, Testing & Commissioning of UL / EN listed (latest version) Repeater Panel shall provide pin point location of the fault or fire event and should Provide complete control of system at remote location. The panel shall have a 320 character graphics / LCD display with touch screen or other keypad.	3.00	Each	54526.00	163578.00
3	Supplying, installation, testing & commissioning of intelligent analog addressable Smoke detector complete with mounting base complete as required.	350.00	Each	2406.00	842100.00
4	Supplying, installation, testing & commissioning of response indicator on surface/ recessed MS Box having two LED, metallic cover complete with all connections etc as required.	120.00	Each	217.00	26040.00
5	Supplying, installation, testing & commissioning of fault isolator complete with base as required.	15.00	Each	2675.00	40125.00
6	Supplying, installation, testing & commissioning of intelligent addressable thermal detector with rate of rise cum fixed temperature thermistor complete with base as required.	10.00	Each	2310.00	23100.00
7	Supplying, installation, testing & commissioning of addressable fire control module complete as required.	1.00	Each	2675.00	2675.00
8	Supplying, installation, testing & commissioning of addressable manual call point complete as required.	17.00	Each	2675.00	45475.00
9	Supplying, installation, testing & commissioning of addressable horn cum strobe complete as required.	17.00	Each	4900.00	83300.00
10	Supplying & laying of 2Cx1.5 Sq.mm fire alarm armoured cable, 600/1000V rated with annealed copper conductor having XLPE insulation, steel wire armouring & FRLSH outer sheath on existing wall / in pipe / surface etc., complete as required.	5100.00	Mtr	160.00	816000.00
11	SITC of Auto Dialler system suitable to connect landline connection etc as required.	1.00	Each	7706.00	7706.00
				Total of Rs.	2302679.00

(Rupees Twenty Three Lakhs Two Thousand Six Hundred and Seventy Nine Only)

*Note: GST Extra as applicable


(P. V. RAMA RAO)
 Jt. General Manager (Engg & Const.)
 AAI, Vijayawada Airport.