



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

भाविप्रा/भोपाल/अभि.सि./सीडब्ल्यू-07/पेरीमीटर रोड/2022-23/ 423 (1-9) दिनांक : 25.05.2022

सेवार्थ/ To,

मेसर्स एस एस कन्स्ट्रक्शन

77 सावन नगर हलालपुरा

लालघाटी हुजूर भोपाल (म.प्र.)

मोबाइल :- 7415562195

ईमेल - ssconstructionbpl25@gmail.com

M/s S.S. CONSTRUCTION

77 SAVAN NAGAR HALALPURA

LALGHATI HUZUR BHOPAL (M P) 462032

Mob :- 7415562195

email :- ssconstructionbpl25@gmail.com

विषय :- राजा भोज विमानतल, भोपाल के विमान परिचालन क्षेत्र में नए अग्निशमन वाहन के सुरचि परिचालन हेतु विभिन्न जगह पेरीमीटर रोड का चौड़ीकरण तथा रनवे से पेरीमीटर रोड तक नए लिंक रोड का निर्माण कार्य

Subject:- Widening of Perimeter Road at various locations and construction of New Link Roads from Runway upto the perimeter road for easy maneuvering of Fire Vehicles at Raja Bhoj Airport, Bhopal.

संदर्भ:- आपकी निविदा संख्या 2022_AAI_109830_1 दिनांक 02/05/2022

Ref: Your E-tender No. 2022_AAI_109830_1 dated 02/05/2022

महोदय/Dear Sir (S),

- अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त वर्णित कार्य का आपकी मद मूल्यों पर आधारित ई-निविदा राशि ₹4,41,98,955.00 (रुपये चार करोड़ इकतालीस लाख अठानवे हजार नौ सौ पचपन मात्र) (बिना जीएसटी) तथा ₹5,21,54,767.00 (18% जीएसटी जोड़कर) होगी, जो कि अनुमानित लागत ₹9,30,56,000.00/- (रुपये नौ करोड़ तीस लाख छप्पन हजार मात्र) (बिना जीएसटी) तथा ₹10,98,06,080.00/- (रुपये दस करोड़ अठानवे लाख छह हजार अस्सी मात्र) (18% जीएसटी जोड़कर) से (-) 52.50% (बावन दशमलव पाच शून्य प्रतिशत) कम हैं, स्वीकृत की जाती हैं।
Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to ₹4,41,98,955.00/- (Rupees Four crore Forty one Lakh Ninety Eight Thousand Nine Hundred Fifty Five Only) (without GST) and Rs 5,21,54,767.00/- (Rupees Five Crore Twenty One Lakh Fifty Four Thousand Seven Hundred Sixty Seven only) (including GST @18%) which is (-) 52.50 % (Fifty Two point Five Zero Percent) below the estimated cost put to tender i.e., ₹9,30,56,000.00/- (Rupees Nine Crore Thirty Lakh Fifty Six Thousand Only) without GST and ₹10,98,06,080.00/- (Rupees Ten Crore Ninety Eight Lakh Six Thousand Eighty only) including GST @18%.
- संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल) भाविप्रा राजा भोज एयरपोर्ट भोपाल इस कार्य के इंजीनियर प्रभारी होंगे। आपसे अनुरोध है कि आप संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल) कार्यालय भाविप्रा राजा भोज एयरपोर्ट भोपाल में दिनांक 08/06/2022 तक उपस्थित होकर करार नामे पर हस्ताक्षर कर पूरा करें। यह करारनामा ₹500.00 (पाँच सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जायेगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।
Jt.GM Engg (Civil), AAI, Raja Bhoj Airport, Bhopal, shall be the Engineer-in-Charge of the work. You are requested to attend the office of Jt.GM Engg (Civil), AAI Raja Bhoj Airport, Bhopal by 08.06.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value ₹500.00 (Rupees Five Hundred only) and the cost of the stamp paper shall be borne by you.

पृष्ठ सं/page no: 01

- 3- आपके निविदा के साथ प्राप्त धरोहर राशि **₹18,61,120.00 (रुपये अठारह लाख इकसठ हजार एक सो बीस मात्र)** को अनुबंध दस्तावेज के पृष्ठ संख्या जी.जी.-1 पर एन आई टी क्लॉज संख्या-8 के अनुसार सुरक्षा निधि के रूप में माना जाएगा और जमानत राशि में परिवर्तित किया जाएगा। इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर शेष सुरक्षा निधि राशि **₹ 3,48,828/- (केवल तीन लाख अड़तालीस हजार आठ सौ अड़्ठाइस रुपये)** जमा करें। असफल होने पर अनुबंध की पृष्ठ संख्या जी.सी.सी. - 16 पर क्लॉज संख्या 1 (अ) की शर्तों के अनुसार सुरक्षा निधि राशि को बिलों से काटा जायेगा।

The earnest money amount of **Rs 18,61,120.00 (Rupees Eighteen Lakh sixty one thousand one hundred twenty Only)** received along with your tender will be treated and converted as part of security deposit as per NIT Clause No 8 on page no GG-1 of Contract Document. Please deposit balance amount of **₹ 3,48,828.00/- (Rupees Three Lakh Forty Eight Thousand Eight Hundred Twenty Eight Only)** towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your R/A bills as per condition of Clause no 1 A at page no GCC -16 of contract document.

- 4- संविदा करार पर हस्ताक्षर होने के 30 दिनों के भीतर आप निविदा दस्तावेज अनुबंध की शर्त संख्या - 1 पृष्ठ संख्या GCC-15 के अनुसार **रुपए ₹13,25,969.00 (तेरह लाख पच्चीस हजार नौ सो उनहतर रुपये)** की निष्पादन पृतिभूती, भारतीय विमानपत्तन प्राधिकरण, के पास जमा करेंगे। यह धन राशि निविदा दस्तावेज के पृष्ठ संख्या GCC-108,109,110 पर सलग्न प्रपत्र पर बैंक गारंटी के रूप में जमा की जाएगी।

Within 30 days of issue of this letter, you shall submit to AAI, a Performance Guarantee for an amount of **Rs. 13,25,969.00 (Rupees Thirteen Lakh Twenty Five thousand Nine hundred Sixty Nine Only)** in the form of Bank Guarantee as per GCC clause 1 on page no – GCC-15 of the Tender Document, on the proforma appended at page no GCC-108,109,110 of the Tender Document.

- 5- आपसे निवेदन है कि आप विभिन्न लागू वैधानिक अधिनियमन जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारी राज्य बीमा (ESI) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्युनतम मजदुरी अधिनियम, 1948, मजदुरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगत नियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/परिवर्तित किया जाते हैं। उक्त वैधानिक अधिनियम व प्रावधानों का नियमित अनुपालन व इनके अंतर्गत सारी विधिक बाध्यताओं का पूर्ण प्रेक्षण आपका एकल दायित्व होगा।

You are requested to comply with the provisions under various applicable statutory enactments including the employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment &



conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, instructions etc. issued/enforced from time to time. It shall be your sole liability to abide with and fully observing the legal obligations under the aforesaid statutory acts and provisions.

- 6- आपको निर्देश दिया जाता है कि आप तुरंत सहायक महाप्रबंधक (सिविल)से संपर्क करें जो आपको साइट को सौंपने की व्यवस्था करेंगे।

You are also directed to contact AGM. Engg (Civil) immediately who will arrange to hand over the site to you.

- 7- कृपया ध्यान दें कि काम करने का अनुमानित समय **12(बारह) माह** हैं जो कि इस पत्र को जारी करने के **दसवे दिन** से मान्य होगा।

Please note that the time allowed for carrying out the work shall be **12 (Twelve) Months** and same shall be reckoned from the 10th day after issue of this letter.

- 8- यह संदर्भित पत्र अनुबंध का एक हिस्सा होगा।

This letter under reference shall form part of Agreement

- 9- इस अनुबंध के संबंध में आगे का कोई भी पत्राचार प्रभारी अभियंता के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.

- 10- कृपया अपनी अभिस्वीकृति भेजे तथा सहमति के लिये डुप्लीकेट कापी, जोकि इस पत्र के साथ संलग्न है, हस्ताक्षर करके अधोहस्ताक्षरी को भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

- 11- यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को ही सही रूप में लिया जाएगा।

In case any discrepancy is found then English version will be taken as correct.

संलग्नक/ Encl.-Schedule 'A'(BOQ)

भवदीय/Yours faithfully

संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल)

Jt.GM (Engineering Civil)

राजा भोज विमानतल भोपाल,

Raja Bhoj Airport, Bhopal

कृते तथा ओर से

For and on behalf of

अध्यक्ष, भाविप्रा,

The Chairman, AAI

मूलप्रति से अतिरिक्त / N.O.O

1. महाप्रबंधक (अभि.-परियोजना),
भारतीय विमानपत्तन प्राधिकरण, जबलपुर हवाई अड्डा, जबलपुर 482005.----- आपकी जानकारी हेतु।
General Manager (Engg-Project),
Airports Authority of India, Jabalpur Airport, Jabalpur-482005----- For Information please
2. क्षेत्रीय श्रम आयुक्त (केन्द्रीय),
निर्माण सदन, सी.जी.ओ. कॉम्प्लेक्स रूम नंबर 306,
तीसरा माला, अरेरा हिल्स, भोपाल-462016.
The Regional Labour Commissioner(Central),
Nirman Sadan. C.G.O. Complex, Room No. 306.
3rd floor, Arera hills Bhopal-462016.
3. क्षेत्रीय भविष्य निधि आयुक्त, मध्यप्रदेश,
भविष्य निधि भवन, 59-अरेरा हिल्स, भोपाल-462011
The Regional Provident Fund Commissioner (M.P.)
Bhavishy Nidhi Bhavan, 59-Arera Hills, Bhopal-462011

आंतरिक/INTERNAL

1. विमानपत्तन निदेशक, भाविप्रा.राजा भोज विमानतल, भोपाल. जानकारी हेतु।
The Airport Director, AAI, Raja Bhoj Airport, Bhopal..... for information please.
2. सहायक महाप्रबंधक - (वित्त) भाविप्रा. राजा भोज विमानतल. भोपाल.
Asstt.GM (Finance), AAI, Raja Bhoj Airport Bhopal.
3. मुख्य सुरक्षा अधिकारी, भाविप्रा, राजा भोज विमानतल, भोपाल पास जारी करने के लिए
Chief Security Officer, AAI, Raja Bhoj Airport Bhopal
4. सहायक महाप्रबंधक (सिविल)/ प्रबंधक (सिविल) भाविप्रा, राजा भोज विमानतल, भोपालआवश्यक कार्यवाही हेतु
AGM (E-C)/Manager (E-C) AAI, Raja Bhoj Airport Bhopalfor necessary action.
5. कार्यालय प्रतिलिपि/ For office copy

संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल)
Jt.GM (Engineering Civil)

SCHEDULE OF WORK / ITEM(S)					
Name of Work: Widening of Perimeter Road at various locations and construction of New Link Roads from Runway upto the perimeter road for easy maneuvering of Fire Vehicles at Raja Bhoj Airport, Bhopal					
Agency - M/s SS Constructions, Bhopal					
Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1	Conducting required soil testing at site and submitting detailed pavement design with section for construction of pavement based on Full running load of Fire Tenders available at Bhopal Airport including vetting of pavement design from approved govt engineering college etc. all complete as per direction and satisfaction of Engineer - In - Charge	1.00	Job	₹ 50,000.00	₹ 50,000.00
2	Excavation for roadwork with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1km.. All kinds of Soil	30103.00	Cum	₹ 75.00	₹ 22,57,725.00
3	Excavation for roadway in hard rock (blasting prohibited) with rock breakers including breaking rock, loading in tippers and disposal within all lifts and lead upto 1000 metres, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections.	225.00	Cum	₹ 120.00	₹ 27,000.00
4	Excavating, supplying and filling of local earth (Excavating within AAI Premises without royalty) by mechanical transport upto a lead of 5.00 Km also including compacting/rolling, making good the undulations and watering of the earth in layers not exceeding 20 cm in trenches, plinth sides of foundation etc. complete as per direction of EIC.	5846.00	Cum	₹ 150.00	₹ 8,76,900.00
5	Construction of embankment or filling of depression with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of MORTH specification table 300-2 upto satisfaction of Engineer-in-charge upto a lead of 2.00 Km.	10920.00	Cum	₹ 120.00	₹ 13,10,400.00
6	Supplying and filling moorum / Good earth obtained from approved quarry for subgrade, embankment, depressions as instructed and in layers not exceeding 20 cm (loose) in depth (or any thickness as approved by the Engineer-in-Charge in case vibratory roller / soil compactor is used) including breaking clods, watering, consolidating each layer with power road roller 8 -10 tonnes weight or vibratory roller / soil compactor of adequate capacity under optimum moisture content condition to give at least 95% of the maximum laboratory dry density (modified Proctor density) as per IS : 2720 (part VIII) complete including leveling, fine dressing to the required grade, camber and slope complete as per MORTH specifications and as directed by the Engineer-in-Charge with all leads and lifts. (The item includes cost of work, payment of necessary royalty, carriage of moorum / suitable earth upto work site for all leads and lifts involved from all sources acquired or arranged by the contractor. Payment shall be made for compacted quantity only.)	8950.00	cum	₹ 70.00	₹ 6,26,500.00
7	Surface dressing of the ground including removing vegetation and in- equalities not exceeding 30 cm deep and disposal of rubbish, within Airport premises as directed bu EIC - All Kinds of Soil	58000.00	Sqm.	₹ 4.00	₹ 2,32,000.00
8	Supplying and stacking at site including all lead and lift - 90mm to 45mm stone aggregate (for soling under paver block or) as directed by E-I-C	200.00	Cum	₹ 700.00	₹ 1,40,000.00
9	Supplying and stacking at site including all lead and lift - stone screening 13.2mm nominal size (for soling / under paver block or) as directed by E-I-C.	140.00	Cum	₹ 700.00	₹ 98,000.00

[Handwritten Signature]

SCHEDULE OF WORK / ITEM(S)					
Name of Work: Widening of Perimeter Road at various locations and construction of New Link Roads from Runway upto the perimeter road for easy maneuvering of Fire Vehicles at Raja Bhoj Airport, Bhopal					
Agency - M/s SS Constructions					
Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
10	Construction of granular sub-base (GSB) by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	6635.00	Cum	₹ 700.00	₹ 46,44,500.00
11	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	4610.00	Cum	₹ 750.00	₹ 34,57,500.00
12	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On bituminous surface @ 0.50 Kg / sqm	4920.00	Sqm.	₹ 15.00	₹ 73,800.00
13	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion On W.B.M / W.M.M. @ 0.4kg/sqm	1000.00	Sqm.	₹ 35.00	₹ 35,000.00
14	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	90.00	Cum	₹ 5,000.00	₹ 4,50,000.00
15	Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per CPWD / AAI specifications and directions of Engineer-in-Charge. - 40 to 100 mm average compacted thickness with bitumen of grade VG-30 prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity. (For tendering purpose VG Bitumen of Grade VG-30 Content shall be taken as @ 5% percentage by weight of total mix and cement filler @ 2% percentage by weight of Aggregate may be assumed. Any surplus Bitumen if used in Job Mix Formula of this item shall be reimbursed on actual basis)	160.00	cum	₹ 5,500.00	₹ 8,80,000.00

SCHEDULE OF WORK / ITEM(S)					
Name of Work: Widening of Perimeter Road at various locations and construction of New Link Roads from Runway upto the perimeter road for easy maneuvering of Fire Vehicles at Raja Bhoj Airport, Bhopal					
Agency - M/s SS Constructions					
Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
16	Providing and laying transparant (1st quality) polythene sheet (separation membrane) 250 microns thick on the base course with overlaps of not less than 100mm both way over the layer of 6mm thick sand complete and as per directions of Engineer-in-charge. Only plan area shall be measured for payment. Cost include laying of 6mm thick layer of sand, overlaps of polythene sheets etc complete.	23910.00	Sqm.	₹ 5.00	₹ 1,19,550.00
17	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in- charge.	1170.00	Cum	₹ 2,800.00	₹ 32,76,000.00
18	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per designmix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer all complete	4640.00	Cum	₹ 4,750.00	₹ 2,20,40,000.00
19	Providing and laying in position bitumen hot sealing compound for expansion/construction joint etc. Using grade 'A' sealing compound.	13790.00	per cm depth per cm width per metre length	₹ 2.00	₹ 27,580.00
20	Providing and laying in position for expansion joint, 25mm thick pre cut Synthetic joint filler board of approved make (HD 100 or equivalent of density 100 kg / cum +/- 10%) conforming to IS:1838 (part 3)-2011, 45 mm from top (to be removed at the time of filling of Silicon sealant), complete as per particular specifications and directions of Engineer-in-charge. (Note: Nothing extra shall be paid for the filler board from top upto the bottom of polyethylene backing rod., Mode of measurement shall be length of joint multiplied by depth of filler board including precut portion.)	280.00	Sqm.	₹ 300.00	₹ 84,000.00

[Handwritten signature]

SCHEDULE OF WORK / ITEM(S)					
Name of Work: Widening of Perimeter Road at various locations and construction of New Link Roads from Runway upto the perimeter road for easy maneuvering of Fire Vehicles at Raja Bhoj Airport, Bhopal					
Agency - M/s SS Constructions					
Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
21	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	800.00	Cum	₹ 2,600.00	₹ 20,80,000.00
22	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	2.00	Cum	₹ 5,000.00	₹ 10,000.00
23	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. - In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	3500.00	Kg.	₹ 100.00	₹ 3,50,000.00
24	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of stone dust, compacting and proper embedding/laying of inter locking paver blocks into the bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. (a) 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	750.00	Sqm.	₹ 600.00	₹ 4,50,000.00
25	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete -450 mm dia RCC pipes.	100.00	Meter	₹ 1,400.00	₹ 1,40,000.00
26	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete -600 mm dia RCC pipes.	30.00	Meter	₹ 2,000.00	₹ 60,000.00
27	Dry stone pitching average 22.5 cm thick including supply of stones and preparing surface complete.	1150.00	Sqm.	₹ 350.00	₹ 4,02,500.00
				Total (Without GST) =	₹ 4,41,98,955.00

841
25.5.22

Signature Not Verified

Digitally signed by Neera Kumar
Chourasia

Date: 2022.07.05 11:09:54 IST

Location: eProcurement System for Central
PSUs